



DETROIT-UMICH LIBRARY

DEC 14 1961

TECHNOLOGY
DEPARTMENT

THE PRODUCTION ENGINEER

THE JOURNAL OF THE INSTITUTION OF PRODUCTION ENGINEERS

NOVEMBER 1961

THE PRODUCTION ENGINEER

VOL. 40 - NO. 11

PRICE 10/-

NOVEMBER, 1961

CONTENTS

"PHYSICAL REQUIREMENTS OF AUTOMATION" by A. L. Stuchbery, M.I.Mech.E., M.I.Prod.E.	701
"ECONOMIC ASPECTS OF AUTOMATION — INTERNAL TO THE FIRM" by A. A. Jacobsen, M.I.Prod.E.	714
"THE PRODUCTION OF PRESSURE VESSELS IN ALUMINIUM AND ALUMINIUM ALLOYS" by A. Townsend, A.M.I.Mech.E., A.M.I.Prod.E., M.I.E.I., and R. N. Saunders	721
"TRAINING FOR THE EFFICIENT CONTROL OF QUALITY" by J. Holmes, A.M.I.E.I.	733
LETTERS TO THE EDITOR	737
<i>The 1961 Summer School</i> "INTERRELATION OF WORK STUDY, ERGONOMICS, OPERATIONAL RESEARCH AND CYBERNETICS AND THEIR APPLICATION TO PRODUCTION ENGINEERING"	738
MANAGEMENT STUDIES — "ECONOMIC LIFE DETERMINATION"	741
NEWS OF MEMBERS	747
DIARY FOR 1962	749
HAZLETON MEMORIAL LIBRARY—Additions	750

*The Institution of Production Engineers does not accept
responsibility for any statements made or opinions expressed in any
Papers published in the Journal of the Institution*

THE JOURNAL OF
THE INSTITUTION OF
PRODUCTION ENGINEERS

10 Chesterfield Street
Mayfair : London : W.1
Telephone GROsvenor 5254-9

EDITORIAL COMMITTEE

John M. Brice—Chairman
Harold Burke—
President of the Institution
R. H. S. Turner—
Chairman of Council
Dr. G. S. Brogan
Dr. E. N. Corlett
Dr. S. Eilon
J. L. Gwyther
B. W. Jenney
H. Peter Jost
J. C. Z. Martin
R. E. Mills
M. J. Sargeaunt
B. E. Stokes

EDITOR

M. S. C. Bremner

SECRETARY OF THE INSTITUTION

W. F. S. Woodford

H

C



This un
boring m
rolled.
milling
facing ca

The Op
time sub
is requir
and reali
engaged
There is
Opticut
speeds,
readily
The Sc
extremel
tric head
absolute
nical str
condition

Write to
which fu

ASCC.B1



12

HEAVY DUTY

PRECISION BORING & MILLING * THE SCHARMANN OPTICUT 'FB 500 C'




This universal and horizontal boring machine is optically controlled. It is also a heavy duty milling machine with a large facing capacity.

The Opticut reduces operating time substantially as far less time is required for spacing, resetting and realigning, particularly when engaged on 180° index boring. There is no guesswork—with the Opticut you see everything—the speeds, feeds and settings are readily visible on the pendant. The Scharmann Opticut is extremely accurate—the concentric headstock suspension ensures absolute stability under mechanical stress and varying thermal conditions.


Write today for Booklet 1704-A which fully describes this machine.


945 CC.81



CHARLES CHURCHILL & COMPANY LIMITED

Coventry Road South Yardley Birmingham 25
Telephone Acocks Green 2281






K9

EDGAR ALLEN'S DIE STEEL

The illustrations show the die and finished product used as a container for an automatic playback tape recorder which is being issued to blind people. The box fits straight over a capstan on the tape deck and close limits have to be maintained. The die is made of Edgar Allen's K9 die steel which has been perfected to meet the need for an inexpensive non-shrinking steel suitable for tools from which the highest accuracy is required. K9 will give long production runs with minimum regrinding. The Die was designed and manufactured by P. & H. Metal Products (Kingston) Limited and has produced many thousands of containers.



EDGAR ALLEN & CO. LIMITED
IMPERIAL STEEL WORKS · SHEFFIELD 9

To **EDGAR ALLEN & CO. LTD., SHEFFIELD, 9**

Please post K9 booklet to :


Name

Position

Firm

Address

TS39/PE



COPPER PLATING

prior to **SELECTIVE HARDENING**

The plant illustrated above has recently been installed in a Midland factory. Upwards of 2,000 components are processed automatically each hour.

Yet another company has turned automatically to Canning

CANNING CO. LTD.

BIRMINGHAM 18
TELEPHONE CENTRAL 8621

LONDON · SHEFFIELD
GLASGOW · BOMBAY
AND ASSOC. CO. IN AUSTRALIA



*For faithful
reproduction
of intricate
profiles*

automatically

*from simple
quickly produced
templates*

*and
reversion to
manual control
at will*

W&B



The application of electronic profile turning and boring equipment to the Webster and Bennett range of vertical boring mills opens up a wide new field of uses for these versatile machines. Although specifically designed for copying applications, when not required the electronic control may be disengaged and the machine operated as a standard machine under mechanical control.

Machine capacities range from 36" to 72" chuck diameter, and machines can be supplied with or without the electronic profiling equipment.

WEBSTER & BENNETT LTD., COVENTRY, ENGLAND

REAMING
TAPPING
DRAWING
DRILLING BORING
FORMING
SCREW CUTTING
THREADING
SAWING
MILLING

ROCOL - FIRST AGAIN!

R.T.D. SPRAY

(R.T.D. COMPOUND IN AEROSOL SPRAY FORM)




**THE FIRST AEROSOL
FOR CUTTING
LUBRICATION!**



This free publication gives performance details, case histories, and technical advice on this unique cutting lubricant. Write for your copy now.

Rocol

ROCOL LIMITED




Dept. Z,
General Buildings, Aldwych, London, W.C.2. Tel: HOLborn 1985
Rocol House, Swillington, Near Leeds. Tel: Garforth 2261.

OILGEAR

"ANY FEED-SPEED PACKS"

PROVIDE YOU WITH:-

- | | |
|--|---|
| SOL "JIC Fail Safe" Solenoid Operated Function Controls | M 125 psi Feed Stabilizing Relief Valve |
| (PV) 0 to 240 cpm or 0 to 950 cpm Radial Piston Pumps | (PF) 2100 cpm or 3280 cpm Traverse Pumps |
| M 1000 psi Feed Pressure Relief Valve | M 300 psi Traverse Pressure Relief Valve |
| COMP Automatic Feed Compensator for Load Variations | M 35 psi System Back Pressure Relief Valve |
| MAN Micrometer Type Fine Feed Adjustment | Flanged Connections; Only Two Pipes Required |
| MAN Screw Type Coarse Feed Adjustment | Auxiliary Test Stations for Gages |



J K TYPE

- Use with a double-acting cylinder and you need only install TWO pipes to complete the fluid power system.
- NO external valves or associated low and high pressure piping required.

YOU NEED OILGEAR!


Weatherley
Oilgear
Limited

HYDRAULICS DIVISION
BIGGLESWADE, BEDS.


TELEPHONE: 2351




WOL4




Martonair lead in every phase of applied pneumatics




The most advanced range of equipment available to industry



An unrivalled technical service



Martonair Limited
Parkshot · Richmond · Surrey



electronic sub-assemblies

FOR SIMPLE OR COMPLEX CONTROL

The Mullard Equipment range of pre-set counters enables you to construct industrial control systems simply and speedily to your individual requirements. Because it is possible to translate almost any characteristic into a numerical count, their scope is almost unlimited: they may be used for a wide variety of industrial control, timing, length measurement, programme counting and for keeping track of changes in any control parameter.

These pre-set counters provide higher counting speeds, with greater reliability and accuracy, than electro-mechanical devices. Built-in control units enable the counters to be set to give output signals at any required measurement. Up to ten different switches can be fitted to each counter, each controlling an output signal so that complicated programmes are possible *which can be altered quickly and easily.*

backed by a comprehensive design advisory service

Mullard Equipment Limited will be happy to discuss with you the possible uses you can make of these and other electronic sub-assemblies. They can also design and construct sub-assemblies, assemblies and systems to your individual requirements. A regular 'Sub-Assemblies Bulletin' is now being published, write to Mullard House to have your name put on the mailing list.

. . . . for sub-assemblies, assemblies and systems

MULLARD EQUIPMENT LIMITED

MANOR ROYAL · CRAWLEY · SUSSEX

Telephone: Crawley 3421

ME 689



Pre-set Counters

The 88930 range of pre-set counters is specially designed for industrial applications and features:—


High counting speed
(up to 120,000 per minute)

Direct visual indication of the number counted


Easy replacements (plug-in units)

Built-in programme switches

Multiple programmes (up to 10 switches can be fitted to each counter)



CINCINNATI



DIAL TYPE MILLING MACHINES MODEL 'ELR'

SIZES 207-12 AND 307-12
PLAIN AND VERTICAL

CINCINNATI MILLING MACHINES LIMITED, BIRMINGHAM 24

Agents:


CHARLES CHURCHILL LIMITED: Birmingham, London, Glasgow, Manchester, Newcastle

production in large or small quantities

with all the convenience of the
general purpose milling machine

When it comes to the choice of either a production miller or a general purpose machine, consider the advantages of combining both functions in one machine—the new ‘Cincinnati’ Plain and Vertical Dial Types. ‘Cincinnati’ Automatic Table Cycles are effective because they are used in conjunction with an Automatic Backlash Eliminator to facilitate both conventional and climb-milling operations.

AUTOMATIC TABLE CYCLES




Plus:—


- * **Power Speed and Feed Changes, New Speed Change Lever** incorporates new 'Cincinnati' EXCLUSIVE Twist-Knob for effortless speed changes.
- * 'Cincinnati' EXCLUSIVE ARBOR-LOC Spindle Nose ensures rapid cutter changes without need for a draw-in bolt.
- * Another EXCLUSIVE feature – vibration dampening device – DYNAPOISE – ensures reduction of vibration caused by cutter.
- * Automatic Lubrication of Vertical Screw means low maintenance costs.

Write now for full details
contained in Catalogue No. M-6005E.

TWO OF THE MANY
CYCLES AVAILABLE



A simple milling cycle : rapid traverse right, feed right, automatic reverse, rapid traverse left, short feed left, stop.



Reciprocating cycle (with centre safety stop): rapid traverse left, feed left, automatic reverse, rapid traverse right, short feed right, stop. Rapid traverse right, feed right, automatic reverse, rapid traverse left, short feed left, stop.

for maximum production



the **SMART & BROWN**

SERIES




CAPSTAN LATHE

Maximum dead length collet capacity	11 16"
Centre height	4"
Spindle bore to turret face (max.)	11 1/2"
Spindle nose	29 32"

EPICYCLIC GEARBOX available

ONE OF BRITAIN'S FINE LATHES



LRST turret slide



CWP screw operated cut-off slide



Smart & Brown (machine tools) Ltd.

25 MANCHESTER SQUARE · LONDON · W.1

Telephone WELbeck 7941-5 Cables: Smartool, Wesdo, London

MAKERS OF PULTRA MICRO LATHES AND GRINDING MACHINES

Member of the GAS PURIFICATION AND CHEMICAL GROUP OF COMPANIES

NRP/3502

ELECTRICAL EPIKOTE RESINS INSULATION



The outstanding electrical insulation, ease of machining and chemical resistance of EPIKOTE resins are qualities excellently applied by Gardners Radio Ltd., in the production of bobbins for winding ionisation-free oil-immersed EHT transformers (for use up to 25 kV). The bobbins are cast and machined to very close tolerances. Does this give you a useful lead on a production problem? Ask for full details quoting No. EE.15

Shell Chemicals

**SHELL CHEMICAL COMPANY LIMITED**

Marlborough House, 15-17 Gt. Marlborough Street, London, W.1


SHELL and EPIKOTE are registered trade marks.

When replying to advertisements please mention The Production Engineer



**are all features of the
range of Precision
Grinding Machines
built by**-----

**FORTUNA-WERKE
SPEZIALMASCHINENFABRIK A.G.
STUTTGART
GERMANY**




**For Toolroom
and Production**



Illustration shows Model AFB, one of the wide range of types available in two sizes, 5 $\frac{5}{16}$ " height of centres, 12" and 20" maximum distance between centres. Can be arranged as plain, universal or automatic machine and with infinitely variable wheel speed.

*Automatic
Sizing*



With FINITOR Automatic size control the measuring head which controls the cycle of the machine is in constant direct contact with the work during grinding. Accuracy is thus independent of all variables inherent in the grinding operation.

**VAUGHAN
ASSOCIATES LIMITED**

LET US DEMONSTRATE TO YOU

4 QUEEN STREET • CURZON STREET • LONDON • W.1 Tel: GROsvenor 8362

Midland Office and Demonstration Department:

WILFORD CRESCENT : NOTTINGHAM Tel: NOTT 88008



THE

BA



"RÉEL"

THE PRESENT SHAPE OF CRANES TO COME



A Battery of four Réel Cranes supplied and erected for a continental customer

BRITISH INDUSTRIAL


ENGINEERING COMPANY (STAFFS) LIMITED

CORONATION WORKS, HAINGE ROAD,

WIVIDALE, TUNTON, STAFFS.

Telephone: TUNTON (333) 12/14

The REEL crane, in step with the space age, brings space into your factory . . . space for greater mobility and increased output. It "overrides" ordinary crane design by operating much higher in the roof. The streamlined all-welded construction combines great strength with easier maintenance. Here is the crane to put your factory planning well ahead. We will gladly provide you with full information and technical advice.



SPARCATRON

SPARK MACHINING


The Manufacturers with the greatest experience
in design and production of Spark Erosion Equipment

*
TECHNICAL DATA AVAILABLE ON REQUEST


SPARCATRON (MANUFACTURING) LIMITED

TUFFLEY CRESCENT · GLOUCESTER

007



large




small

thick



thin



tubes

*in Mild Steel and Stainless Steel
in Randoms or cut to length*

Do you have our Stocklist
of Standard and
Non-Standard Tube?

Markland Scowcroft LTD

Bromley Cross Nr Bolton
Telephone EAGLEY 600



MILLS

BRIGHT STEEL BARS

**Rounds (drawn, turned and ground)
Hexagons, Squares, Flats,
and Special Sections.**

**Mild, Freecutting, Casehardening,
Carbon and Alloy steels.
Supplied to A.I.D., Admiralty,
B.S. 970 and customers'
own specifications.**



EXORS. OF JAMES MILLS LTD.

BREDBURY STEEL WORKS WOODLEY. NR. STOCKPORT

Telephone: WOODLEY 2231. (10 lines) Telegrams: "MILLS" PHONE WOODLEY

SURELY, INFORMATION ON THE NEWEST TECHNIQUES IS VITAL TO YOU



The techniques of automation and control engineering are vital to every industry and engineering activity. CONTROL magazine serves them all. It is the leading automation and control engineering journal. Every month it reports hundreds of new ideas, applications and products. It is edited by an outstanding team of qualified engineers and carries in every issue at least 5 top-line exclusive contributed articles, plus regular features, covering systems engineering, instrumentation, data processing, servo-mechanisms, process control, and all their applications. The influence of CONTROL is wide—it is read by directors, plant and works managers; design, instrument, maintenance, production and research engineers; scientists, lecturers and students—the world over.

TWO OF THESE BOOKS — FREE



POLE
ZERO
APPROACH



MEASUREMENT AND DETECTION (CONTROL Monograph 1 SHOP PRICE 10/-)

A complete and authoritative study of electrical transducers by staff of British Scientific Instrument Research Association

THE INDUSTRY GUIDE AND DIGEST, 1962 (SHOP PRICE £1)

Second edition of this invaluable reference to the British control industry, detailing its firms, products and personalities, and providing a digest of new developments in the last 12 months

POLE-ZERO APPROACH TO SYSTEMS ANALYSIS (CONTROL Monograph 2—SHOP PRICE 10/-)

The widely acclaimed elucidation by Dr. P. F. Blackman of Imperial College, London

CONTROL REFERENCE-PAGE BINDER AND DATA SHEETS (SHOP PRICE 10/- + 10/- for Data Sheets)

A handsome vinyl-covered loose-leaf binder containing over 20 of CONTROL's celebrated data sheets, plus the October, 1961 computer survey (a chart 30" x 40")



TO NEW SUBSCRIBERS 'CONTROL' MAKES THIS OUTSTANDING DOUBLE OFFER—a special introductory price of 35/- for 12 monthly issues (full rate 42/-) plus a choice of 2 FREE books (value up to 40/-)—SO YOU GET 82/- worth for 35/-

A SAVING OF UP TO 65%

Please send me my FREE copies of

Measurement and Detection ☐

Industry Guide and Digest ☐

Pole-Zero Approach ☐

CONTROL Binder and Data Sheets ☐

TICK THE

2

YOU WISH TO
CHOOSE

and enter my subscription for 12 months at the special offer price of 35/-

I enclose 35/- ☐

Please invoice me later ☐

NAME

ADDRESS

POSITION

SIGNATURE

Postage
will be
paid by
Control

Business Reply Folder Licence WD 1823

No Postage
stamp
necessary
if posted in
Great Britain
or Northern
Ireland

CONTROL,
Rowse Muir Publications Ltd,
The Rowse Muir Building,
77-79 Charlotte Street,
London, W1 England




(C)

J.

Goulder

GEAR MEASURING EQUIPMENT


This series of advertisements is intended to show how attention to detail design backed by careful and precise manufacture has made Goulder gear measuring equipment first choice of buyers who appreciate these qualities.



ROLLING TESTER SADDLE ASSEMBLY

used on Goulder No. 1 Rolling Tester to measure variations in centre distance as two gears are rolled together under spring pressure and hence composite gear errors. Special layout of saddles allowing 1, vertical adjustment for gear under test 2, extra sensitivity 3, reduced bed length.

- CAM ACTION CENTRALISING LOCK TO PROVIDE DATUM
- FLOATING SADDLE IN NITRALLOY STEEL
- MICRO-INDICATOR AS ALTERNATIVE TO ELECTRONIC RECORDER
- SPRING TO PROVIDE ADJUSTABLE MEASURING PRESSURE
- STYLUS ABUTMENT PEG
- REAR BEARINGS CONSISTING OF TWO RINGS OF BALLS CARRIED ON A HARD STEEL SHAFT IN A HARD STEEL BUSH
- FRONT BEARINGS CONSISTING OF TWO BALLS CARRIED IN HARD VEE AND FLAT BEARINGS
- SLIDING SADDLE IN HARDENED NITRALLOY STEEL
- CAM ACTION LOCK FOR CENTRE DISTANCE SETTING



Goulder

THE NAME FOR ALL GEAR TESTING

J. Goulder & Sons Ltd., KIRKHEATON, HUDDERSFIELD.


Tel: Huddersfield 5252-3

19.17


THERE'S POWER TO SPARE...



Screwdriver LBU33H26



Pistol Drill LBB33



Angle Drill LBV33



Grinder LBF338

...with the new hand tools from Atlas Copco

Here are the latest air-powered tools! A range of light, compact drills, screwdrivers and grinders from Atlas Copco. Contour-styled to fit the hand, these tools offer unprecedented power/weight ratios and greatly improved starting torques. Drills weighing less than 3 lb. have 5-vane air motors developing nearly $\frac{1}{2}$ H.P. ... with all the reserve power you need at the break-through point.

In all designs the keynote is simplicity. Each tool has as few parts as possible; and wherever possible parts are interchangeable. Thus relatively few spares are needed to service the entire range.

The new Atlas Copco tools have been proved by more than a year of trials in factories such as de Havilland, Vauxhall, Canadair Fokker (Holland), Fiat (Italy), SAAB and Volvo (Sweden). Contact your local Atlas Copco branch office for further information. Literature is freely available and demonstrations can easily be arranged.

ATLAS COPCO (GREAT BRITAIN) LTD.,

Maylands Avenue, Hemel Hempstead, Herts. Boxmoor 6040

Sales and Service Depots at: LONDON · BRISTOL · CARDIFF · LICHFIELD
LEEDS · MANCHESTER · NEWCASTLE · GLASGOW · BELFAST · DUBLIN

Atlas Copco


puts compressed air
to work for the world

1/217

TH
GRAIS

Taking it easy, Mr. Williams?


Well, why not . . . he'll do the back lawn in next to no time with that fine new mower. It's all part of the good life he's come to expect. But do you know the part that pressure die castings play in that good life? We hardly expect you to. Let's just say that they're inseparable from it. Wolverhampton pressure die castings offer manufacturers high quality components at remarkably low cost in a variety of pleasing finishes. And the massive scale of production that can be achieved helps everyone to enjoy a higher standard of living. Wolverhampton pressure die castings in zinc and aluminium point to progress in a big way. Your enquiries would be welcomed.



THE WOLVERHAMPTON DIE CASTING COMPANY LTD

GRAISELEY HILL, WOLVERHAMPTON

TELEPHONE: WOLVERHAMPTON 23831/7



BI-Stat

the complete switching system

BI-Stat controls any automatic sequence of motor operation.

It does anything that electro-mechanical relays can do, without any of their accepted limitations. It will never do wrong. It will never need maintenance. What's more, it is far simpler to modify when the need arises.

WHAT IS IT?

A system of logic units and amplifiers, which combine and sort input signals, then magnify them to drive the solenoids, contactors, etc., that initiate plant motions.

WHY IS IT BETTER?

Because BI-Stat switching is entirely devoid of moving parts and contacts. Because BI-Stat components are completely encapsulated.

BI-Stat suffers no burn-outs, maladjustment, wear or corrosion, no sticking or fouling or fatigue. BI-Stat works happily amidst dirt, oil, moisture and fumes.

BI-Stat is supplied as BHI-engineered equipment, or as components for your own systems.

Write for publication ZB35 and consult BHI for the BI-Stat answer to your control problems. BI-Stat will solve them permanently.



BROOKHIRST IGRANIC

Enquiries to:

BI-STAT DIVISION • NORTHGATE WORKS • CHESTER

MAKERS OF BRITAIN'S WIDEST RANGE OF ELECTRICAL CONTROLS AND ASSOCIATED EQUIPMENT

BI/60

for all materials handling problems...



FLOOR CONVEYORS
SKI-WRACKERS
OVERHEAD CONVEYORS
HOISTS
RUNWAYS
CRANES
GRABS

KING

have the
answer



MATERIALS HANDLING SPECIALISTS


GEO. W. KING LTD. ARGYLE WORKS, STEVENAGE, HERTS. TEL: STEVENAGE 440

A KING representative will be pleased to call on you anywhere in the world.

When replying to advertisements please mention The Production Engineer

Gosheron
tapes

serving industry
— everywhere



trouble-free CONTOR SELF-ADHESIVE masking tapes

Clean lines, minimum paint build-up, no impregnation, stain or adhesive residue at high temperatures. CONTOR Paper Masking Tapes (BSJ11) provide the complete answer for all spraying, painting, stoving, protecting, sand or shotblasting processes.

Write for
"Tape Times" now —
the up-to-date journal
for all tape users.

**John
Gosheron
& Co. Ltd**

THE PACKAGING & INDUSTRIAL TAPE CENTRE
58/60 KENSINGTON CHURCH ST. : LONDON W.8
WESTern 8011/20

Photo courtesy Croall Bryson & Co. Ltd.

The Production Engineer

**Faster production
flows with this reliable
high-speed counter**



2,000 counts a minute!
That's the kind of speed this counter revels in. It's one of Tyer's famous Perram Photo-Electric Counters—all of which now have fully-transistorised circuits, giving operating speeds far greater than ever before. Apply now for full information about this incomparable range.

PERRAM

**Yet another
important achievement by**

TYER

TYER & COMPANY LIMITED

(Formerly P.A.M. Ltd.)


PERRAM WORKS · MERROW SIDING · GUILDFORD · SURREY

TEL: GUILDFORD 2211

Within the organisation of the Southern Areas Electric Corporation

Est. 1851

controlling a fluid power



BY HAND
BY FOOT
BY PUSH BUTTON
BY CAM
BY SOLENOID




One of the most popular range of valves is this P.800 series available as lever, foot, toe, air pressure or solenoid operated. The basic valve is engineered to give the maximum number of trouble free operations, unaffected by dirt because it is self cleaning, full air flow through valve giving faster response to cylinders, and easy fixing to any machine, make this range the most versatile available. $\frac{1}{4}$ " and $\frac{1}{2}$ " BSP sizes.

Manufactured by the Makers of Fine Machine Tools

Stuart
DAVIS
LTD

STONEBRIDGE HIGHWAY, WILLENHALL
COVENTRY

Telephone: Toll Bar 2451/5



A panoramic illustration of










*A typical pressing
assembly of body panels and
other components as produced on
Wilkins & Mitchell Presses*




WILKINS & MITCHELL PRESSES at PRESSED STEEL Co. Ltd., LINWOOD

The long standing preference of so many of the busiest producers in the motor industry for Wilkins & Mitchell Presses, especially in their most recent installations is based on their need for higher productivity. Throughout the world, users have learned to rely on the design, dependability and built-in reserves of Wilkins & Mitchell Presses.
 ..the complete press shop or the single press.
 why not consult us?




WILKINS & MITCHELL

The Presses that cut costs



WILKINS & MITCHELL LTD DARLASTON S. STAFFS . ENGLAND

small parts
play a
big part



PRECISION GRINDING SMALL COMPONENTS FOR MOTOR ACCESSORIES AT SMITHS

This is a typical grinding operation carried out on our Model 1212 High Precision Grinding Machine.



At the Cricklewood works of Smiths Motor Accessories Ltd., a number of Jones-Shipman precision grinding machines are employed in the production grinding of the many small components which go into the making of their renowned accessories for motor cars such as speedometers, clocks, gauges, etc. This type of work calls for the smaller models in our grinding machine range such as the Model 1310 Cylindrical Grinder 8 in. \times 18 in. capacity, and particularly the Model 1212 High Precision Grinder 5 in. \times 18 in. capacity.

JONES - SHIPMAN

precision grinders

A. A. JONES & SHIPMAN LTD.


Leicester. Telephone: 823222

London Office: 50/52 Great Peter Street, London, S.W.1.

Telephone: ABBey 5908/9.


SOLENOID CONTROLLED VALVES

Built to JIC Standards for pressures up to 3,000 psi and 5000 psi.




MANUAL CONTROL VALVES

Threaded body or subplate mounted design for pressures up to 2500 psi or 5000 psi, 7 different spool configurations.



DENISON VANE PUMPS/MOTORS

Output from 80 gpm to 97 H.P.




PRESSURE CONTROL VALVES

Available as Relief Sequence. Unloader — Pressure reducer.




DENISON AXIAL PISTON EQUIPMENT



Pumps and motors of this series are expressly designed to cater for application demanding heavy duty service and high efficiency operation. Available in both fixed and variable displacement 6 different types of controls are offered

- HANDWHEEL CONTROL ● STEM CONTROL
- HYDRAULIC CYLINDER CONTROL ● ELECTRO MOTOR CONTROL ● PRESSURE COMPENSATING CONTROL ● SERVO CONTROL

Pump output range from 1.9 to 115 g.p.m. Motor output range from 1.25 to 310 H.P. over various speed ranges. Send for full details.



DERI SINE EQUIPMENT

Pumps to 120 gpm. Motor to 100 H.P.



FLOW CONTROL VALVES

Instant, exact, and infinitely variable regulation of flow up to 3" capacity.

Denison

Deri


LIMITED

Low in cost - Highly flexible

TRANSISTOR P.S.U.s

Here is the most economical and convenient method of obtaining low voltage power supplies to meet differing production or laboratory requirements.

Mullard Equipment Limited has produced a range of P.S.U. sub-assemblies, consisting basically of four simple units which, readily added one to another in building brick fashion, will provide power from 1 to 39 volts. And they will do this most economically. A 1 amp stabilised supply need cost only £25.



The basic units are :—

- * 1 amp Unstabilised Unit (YL. 6101)
- * 5 amp Unstabilised Unit (YL. 6102)
- * 250 mA Stabiliser and Reference Section (YL. 6103)
- * Series Regulator Section (YL. 6104)
- * 6 volt Positive Line Stabilisers (YL. 6105)

Constructed for easy assembly, the basic units may be duplicated in operation for higher power applications.

These P.S.U.s are ideally suited for use in equipments and systems employing other Mullard Equipment sub-assemblies such as the well-known Norbits and Combi-Elements.

For further details please write, quoting reference AC/690/11, to :

MULLARD EQUIPMENT LIMITED

Manor Royal • Crawley • Sussex • Telephone Crawley 28787

SAVE wear and you **SAVE** money




invest
in quality

use



ENERGOL
INDUSTRIAL LUBRICANTS




Distributed by

THE POWER PETROLEUM COMPANY LTD

76-86 STRAND · LONDON W.C.2 (Branches and Depots throughout the country)

Silicones in Engineering



THE LATEST FROM **MS**

This new booklet gives you numerous examples of how MS Silicones are being used in engineering and allied industries—case histories, production techniques and a wide range of illustrations from current industrial practice where MS Silicones have cut manufacturing and design costs, as well as improving operational reliability.

Send for 'SILICONES IN ENGINEERING'

—you'll find things in this booklet you'll want to know more about

Write for 'MS News'

—it contains the latest news about all MS products

See MS Silicones

—on stand C4 at the Engineering Materials and Design Exhibition

*MS Silicones offer you
a unique combination of properties*

- * Resistance to extremes of temperature
- * Water repellency
- * Chemical inertness
- * Excellent electrical properties
- * Adhesion resistance

MS MIDLAND SILICONES LTD

(Associated with Albright & Wilson Ltd. and Dow Corning Corporation)

first in British Silicones

68 Knightsbridge, London, SW1 Telephone Knightsbridge 7801

Area Sales Offices: Birmingham, Glasgow, Leeds, London, Manchester

Agents in many countries



Please send me:

1. a copy of 'Silicones in Engineering' ☐
 2. a copy of the latest 'MS News' ☐
- (and put me on the mailing list)

Name _____

Company _____


Address _____

E.8

AIRMEC

AUTOSET

*Gets
those
Drilling
Jobs
taped*



AUTOMATIC PRECISION DRILLING (LARGE SCALE OR SMALL) WITH THE AIRMEC AUTOSET

POSITIONS THE WORK

AUTOSET automatic co-ordinate setting equipment provides accurate automatic control of the lead screws of a co-ordinate table. It enables the table to be positioned automatically by means of a punched tape (containing co-ordinate information for up to 400 operations) or manually by means of a series of knobs and dials.

SELECTS THE RIGHT TOOL

Facilities are provided for selecting one of up to ten tools and for controlling a large number of other variables such as tool rates, feed depths and spindle speeds.

CUTS OUT ERRORS

Autoset is highly accurate — automatic compensation is provided for table backlash and cumulative lead screw errors.

CUTS THE COST

An equipment for automatic control in two dimensions, complete with tape reader and tape punch, costs only £1,630. Manual control considerably less.

ROBUST AND RELIABLE

No electronic valves used.

EASY MAINTENANCE

Autoset has been designed for trouble-free service and easy maintenance.

VERO AUTODRILL MODEL 5625

This Full Automatic 6 Spindle Turret Drilling Machine has a maximum capacity of 9/16" in mild steel and enables components with up to 400 holes to be drilled, reamed, counter-bored or tapped without supervision.

Full details available from:
Cammur Machine Tool Corporation Ltd.,
103 Lancaster Road, London, W.11

Airmec

AUTOSET Low cost tape control


AIRMEC LIMITED High Wycombe Bucks
Tel: High Wycombe 2501

BRITAIN'S FIRST NYLON BELT

STEPHENS
Miraclo

The best belt for EVERY drive

If you require a top performance lightweight flexible belt that won't slip, has enormous strength and elasticity with virtually no stretch, and with the grip that only chrome leather can give, then you need a MIRACLO nylon-core belt.



FREE Send for this new 12 page colour brochure 400 which fully explains in word and picture the Miraclo Nylon-Core Belt — the Belt that performs miracles.



from fractional h.p. to 1,000 h.p.

STEPHENS BELTING CO., LTD.
SNOW HILL · BIRMINGHAM 4

IRA STEPHENS LTD.
ASHTON-UNDER-LYNE

The First Power Saw with Automatic Overload Cut-Out



**SEE STAND
781
ROW R
at the
BUILDING
EXHIBITION**

Bridges

With NEONIC SAFETY

PORTABLE

**7 1/4" POWER
SAW**

Years ahead in design, the new Bridges 7 1/4" Power Saw is the tool for which every craftsman has been waiting. Lighter, more comfortable to use, safer, it's the first portable power saw to be double insulated. No other Portable saw has so much power or so many BIG features.

UNIQUE SPLITTER KNIFE

For 'dead-eye' accuracy and ease of use. Also acts as safety device. The knife rises and falls with depth of cutting setting.

DOUBLE INSULATED CARTRIDGE MOTOR

Gives more power for its size... greater resistance to overloading... far longer working life. Air jet clears sawdust from blade and marker.

EXCLUSIVE TORQUE CLUTCH

Protects motor against jams. If blade stalls, it allows motor to run at reduced speed until switched off or blade pressure is released.

NEONIC SAFETY EYE

Indicates that saw is earthed and correctly wired to the mains. An important safeguard to the user. All these features plus depth of cut and bevel adjustment up to 45°, make Bridges 7 1/4" Power Saw a better, far more profitable tool to use by boosting production and giving safer, easier operation. Right through it is a Power Saw you can rely on. Selection of Saw Blades available for Rip and Cross Cut, Planing and Mitering, etc.


S. N. BRIDGES & COMPANY LIMITED, YORK ROAD, BATTERSEA, LONDON, S.W.11



Kopp VARIATORS
CAN NOW TRANSMIT

UP TO 50 HORSE POWER

**AT CONTROLLED
VARIABLE SPEEDS**




The new "K" range of Variators have the same advantages of high reliability, compactness and sensitivity of control which have contributed to the successful use of Kopp Variators in Industry throughout the world.

Efficiencies of between 85% and 93% are obtainable over an increased speed range of up to 12:1. The minimum output speed has been reduced to one seventh of the input speed. Technical Representatives in London, Birmingham, Manchester, Leeds, Bristol and Glasgow, or write to the address below for full details of the advantages of controlled variable speeds.

ALLSPEEDS LIMITED

ROYAL WORKS, CLAYTON-LE-MOORS, P.O. BOX 43, ACCRINGTON, LANCASHIRE. TEL ACCRINGTON 35441 (6 lines)

When replying to advertisements please mention The Production Engineer



Compressed air plays a part in the Can-making industry


Broomwade Air Compressors provide power for many important British Industries. Can-making, for instance, for The Metal Box Company. The photograph shows Broomwade Compressors at their Westhoughton factory; six Compressors and three Vacuum Pumps are installed, and are proving themselves daily as a safe, reliable and economical source of power.

Please write for full details


BROOMWADE manufacture a wide range of Stationary Air Compressors with outputs from 2 to 2,200 c.f.m. of free air at 100 p.s.i. There are compressors specially designed to supply oil-free compressed air, and the new "V" range with outputs from 365 to 1,000 c.f.m. per minute at 100 p.s.i., which run so smoothly that deep foundations are unnecessary.

"BROOMWADE"


Air Compressors and
Pneumatic Tools
YOUR BEST INVESTMENT




Line boring camshaft and crankshaft bores and facing, counter-boring and milling of seating on end of crankcase.



Finishing liner bores including grooving operation.



Boring and milling on drive take off holes and faces.



chosen by


...machining
crankcases

Fine Boring
THE PRECIMAX
Way

These Landis Lund Fine Borers are installed at the Crewe works of Rolls Royce—meeting the exacting standards of this Company on the production of crankcases.

The finest car in the world relies on machining the Precimax way.

TYPE FBI/3
FINE BORING MACHINE



LANDIS LUND LIMITED

CROSSHILLS—KEIGHLEY—YORKSHIRE



MAXIMUM PENETRATING CAPACITY


... and not only maximum penetrating capacity . . . but also unsurpassed speed and ease of operation, due to hydraulic pre-selection of feeds and speeds. Capacity is up to $4\frac{1}{2}$ in. diameter, in cast iron. There are 22 speeds from 11 to 1,450 r.p.m., and 18 rates of feed. These powerful and versatile machines are available in ten sizes, from 5 ft. to 14 ft. spindle radius. Complete details gladly sent on request.

ARCHDALE

JAMES ARCHDALE & CO. LTD.

BLACKPOLE WORKS • WORCESTER


Worcester 27081 (7 lines)



Sole Selling Agents: ALFRED HERBERT LIMITED

Hydraulic
PRE-SELECT RADIALS

*H*YDRAULICS serve the very young...



VSG Mark III Hydraulic Transmission Gears capable of 50 H.P.
output driving Richard Simons & Sons Ltd., twin
cylinder drying machines in the Farex Dept.
at Glaxo Laboratories Ltd., Greenford, Middx.

**INFINITELY VARIABLE
HYDRAULIC TRANSMISSION GEARS**

VICKERS-ARMSTRONGS (ENGINEERS) LTD

HYDRAULICS DIVISION WEYMOUTH WORKS WEYMOUTH DORSET Tel: Weymouth 6



Further Technical Information Supplied on request to

Registered Offices and Sales Department: VICKERS HOUSE BROADWAY LONDON SW1 Tel: ABBEY 7777

wm 369

The **VERSATILE TURRET MILLER**

for Milling, Boring, and Jig
Boring at any angle, Keyway and
End Milling, Die Sinking, Mould
and Pattern Making. Machine
illustrated is fitted with table
power feed and slotting
head as extras.



Head swivelled and tilted.



Head angled, swivelled and tilted.


For full details write to:

WOODHOUSE & MITCHELL

**WAKEFIELD ROAD
BRIGHOUSE YORKS
ENGLAND**


PHONE: BRIGHOUSE 627 (3 LINES)
GRAMS: 'WOODHOUSE BRIGHOUSE'

WM26



A move in the right right direction

THE EXCLUSIVE DOUBLE WIPE ACTION



The essential dependability of A-MP programming systems is ensured by the double-wipe action which cleans contact surfaces as they engage. The unique design provides contact engagement by a lateral locking movement of the entire removable patchboard so that contact pressure is consistent, and pins cannot be displaced. Note the special chevron shape of the contacts, providing 0.090" of wiping action with only 0.060" pin travel.

Other advantages of A-MP patchboard systems are:

- Remarkable flexibility of switching arrangements.
- Contacts made and broken by cam action of frame.
- Double wipe action precleans contact springs.
- Contact resistance stable down to low microvolt levels.
- Consistent contact pressure, irrespective of number of connections.
- Range covers 240 to 5304 contacts, in various materials.
- Standard range of pluggable leads covers all lengths and configurations.

A-MP PROGRAMMING SYSTEMS



★ Trade Mark of
AMP Incorporated U.S.A.

AIRCRAFT-MARINE PRODUCTS (GT. BRITAIN) LTD

Head Office: Dept. 33

AMPLO HOUSE, 87/89 SAFFRON HILL, LONDON, E.C.1

Tel: CHAncery 2902 (7 lines)

Telex: 23513

Cables: AMPLO LONDON TELEX

SOUTH AFRICA: DISTRIBUTOR, E. S. HOWAT & SONS (PTY) LTD. 51-57 MILNE STREET, P.O. BOX 437, DURBAN, NATAL, SOUTH AFRICA
ASSOCIATED COMPANIES IN: U.S.A., AUSTRALIA, CANADA, HOLLAND, FRANCE, GERMANY, ITALY, JAPAN AND MEXICO.

AP 190


When replying to advertisements please mention The Production Engineer

CONSUL


CONTROL EQUIPMENT

**AIR CYLINDERS
CONTROL VALVES,
FITTINGS etc., FOR ALL
INDUSTRIAL APPLICATIONS**

- PRECISE CONTROL
- ADVANCED DESIGN
- COMPETITIVE PRICES



- ★ Total absence of assembly screws—internal assembly may be removed by merely releasing retaining clip
- ★ 1/16" movement to open valve with 3/32" over-travel
- ★ Balanced action with maximum sensitivity.
- ★ Push-out hollow tension pins serve the dual purpose of fixing holes for single valve or battery mounting. Simple conversion of valve to alternative methods of operation: Plunger—Hand Pad—Hand Lever—Lever and Roller—Ball—Air—Solenoid—Foot.
- ★ 1/8" and 1/4" B.S.P. port sizes.



The co
covers a
light h
automat
and pro


Our exp
will be
receipt
of prop
are pro
Technic
through

★ Ro
m
★ N
ba
co
★ A
e
★ B
no

ULTAIR


The comprehensive CONSULTAIR range covers all requirements for pneumatic and/or light hydraulic equipment in the fields of automation, mechanisation, materials handling and process control.

Our experienced team of technical engineers will be pleased to advise immediately on receipt of your requirements. Layout drawings of proposed circuits and standard components are provided free of charge with quotations. Technical representatives are at your service throughout the country.



- ★ Robust construction — corrosion resistant materials — maximum power.
- ★ No tie rods—end covers positively located in cylinder barrel and secured by retaining ring, thus ensuring correct alignment of piston and rod bearing.
- ★ A wide variety of mountings to suit any application, e.g., foot, flange, trunnion, base, etc.
- ★ Bore sizes 7/8", 1 1/4", 2 1/4", 3" and above, cushioned and non-cushioned, double acting and single acting.

- ★ Simplicity of design with minimum of component parts.
- ★ Strong non-rotating operating piston.
- ★ Capable of many millions of reversals.
- ★ Available for positive self-centring and self-reversing action. Hand, air and solenoid operation.
- ★ 1/8", 1/4", 3/8" and 1/2" B.S.P. port sizes.



***No need for additional
machines and extra floor space***



DIMENSION INDICATORS



- * Reduce stoppages for measurement after each cut.
- * Increase machine utilisation and output.
- * Reduce setting errors.
- * Direct readings of workpiece dimensions give greater speed and accuracy.

Full technical details on request

English Numbering Machines Ltd.

Dept. 3K · QUEENSWAY · ENFIELD · MIDDX · HOwARD 2611 (5 lines) · Grams: Numgravco, Enfield

HEYLIGENSTAEDT

G I E S S E N



ROTOR DISCS FOR JET ENGINES

are often extremely thin. Besides that, both faces are of different profiles and sometimes without centre bore (see section, top right). It is no longer a problem to economically turn these difficult work-pieces since the DPK 750 'DISCOMAT' Twin Copy Turning Machine appeared on the market. The discs are clamped at their circumference and simultaneously machined on both sides with 2 copying slides. Operation is very simple; when pushing a button, the automatic cycle starts.

The application of the DPK 750 is not only restricted to rotor discs, however; thick-walled, even asymmetrical work-pieces can be machined as well, e.g.: bearing caps, rope pulleys, brake drums, housings, etc.

Swing	750 mm
Speeds, two steps	12 - 120, 28 - 280 rpm
18 Feeds, range	0.06 - 3.15 mm per rev
Motor power	10 - 34 HP



Bishop, Eaves & Sons, Ltd.

868, Alum Rock Road,
Birmingham, 8

Telephone : East 4071
Telex 33461 Bishheaves Birmingham


Prolite


Precision Ground
SOLID CEMENTED TUNGSTEN CARBIDE

BURS



- for machining and finishing any material from plastics to hardened steel
- These tough tools are perfectly balanced with sharp accurate tooth forms
- Very fast cutting rates are possible with 'PROLITE' BURS
- The working life is 50 to 100 times that for steel burs
- Available in fine, medium and coarse flutings, also diamond cut and file cut, in a wide variety of shapes and sizes
- An efficient
**REGRINDING
 SERVICE**
 is available

*Write for our catalogue
 of 'PROLITE' BURS*



Home Sales: **PROLITE LIMITED** (a subsidiary company of Murex Ltd.), RAINHAM, ESSEX.
 Telephone: Rainham, Essex 3322. Telex: 28632. Telegrams: Prolite Rainham-Dagenham, Telex.
 Southern Area Office: Central House, Upper Woburn Place, London, W.C.1.
 Midland Area Office: Guildhall Buildings, Navigation Street, Birmingham, 2.
 Northern Area Office: Norwich Union Buildings, City Square, Leeds, 1.
 Export Sales: **MUREX LIMITED** (Powder Metallurgy Division) RAINHAM, ESSEX, ENGLAND.
 Telephone: Rainham, Essex 3322. Telex: 28632. Telegrams: Murex, Rainham-Dagenham, Telex.



Enots

LOCAL STOCKISTS

BRADFORD

Thomas Wright (Bradford) Ltd.,
85 Bower Street, Bradford 5.
Tel : Bradford 28831-2.

BRISTOL

C. E. Kidd & Son Ltd.,
15 Rupert Street, Bristol 1.
Tel : Bristol 27594.

COVENTRY

G. E. Adams Ltd.,
401 Broad Lane, Coventry.
Tel : Tile Hill 66472.

LEEDS

Thorite Pneumatics Ltd.,
135-137 West Street, Leeds, 1.
Tel : Leeds 35512.

LEICESTER

Headland Engineering Developments Ltd.
38 Gartree Street, Leicester.
Tel : Leicester 29888.

LONDON

G. X. Engineers Ltd.,
Gerrards Cross, Bucks.
Tel : Gerrards Cross 3954.

LONDON

Process Pneumatics Ltd.,
19 Charlton Road, London, S.E.3.
Tel : GREenwich 6575.

MANCHESTER

Car & Cycle Dept.,
Baxendale & Co. Ltd.,
Miller Street, Manchester 4.
Tel : Blackfriars 8282.

NORTH SHIELDS

James Hogg & Sons
(North Shields) Ltd.,
Collingwood House, Lawson Street, North Shields.
Tel : North Shields 503/4.

RUSHDEN

Cox & Wright (Shoe Machinery Services) Ltd.,
Wellingborough Rd., Rushden.
Tel : Rushden 4041-2.

SALFORD

Modine Productions Ltd.,
Dawson Street, Greengate, Salford 3.
Tel : DEAnsgate 7011.
BLAckfriars 2763.

SHEFFIELD

Tuckers (Sheffield) Ltd.,
Shoreham House, Shoreham Street, Sheffield 1.
Tel : Sheffield 29691.

SOUTHEND-ON-SEA

A. J. Howard,
19 Alexandra Street, Southend-on-Sea, Essex.
Tel : Southend-on-Sea 43579.

STOCKPORT

L. L. Price (Pipelines) Ltd.,
Brascope House, 33 Buxton Road, Heaviley, Stockport.
Tel : Stockport 5202.

STOKE

Cotton Bros. (Longton) Ltd.,
Crown Works, Longton.
Tel : Stoke on Trent 33021.

SCOTLAND


J. & T. Lawrie Ltd.,
Livingstone Street, Clydebank.
Tel : Clydebank 2171-2/3.

SOUTH WALES

G. N. Hunter & Co. Ltd.,
Walsall House, West Wharf Road, Cardiff.
Tel : Cardiff 23458.

PNEUMATIC CONTROLS
LUBRICATING SYSTEMS
SOLDERLESS TUBE FITTINGS
COOLANT FITTINGS
FILLER CAPS

BENTON AND BONS LIMITED - ASTON BRIDGE STREET - BIRMINGHAM 5



IMPROVED METHODS OF INDUCTION HEATING

ADVISORY SERVICE:

Radyne Ltd are leaders not only in the theory of induction heating but also in the best ways of using it in practical, down-to-earth industrial problems. We will be happy to discuss your problems without obligation.

Please use the coupon below.

A line of R.F. induction heaters in service with the Ford Motor Company, Basildon, Essex.



Many high production processes are best carried out by radio frequency heating... best because of its inherent controllability; best for blunt indisputable facts of economics.

INDUCTION HARDENING

R.F. heating will harden components locally with the greatest precision, and is far quicker and cheaper than conventional methods of surface hardening, localised through hardening, and tempering.

SOLDERING AND BRAZING

Soldering and brazing by induction are quicker and cleaner than by conventional methods. Localised heating restricts the flow of solder to the joint area. Both parts to be joined are raised to working temperature together. Scale and discoloration are reduced to a minimum.

THROUGH HEATING

In forging, stamping, and other processes, rapid through heating to forging temperature saves time and space, reduces scaling and in consequence wear and tear on dies, improves dimensional accuracy, and gives better working conditions.

ANNEALING

Localised annealing between processes can be carried out with greater speed and control by induction methods than by any other.

Across
new
frontiers



WOKINGHAM BERKS ENGLAND
TELEPHONE: WOKINGHAM 1030
(12 LINES)
CABLES: RADYNE ENGLAND

I am interested in the industrial applications
of induction heating

NAME

COMPANY

BIRMINGHAM · LONDON · MANCHESTER · GLASGOW · NEWCASTLE-ON-TYNE · LEEDS · BRISTOL · BELFAST

BIRMINGHAM • LONDON • MANCHESTER • GLASGOW • NEWCASTLE-ON-TYNE • LEEDS • BRISTOL • BELFAST

**BRITAIN'S
FOREMOST
DISTRIBUTORS**



**SERVING
INDUSTRY
AND THE
COMMUNITY**

SMALL TOOLS

MACHINE TOOLS

RUST-OLEUM/SLIP

AND RETAIL

DIVISIONS

Monks & Crane Ltd

For competitive plunge or through-feed grinding, and to tenths

Wickman Scrivener



This machine offers accuracy of grinding, quality of finish, and economy of production under the most exacting conditions. With a grinding capacity up to $\frac{3}{8}$ " diameter at maximum production rates and 1" for batch work, the No. '0' machine caters for most classes of small work. Many standard features normally regarded as extras contribute to operating efficiency and together with a patented controlled-cycle system for plunge grinding this machine is today's best proposition in small centreless grinders.

If you have a centreless grinding problem — share it with us !

Centreless Grinding Machine

Some standard features.

Grind specifications

Maximum opening, new wheels, hand-operated machine	1 $\frac{1}{8}$ "
Maximum opening, new wheels, controlled-cycle machine	1 $\frac{1}{2}$ "
Grinding wheel size, diameter x width	12" x 3"
Control wheel size, diameter x width	7" x 3"

- ★ Separate hydraulic form truing attachments to both wheels.
- ★ Anti friction rollers to diamond dressing attachment for positive truing of grinding wheel.
- ★ Universal workrest for through-feed and plunge feed workpieces.

W I C K M A N  L I M I T E D

FACTORED MACHINE TOOL DIVISION, BANNER LANE, COVENTRY

Telephone: Tile Hill 65231

540 F20/80

The Production Engineer

THE JOURNAL OF THE INSTITUTION OF PRODUCTION ENGINEERS

VOL. 40

No. 11

NOVEMBER 1961

PHYSICAL REQUIREMENTS OF AUTOMATION

by A. L. STUCHBERY, M.I.Mech.E., M.I.Prod.E.

Chief Technical Engineer, The Metal Box Co., Ltd.;

Vice-Chairman of Council,

The Institution of Production Engineers.

★ ————— ★




This Paper, and the Paper which follows it, were presented at the First British Conference on the Social and Economic Effects of Automation, held at Harrogate in June, 1961.

★ ————— ★

I PROPOSE in this survey to limit myself to the requirements for automation practices when applied to manufacture. The exclusion of reference to automation in the chemical and similar industries, and applications to data processing directed to forecasting and production control, in no way belittles these important aspects. The purpose is to consider automation requirements associated with the machining, forming and assembly of things of unlimited variety and, in some cases, almost unlimited complexity.

If we consider what is involved in the manufacture of a motor car, it is clear that between the automatic manufacture of a single set screw and the automation of, say, a cylinder block, as single components there is an enormous difference in complexity. It is also clear that apart from the wide range of components which a car manufacturer may himself attempt to automate, there is a very wide variety of items made for him by his suppliers and, in turn, by theirs. But the motor car is still only a small part of the manufacturing spectrum, so that even limited in the way I have indicated, the field remains immense. Essentially our problem is that of considering the variety of extents to which we may engineer production and to underline some of the guiding principles and needs.

It is trite to observe that man is a tool-using animal. It is, nevertheless, fundamental to the whole industrial



scene. From time immemorial he has developed amazing skills in the fashioning and use of these tools, and it needs no argument to extol the perfection and beauty of the many things man has made through countless centuries with nothing more elegant than hand tools. Nor is there any field in which we lack example and inspiration: magnificent buildings and their furnishings, carvings, engravings and paintings and, of course, development of tools and instruments used by the mathematicians, astronomers and mariners of early time.

Nevertheless, when things were made in this way, time was unimportant and we may judge that progress in the development of skill was correspondingly slow. Indeed, looked at from our position, these eras appear almost static since progress depended upon minute increments of improvement and transmission from generation to generation. Certainly there are peaks of outstanding achievement, but great intervals intervene and if the progress really is systematic it can only be so when judged on a very long time scale.

the industrial revolution—first order of mechanisation

Such tools are, of course, the elements of mechanisation and, together with devices like the wheel and the level, were the instruments of individual skill while wielded by hand, and this situation prevailed throughout known history until the era of power. All tools were simple and general and bore no specific relationship to a given product. They were simply to cut, to hammer, and to hold. The only exceptions were moulds for castings and coinage.

With the coming of power came a revolution in tools. Cutting tools were put under control, hammers became formers and the holding tools became specific fixtures. They began to bear a recognisable relationship to the product. The development of such practices really represents the awakening of production consciousness. It opened up the major preoccupation of production until the end of the 19th century which was the division of labour, the multiplication of tooling and the general de-skilling of the work. Although individual skill remained important, the division rendered it sufficiently narrow in scope that the number who could acquire it became correspondingly increased. Together with the application of the power which could wield and sustain these tools, this represents the essential element in the Industrial Revolution.

The other important factor was the change in the pattern of demand. It was not only a case of an ever-increasing number of people becoming capable of producing; the products themselves stimulated unsuspected appetites which, after two or three centuries of growth, show no signs of being satisfied. Indeed, though a demand may be started by a specific invention or development, it is the persistent pressure of an expanding and unsatisfied demand which determines the extent to which production practices are mechanised.

This kind of mechanisation had, in many applications, arrived at a very advanced state of development by the close of the last century and I propose to call this the mechanisation of divided operations or the first order of mechanisation.

automation—second order of mechanisation

It is from this point that automation starts and in the same context may be defined as the second order of mechanisation. Two basic steps are involved—one concerned with the conditions of "flow" which must follow the joining of separately mechanised operations into one continuous process, and the other, those aspects of control needed to make such an integration a viable undertaking.

In the same way that there may be many degrees of the mechanisation of divided operations, so too are there endless variations in the extent to which these two factors of integrated mechanisation may be applied.

The pressures which demand, and the reasons for adopting, varying applications will be the major object of this review, but in the most general sense

the purpose is to make more effective use of manpower, which of course, means man's skill.

Whereas in hand work the whole available skill is invested in the product, in the mechanisation of divided operations a varying amount of skill is invested in the specific tooling and less in the product. When we proceed to the mechanisation of integrated operations we need additionally to invest skill in both the means for linking the operations, and the means of control. Usually, the skill then invested in the specific tooling will be at its maximum.

Fig. 1 sets out the sort of relationship which may exist between the three stages. With an arbitrary unit of skill per unit of production, the line "A" shows the trend likely to take place at different levels of mechanisation of divided operations; while "B" and "C" show the trends with varying degrees of the application of the two main factors of automation, or the second order of mechanisation. The likely investment of skill in the mechanical facilities is shown at "D"; while the line "E" shows the sum of all the skills.

Fig. 2 shows the sort of trend to be expected in administrative effort. Fig. 3 indicates the capital employed relationship, to which further references will be made later.

The extent to which investment is made in making man's skill more productive will be determined by one or more of the following requirements. Their order of importance will vary with circumstance, though the first is likely to be the most compelling, at least in the early stages. To the extent that skill in converting materials is the basic element of cost, the economic and efficient application of automation must result in cost reduction. The crux is the economic and efficient application.

These requirements are:


1. the overall increase of production in order to meet demand;
2. the reduction of the labour or skill element to remain competitive;
3. the improvement of quality or consistency;
4. the better utilisation of equipment, buildings and capital resources;
5. the reduction of wasteful inter-operation inventories.

These are the factors in the overall industrial pressure which determine the extent to which mechanisation of either the first or second order is adopted and the rate of change from one to the other.

Mechanisation of the first order has been concerned mainly with items 1 to 3, usually in an *ad hoc* and disconnected fashion. The second order, however, deals with them all and essentially in a connected and systematic way, in order to achieve a coherent and controlled whole or process.

product development for automation— some historical notes


Although the quality of the second order of mechanisation will depend on the quality of the first, it does not follow that the first order, chosen for its



LONDON TIMES (1850)
FIG. 4

own sake, will necessarily be appropriate to extension to the second. The division of operations appropriate to re-integration needs not only to foresee this integration, but needs also to be related to what may be called unit or proportional cycle time. The essential need for "flow" is that the individual operations into which the whole is broken shall have as near as possible a unit time for performing those operations so as to achieve a steady load. Accordingly, although automation may well be built on to an existing first order, this can only be done after the most careful operation-by-operation reviews. Indeed, it has frequently been found that the first order is basically unsound for the second order.

Fig. 4 illustrates a newspaper machine installed by *The Times* about 1850. It was based on the feeding of individual sheets by separate operators and subsequent collation also by separate operators. Fig. 5



CONTINUOUS WEB MACHINE
FIG. 5





Fig. 6



OLD/MODERN SOLDERED/SEAMED CAN
FIG. 7

shows a scheme of a continuous web or reel-fed machine installed only a few years later wherein the product was printed on both sides, folded, cut and collated completely automatically. The essential difference was the new form of material available and, therefore, a basically new first order of division for re-integration.

Paper was itself invented by the Chinese in the first century A.D. and was made by hand beating and pulping the fibres and setting and drying it in sheet moulds, and this continued right up to the beginning of the 19th century. Then the Fourdrinier Brothers developed the invention of Louis Robert who, in 1799, had made a paper making machine for continuous production. They used the engineering skill of Bryan Donkin and by the 1830's some 30 or 40 machines had been produced. The essential element or new thought here was a continuous moving web to carry away and process the milled pulp. Fig. 6 shows the machine as built in 1839 and indicates the steps taken in integrating into a continuous process the separate operations which had hitherto governed paper making. It also indicates the basic change from discrete sheets to the continuous web which was in its turn the basic requirement for the change of approach to newspaper printing.

Oddly enough, contemporarily with this the Frenchman Nicholas Appert had invented his method of food sterilisation. This was adapted to the use of cans and developed into a serious canning operation, again by Bryan Donkin. Thus was born the canning industry, and the pressure of demand

resulted in considerable first order mechanisation. It was not until the close of the century, however, that the container was redesigned so that second order mechanisation could be adopted. Fig 7 shows the product change, while Fig. 8 shows the process integration which this has made possible.

problems arising from extending automation unit time cycle

Hitherto, the general pressure of industrial demand has resulted in the second order of mechanisation being applied to many products which are basic—like paper, board, steel sheet and strip, wire, cable and so on. Most of these involve massive manufacturing undertakings, though the complexity is more in detail than in the multiplicity of operations.

The present trends in automation of manufacture are more concerned with the conversion of these basic materials already automated. Applications to multi-operation components like screws and similar items have been made since the early part of this century by moving tools successively to the work as well as *vice versa*, as in single and multi-spindle automatics. In such cases the operation time need not be equal since each operation is sequential. However, to the extent that one tool only is operating at a time, the


rest of the tools are idle and though such automatics represent an entry into the second order of mechanisation, they do not achieve full tool utilisation and thus fall short of the ultimate. To achieve this we need to move the work progressively from tool to tool, so that ideally all tools are working all of the time except that part consumed in work movement or transfer.

For this to have the greatest effect, the division to individual operation needs to be on a constant unit or proportional cycle time. This operation cycle time being the sum of transfer time and work time, it follows that any particular transfer problem may be adjusted by appropriate allowance in the next succeeding operation work time. Alternatively, it may indeed be made an operation in itself and thereby given the full cycle time to carry out its function.

The relation between feed time and work time largely determines the extent to which automation can secure greater equipment utilisation.

in-process work reservoirs and banks

Suppose we consider a single press operation where each stroke is manually controlled and takes one second to complete. Suppose the component takes the operator three seconds to pick up, orientate, and



PROCESS INTEGRATION
FIG.8

deliver to the dies, then depending on the degree of synchronism and overlap achieved by the operator, the maximum possible production will lie between 15 and 20 per minute. If now a hopper or magazine is used which, because of sequential selection or separation, orientation or presentation, and transfer or feed, can achieve these functions in something better than one second, then by integration and synchronisation with the press an actual production of 60 per minute may be obtained.

Since the ejection of work from presses is usually controllable, in many cases an inter-operation transfer is all that is required in linking a number of operations so that almost all the automation gains are of a high order. Machine utilisation may go up some hundreds per cent., the attendance of human operators is vastly reduced and, of course, inter-operation work in progress is drastically reduced. Fig. 9 shows a modern transfer press where a large number of operations are carried out on a common

bed and where the component is progressively fed from operation to operation. This represents what may be done with relatively small components and achieves the maximum of integration. To achieve a similar result with larger components separate presses are frequently joined by conveyors or transfer mechanisms, as in the multiple press operations in car body production.

If we now take a machining operation where, in the overall floor-to-floor time of four minutes, the unload, feed and load time is 15 seconds, the most elegant use of automation will only marginally increase equipment utilisation. However, the greatly reduced requirement of human attendance does confer on equipment utilisation the advantage of more certain and consistent cycle time achievement. The unit or proportional cycle time is the overall potential of the automated plant as a whole. Its three main fractions are feed time, work time and down time, the last both scheduled and unscheduled.





Fig. 9
Modern transfer press



MOSCOW BALL BEARING FACTORY
FIG. 10


If operations, which individually have substantial magazines or reservoirs feeding them, are joined into an integrated line we still retain inter-operational flexibility.

In most press work operations equality of cycle time is not difficult to contrive, while unscheduled down time should not be significant. Accordingly, direct coupling for a convenient number of operations is not difficult.

In machining operations it is frequently necessary to duplicate or multiply certain operations to achieve an overall uniform cycle time. In such an event the product may be delivered from duplicated operations into a common feed to the next operation, or alternatively it may be fed into a reservoir or inter-operation hopper. This, however, is only satisfactory when the reservoirs themselves are properly designed both as to position and capacity in relation to the risk of unscheduled down time of one kind and another. Accordingly, the extent to which one operation eject may be the feed to the next, and the number of such connected units, will be determined by the estimate, operation by operation, of this risk. If the risk can be made insignificant, then the production advantage *per se* will improve with the number of connected units. If, however, there is a significant risk operation by operation, it is clear that

for any combination of operations the overall unscheduled down time will lie somewhere between the sum of all the risks and the individual greatest. Obviously, this must be reduced as far as mechanics and tool life will permit. However, this must remain a calculated risk and to minimise its overall effect, use must be made of reservoirs and/or banks, which may provide the flexibility needed between the respective sections of an automated whole.

In the case of the automated ball and roller bearing factory in Moscow, the incoming raw materials are forgings or tube from which the inner and outer races are made, the finished balls or rollers and their respective cages. The problem in any single product consists of making two components and then assembling them with the balls and cages. The overall cycle time on the ball bearing line is an actual 200 per hour and on the roller line 130. The operations involve turning and marking, heat treatment, grinding and assembly, as well as comprehensive cleaning and inspection needs. The individual operations clearly cannot be brought to equality so they have to be balanced by factor multiples, including an overall balance of estimated unscheduled down time. Fig. 10 shows the general layout and indicates the way in which hoppers or reservoirs interpose specific operations, and how those operations are performed with



multiple equipment. Such an arrangement not only bridges the different actual times of single machines, but provides an additional flexibility against the effects of unscheduled and scheduled tool changes.

The other major consideration in selecting the number of operations which may be joined together is, of course, the scheduled down time. The extent to which changes of products are required and the frequency of change will dominate this aspect. Experience in almost all cases of automation has shown that the use of banks or reservoirs and the limitation of operation integration to reasonably manageable sections is imperative, and especially where variety changes have to be provided for.

In the case of the ball bearing factory these are essentially reservoirs. In some cases the inter-process material amounts to a bank.

Fig. 11 illustrates the use of banks to provide mass flexibility and maximum variation. The example shows modern steel sheet production and indicates the progress from a common ingot to the highly variable end product. The work done between each bank comprises many operations and is highly automated. The discontinuity at each bank provides manufacturing flexibility and relative indifference to unscheduled troubles at either stage affecting the whole. What is, however, much more important is that these breaks in the continuous line provide the means for the orderly provision of end product variables. In this case the stock of product between the different sections is truly of the nature of a bank. It represents the premeditated cessation of an undertaking at a given point and an accumulation of goods from which on some future occasion a further start

will be made. It not only provides an overall system which can be reliably planned or predicted, it provides convenient points for bulk accounting and the preparation of digestible operating statements.

The provision of a reservoir, however, is usually to be taken as an in-motion moderator. This is the case with the ball bearing factory.


Fig. 12 shows the mechanical connection of the many operations of can making. In each case there are in-line reservoirs or moderators in order to maintain steady flow, while at the ends of each line a bank is formed. Although in a balanced plant the product of each section must be substantially equal, the banks mitigate the evils of unscheduled down time and permit effective planning.

Fig. 13 shows the layout of a popular car cylinder head and valve guide assembly line and shows the points at which banks are provided and where quality inspection is carried out. The strategic positioning of control points will be noted. The cycle time is 0.8 minutes or effectively 60 per hour, and the reservoirs are again essential in order to ensure that the effects of unscheduled down time, or deficiency, may be evened out. To be effective the reservoir must start with a content below its maximum capacity so that it has "product" to give if its supply dries up and capacity to hold if its output cannot be taken. Such reservoirs may be manually regulated from control desks where the pattern of down time behaviour may be seen, or may be automatically controlled by high/low level controls or gates.


A plan adopted for cylinder head and block production for commercial vehicles, where the output required is much lower, is indicated in Fig. 14. In this



(a) SHEETS PREPARATION




(b) END PRODUCTION



(c) CAN LINE

CAN FLOW LINES

FIG. 12



FLOOR LAYOUT FOR CYLINDER HEAD & VALVE GUIDE ASSEMBLY

FIG. 13

case three separate lines are required and provide for production on cycle times of from 10 minutes in the case of the fastest, to 20 minutes in the case of the slowest. In this application there is provided room on the conveyors for three components between each operation. This is clearly sufficient to provide for normal tool replacement and because of the time cycle the components are manually progressed.

The proper choice of banks and reservoirs is economically as important as the technical choice of equipment. Reservoirs are generally chosen on the analysis of well designed work study, while the choice of bank policy will usually depend on longer term considerations and may well be the subject of study by statistical techniques and operational research.

Reservoirs or banks necessarily imply hopper feeds when flow is to be restarted. Many small components may be stored in random hoppers from which they may be allowed to move by gravity, rotational or vibratory energy into means for orientating for correct relationship. Larger and more complex elements may need to be banked or reservoirised in orderly form for re-feeding. Staggered, tiered or looped conveyors with suitable in and out transfer devices are usually appropriate.


The major applications of the second order of mechanisation in manufacture have so far been directed toward the integration of the various

operations involved in a single component. Some applications, like the ball bearing project, or can making, have, however, been made in the field of assemblies. The problems are usually sufficiently complex to justify their being considered quite separately from the automation of the component parts. In most cases separately made components will be brought to meet the major element appropriately during its manufacture.

In general, however, the feeding of mating parts is arranged from banks, when complete flexibility of supply is attained. In these applications a more elaborate system of control is required to ensure that the main stream of operations can selectively call for sub-components as and when needed. Suitably triggered gates are usually all that is required, though the need for control is essential.

In the Russian automated ball bearing factory there is provision for selective assembly of the elements according to their position in dimensional tolerance. Obviously, this presents no difficulty once the components are appropriately gauged and directed into respective dimensional banks and so long as appropriate demand signals can be initiated. Similarly, with a proper grading of the balls or rollers a geometric distribution of dimensions can be readily obtained.

An equally interesting application to multiple parts is the assembly of a talcum powder tin (Fig. 15). It



ENGINE BLOCK & CYLINDER HEAD LINES

FIG. 14

consists of a bottom, a body, a breast or top, an inner closure and an outer closure. Usually the first two are dealt with by a sequence of automated operations which completely make the body and accepts the bottom from a magazine for attachment.

The top assembly is usually produced on automated lines producing each element which meet at an assembly point for completion.

problems of control

The forms of control to be adopted will have four main functions :

- (a) to regulate and maintain flow in conformity with line requirements;
- (b) to secure tool and component relationship while being worked upon;
- (c) to protect the equipment and tooling from damage due to faulty transfer or improperly completed work; and
- (d) to audit the performance of the respective operations and maintain the quality of the product.

For all these aspects control equipment needs to do four things :

1. to detect or recognise a situation;
2. to express it in actionable terms with respect to time;
3. to signal or initiate an action;
4. to carry it out.


Detection of almost any characteristic is nowadays relatively simple. Physical reactions from touch or contact, from seeing, or interpreting colour, embossments, fluorescent codes, or light interference, from nearness or proximity indicated by mass or inductance or various applied codes, are all capable of electronic amplification and discrimination into actionable decision.

There is likewise no shortage of suitable servo mechanisms which can apply the power required to carry out the instructions signalled.

The time relationship on a line will usually be sequential whether this merely be from operation to operation, or whether this sequence is supplemented by other audits.

In every case the functional performance of the servo systems has to be interlocked with, or part of the system.

In the case of quality a different circumstance arises. Where trends are being detected, stop or warning signals will be provided at the unaccept limit. There may be, however, random components which are unacceptable which do not reflect a line failure. Such components may well be permitted to pass through the line without interruption so long as they are rejected at the end. In such cases the line may have a built-in and timed memory so that a signal at detection will secure ejection at the end. Alternatively, the component may be made itself to be the memory by being given a code on inspection which a device at the line end may observe and reject.



TALCUM POWDER TIN
FIG 15

These various devices may be sequentially quite automatic as they are in very fast moving operations. In many machining operations it is more practicable to have a certain amount of direct manual initiation, or a form of signalling to central control centres or desks where decision switching takes place. The inflood of such signals to recorders is frequently valuable for the study of operation or sequence improvement, and the better use of reservoirs and banks.

Clearly the control system meets the separate needs of flow, of position, of protection, and of quality, and at the same time integrates or interlocks them all together.

The audit of quality should be no more complicated than that essential to secure an acceptable product and a minimum of unscheduled down time. In many cases certain aspects may be inspected on a suitable sampling plan at the banks, while other features may have built-in inspection as specific operations. The more advanced the order of mechanisation the more imperative is built-in quality control, for after excessive down time, the fatal fault can be the high speed production of unusable parts.

The study of quality for accept/reject or for trend will provide for the study of tool, material and control reliability. The traditional method of cost reduction in the first order of mechanisation is the increase of operation speed to reduce the individual floor-to-floor time. With the second order of mechanisation, individual operation speeds give way to reliability so that a tool which will cut fast is less important than one which will keep up to line speed for a longer time. In the same way, materials variations which can affect consistency of performance must be eliminated.




Fig. 16(a) (left)

Fig. 16(b) (below)




Fig. 16(c)

economics

The question of capital cost in the sort of automation I have been considering, calls for very careful study. Brief reference was made earlier to Fig. 3, where we see the very attractive possibilities at the early part of the curve and the rapidly diminishing returns thereafter. In practice this curve will never be a smooth progression for a given product, but will effectively be substantial production returns for substantial steps in capital investment.

If we consider again the example of the press operation which became raised from 15-20 per minute to 60 per minute with considerable reduction in operator attendance, we see that this was achieved with the same press and the same tools. All that was added was a hopper or magazine and perhaps a timed infeed and eject mechanism, together with perhaps one or two triggers and limit switches. At the outside, 50% more in capital cost resulting in 400%

prod
same
opera
tion
work
Un
in m
speci
integ
and
tion
so th
neces
given
Mach
even
need
cann
adju
swar
impo
Be
altog
a fu
press
a fas
much
select
mach
very
really
capit
a he
break
auton
is us
cienc
stopp

tren
W
futu
Cl
stand
factu
neces

product increase. From this point there is also the same order of improvement by integration with other operations, more speedy throughput, higher production of other capital resources and vastly reduced work in progress.

Unit machines built up into line production can, in many cases, save the expense and inflexibility of special purpose machines. Thus, investment in the integration, in the special tooling, and in the transfer and control gear is the major cost. Increasing attention is being given to unit construction of machines so that integrated lines may be built and where necessary rebuilt. So, too, is increasing attention being given to operating convenience or ergonomics. Machine to machine convenience is important, but even more important are those aspects of human needs without which even the most automated plant cannot work. Safe and easy access for tool removal or adjustment, for lubrication and maintenance, and for swarf removal and cleaning, are perhaps most important.

Beyond this sort of automation the order changes altogether. It would probably be possible to secure a further increase of, say, 50% in the case of the press operations if a great deal were now invested in a faster, more robust and more accurate press, and much more elaborate means of hopping, pre-selecting, pre-orientation, feeding and so on. In machining operations it is very doubtful whether even very expensive special purpose plant would make a really significant improvement. Furthermore, as capital investment increases so does down time become a heavier burden. With machining operations the breakeven usually comes much sooner and once automated, the most profitable development thereafter is usually to be found in patiently weeding out inefficiencies and especially the causes of unscheduled stoppages.

trends in machine tool and process development

What are the possibilities and trends for the future?

Clearly, the most obvious will be in the direction of standardising more and more components of manufacture, so as to bring them into the volume class necessary for the second order of mechanisation.

We must, however, have constantly in mind the basic need of an appropriate foundation in the first order. Since we know the devastating effect of the law of diminishing returns, we may well see whether a radical change of view may not uncover the possibility of a new scale for the curve. Figs. 16(a), 16(b) and 16(c) show three first orders in steel sheet production. Each was no doubt brought to a high degree of perfection in its own class, and each change required a revolutionary change of basic operation.

The possibilities from original thinking of this kind are surely the most exciting and will prove the most rewarding aspects of the production horizon. More and more machining operations will be displaced by metal and material forming operations. Massive developments are likely to take place in forging, press forming and extrusion applications, while the possibilities of dynamic or high energy material flow, as in many thread and gear rolling and so-called flow turning operations, are as yet barely touched. Furthermore, in many products metals will be replaced by plastics which are much less likely to be cut than formed.

Modern materials for machine construction open up completely new parameters of power application. The power available in the five stands of mills in Fig. 16(c) is no less than 18,000 h.p. and it reduces strip of approximately 0.1 in. thickness, to 0.01 in. at an output speed of 5,000 ft. per minute. In the metal forming and extrusion fields, presses rated in thousands of tons will become commonplace.

These are the prospects, the meeting of requirements, the challenge. In the field of review, the satisfaction of demand itself demands economy: economy of effort and efficient deployment of skill, economy of material and economy of time. Since the beginning of the Industrial Revolution, production has grown up. If one regards the history of invention over the period, it might be suggested that the period was that of the Industrial Revolution.

It is certainly the task of manufacturing production to apply what is revealed. It may perhaps say with Browning —

*"Grow old along with me
The best is yet to be."*

acknowledgments

I am indebted to the following for the use of their examples:

Associated Equipment Co. Ltd.
Bryan Donkin Co. Ltd.
Metal Box Co. Ltd.
L. Schuler, A.G.
Steel Company of Wales Ltd.
Vauxhall Motors Ltd.

ECONOMIC ASPECTS OF AUTOMATION —

Internal to the Firm

by A. A. JACOBSEN, M.I.Prod.E.

selection of case histories

The number of case histories that could be written on the introduction of automation is very large indeed and careful selection to illustrate the theme of this Conference has been necessary. On the one hand we have some authorities arguing that all the elements of the fully automatic factory are discernible in the Stone Age flint factories and on the other we have the specialised study of the last decade, such as the Tinker Toy project. In this case the U.S. Navy Bureau of Aeronautics instituted a special study at some considerable expense to establish the economics and the technical practicability of automatic assembly of electronic units. Three broad comparisons were made and the figures were published. The results of

this study were expressed under the following headings:

- (i) cost of production of conventionally designed unit produced by conventional means;
- (ii) cost of production of unit redesigned for automatic assembly but produced by conventional means;
- (iii) cost of production of unit redesigned for automatic assembly and produced by automatic assembly.

Neither the flint factory at Grimes Graves nor the Tinker Toy project will serve our purpose today. The first was not well documented and the second, although well documented and valuable, was too remote from the pressures of every day industrial life. Accordingly case histories have been chosen which demonstrate typical situations in manufacturing organisations operating under representative conditions in recent years.

ethics of case histories

The writer of any industrial case history is in much the same position as a doctor taking the case history of a patient. His aim is to draw out and set down all relevant facts accurately, so that all who refer to it will have a true picture from which to draw conclusions and on which to base subsequent actions. Doctors and patients vary considerably. The doctor may not fully understand the patient. He may not have been present at previous operations. The patient is complex and always unique and often has a bad memory. The doctor may fail to draw out one or more important facts and he may get inaccurate answers from the patient.

When he is involved in the treatment and in the interest of the advancement of science issues a Paper

★—————★

A Paper presented to the First British
Conference on the Social and Economic
Effects of Automation, at Harrogate, in
June, 1961.

★—————★

and publishes the case history, then it is only fair to the patient not to disclose her identity. If she is still living her health may not be improved by learning of her true condition. If she is dead, then her relatives may be even more deeply concerned.

Finally all case histories are taken in good faith, with the first object of helping the patient, the second of instructing the taker of the history and the third of increasing the general pool of knowledge.

These case histories have been prepared on just these three principles and I shall ask your understanding for any omissions or misinterpretations that may occur.

the case histories

history no. 1

Continuous Production. The basic process is the spinning of wire. The degree of automation is increased by adding a specialised monitoring device.
Wire Manufacture.

history no. 2

Mass Production. The basic process is the assembly of a small electro mechanical unit at a rate of about 30,000 units a week. A number of operations are made automatic but adjacent and linking operations are not all made automatic.
Light Assembly.

history no. 3

Large Quantity Production. The basic process is the making of pressings for a precision mechanical assembly. The press operations are automated. Other operations are not made automatic. The rate is about 24,000 units a week.
Presswork.

history no. 4

Small Quantity Production. The basic process is the turning of batches of components on specially designed lathes using automatic control to give high repetitive accuracy. The rate of production is about 750 sets of parts a week.
Precision machining of medium size turned components.

history no. 5

Manufacture of Single Units. This stretches the definition of automation to the limit and deals with the introduction of optical measuring devices to any engineering works.
Heavy Engineering.

CASE NO. 1

The process on which this history centres had been running for many years. An output of tens of thousands of feet of a specially spun steel wire was obtained from a battery of several special purpose machines, each with a number of spinning heads corresponding to the number of layers of wire needed. The machines were all old and scheduled for replacement within three years with more advanced equipment then under design. The supply position was such that a night shift was essential and this in turn necessitated the use of male labour. Although the operation was automatic once the machines had

been set, custom and practice had established a condition whereby one operator was in attendance on each machine; the technical basis for this arrangement being that a break undetected in one strand of wire resulted in either an expensive quantity of scrapped material, or if missed at a later inspection stage, failures in service. Thus the operator's continuous duty was to monitor the strands of wire feeding on to the main core.

The cost of production was known and the specific problem was to obtain a reduction of cost in the shortest possible time without any substantial capital expenditure, in order to keep the price of the finished article competitive. The design was proved and any change was out of the question, and as the process was fundamental the only practical solution was to reduce the cost of the labour, by making the process fully automatic.

From the factory's point of view this would be an attractive approach as there were a relatively large number of men employed on these machines, earning a high bonus for a low real effort.

Accordingly the problem was reviewed and a study was made of the engineering problems involved in making the process automatic.

Previous attempts to use photo electric cells had failed due to the fine gauge of the wire, and no practical alternative had been found. However, a nearby company specialising in control systems was consulted and the problem was examined by an expert who was conversant with all the latest developments in sensing heads and the use of modern electronic equipment. He was confident that a solution could be found and in a very short time a proposal was put forward. This was proved in a laboratory as being practical and a cost estimate for the equipment was drawn up. This showed that for a capital cost of less than £2,000 all machines could be equipped, and the probable saving in labour could be two out of every three persons employed. The overhead increase in spares and maintenance was estimated at less than £250 p.a. Thus, allowing the equipment a life of two years the gross saving would be not less than £10,000, provided that at least six persons were released from each shift.

Authorisation was given for the work to be commenced, and within six months the equipment was ready. It was installed without difficulty and without interruption to production. Discussions had taken place with the labour representatives and established that the men released would be moved to other jobs; this transfer worked smoothly. It is relevant to this study to note that in fact previously the operators were not fully occupied, but that all managerial attempts to negotiate a redistribution of duties based on work studies had failed, due to the technical point that there had been no change in the method.

The standard costs were revised, the overhead budget amended, and it was immediately evident that the estimates of saving would be achieved.

The most interesting effect of this successful application of an automatic method of control to a process was that the operators remaining on the machines successfully negotiated a bonus earning well above

that obtained elsewhere on the factory site for equivalent effort. The argument advanced was that the management was making a great saving in introducing this change. They were also, as the "first in, last out" principle had been used, the longest served operators, and when after two years this production section was closed down and these men were moved to other jobs yielding lower bonus, they felt badly treated. By the very nature of industrial growth these new jobs were products planned to run for a long period and in the end the men secured concessions in bonus and wage rates which would not normally have been granted. This was because their attitude reflected in the relevant negotiations and also because the management felt a sense of obligation to men who had not obstructed the introduction of a new process, and who had subsequently suffered a loss in their pay packets.

CASE NO. 2

This study deals with an assembly line producing each week several thousand small electro mechanical assemblies made up from laminated cores and windings.

Production had grown with the demand for the final product from zero to 10,000 a week over a period of 10 years. The firm took an optimistic view as to future prospects and considered an output of 30,000 units a week as a foreseeable requirement within a few years.

This particular assembly accounted for nearly one-fifth of the end product cost, and as the industry was highly competitive it was vital that the lowest possible manufacturing cost compatible with the efficient functioning of the unit should be achieved.

The position was examined by the firm's senior production executives and after a preliminary examination they were given the broadest possible terms of reference to draw up a scheme for the manufacture of the unit, redesigning where necessary, and using new equipment regardless of the plant already in service. The new unit was to be made on the same site and by the same labour.

In due course the design for cheaper production was completed and proved electrically. Where possible production techniques were also proved, and on the basis of all the information obtained the capital cost was estimated and also the cost of production of each unit. It was apparent that a saving of at least 15% would arise and as the extra production was required authorisation was given for the work to be put in hand.

This firm organised on the basis that a specialised production engineering department handled projects of a major nature. The local management of any factory site was responsible for running the production, and for engineering any moderate projects. The actual introduction of a new integrated assembly line with several improved processes was a joint exercise, with responsibility for successful operation of the site falling on the local management.

The basis of the new assembly line, however, was not full automation. The product design had been simplified and a number of consecutive operations

had been made automatic. The movement of parts between each working station was controlled by a conveyor. A large labour force was needed to load and unload the assembly fixtures and perform the various manual operations. Even so, it represented a substantial reduction in the number of people required for the original line.

With respect to the overall principles involved the production engineering department had worked with a ruthless regard for efficiency. The first principle was that work should flow non-stop from operation to operation; the second principle was that the distance travelled by each piece of material should be the shortest attainable. The final principle was to co-relate all movement to one conveyor line, so that if one stoppage arose at any point the effect would be instantaneous throughout the shop and a tremendous incentive would exist both to deal with the problem immediately, and in the long term to prevent any repetition of the trouble.

The local management team understood the reasoning behind this approach and considered it to be the correct basis for planning production, but they were apprehensive that the human problems would be troublesome and might even prevent the cost estimates from being achieved.

In due course the equipment started to reach the assembly plant where a suitable shop had been laid out in readiness, and installation proceeded in accordance with the methods and principles planned. The development period went by without any significant difficulty as the project had been very well thought out, and it is necessary to record at this point that complete success was achieved in spite of the problems which are referred to in the following paragraphs.

The operators settled down to the new line in all respects except to complain about the noise from the machines responsible for making the detail parts, which were placed next to the assembly point. The arguments grew so frequent and fierce that the noisy machines were removed from the shop and the parts were moved in skips to the assembly line.

Then a mechanical failure occurred on a complex transfer machine designed to feed the line on a continuous basis. The stoppage that ensued resulted in a return, at least for this machine, to the philosophy of holding a reserve of stock parts adequate to maintain assembly production for the period of any probable repair.

Production was nursed up to the 80% level using the operators from the old line. These operators were accustomed to high bonus earnings arising from a high working effort, and as it was not practicable to lower earnings too radically on transfer to the new line, periods arose when certain operators would get paid very well, but would be working at a below average effort. When, as the line speed was advanced, the effort was increased these operators expected more payment. The very close interrelation of all operations made the work study engineers' job of balancing the labour load at varying levels of production extremely difficult. One or two of the operators then grasped the idea that if only one small section

stopped, a total stoppage of work would follow throughout the shop. Thus those who saw a grievance with respect to their earnings were able quite easily to bring a dynamic type of pressure to bear on management. The earnings in this shop were already considerably higher than those elsewhere in the works and after taking positive steps to ensure that really good industrial relations existed in the department, changes were made to the set up which reduced the interdependence of each section of the line. Further where possible, conditions were established so that some operators could determine their own working pace without affecting the balance of the whole.

All this took place over a period of years, and it is pleasant to be able to report that in the end the estimates were achieved, and that very happy industrial relations prevailed and that both the local management and the production engineering department grasped the need for working to each other's principles to the fullest possible extent.

The history should end here but there is one point that should be made. As the project was slowly translated into reality other problems on other products beset the production engineering department and likewise the local management, so that although the original project was really dated perhaps two years after conception, the fresh possibilities were not properly referred to the policy making levels in the firm. In consequence for two or three years the rate of development on the replacement assembly and associated techniques was extremely slow.

CASE NO. 3.

This study deals with the situation which arose when it was decided to replan the production of a sub-assembly made from a number of formed metal pressings. The accuracy with which the pressings were made controlled the smooth functioning of the sub-assembly and this in turn was an important feature of the final product. The Sales Department claimed that competitors had an advantage as smooth operation of the unit was a strong selling point.

The sub-assembly had been produced for several years at a rate of about 12,000 units a week using separate presses for each operation on each component used. Assembly was relatively straightforward but involved a certain amount of hand fitting.

The terms of reference for the change of production stated that an output of 24,000 units should be achieved per week, accompanied by a substantial reduction in cost. No reference was made to the need for an improved engineering product.

The proposition put forward and accepted called for the retention of the existing design of the unit and for the use of a transfer press. The tools were to be supplied by the firm making the press. The blanks for feeding the multi-station press were to be taken from standard sheet produced to commercial limits and made in a separate press. The multi-station press was to be given five separate sets of tools so that each piece of the sub-assembly could be produced in turn.

No special consideration was given to the problems of feeding the presses or stacking the resulting production. It was also considered unnecessary to plan the assembly in detail.

Although the capital cost was high it was believed that a considerable saving would result in labour and work in progress and the Sales Department, knowing that a transfer press was to be used, expected an improvement in consistency of the product.

In due course, the press was delivered and development began under production conditions. No special difficulties were encountered with the press or the tools, but the points that emerged from this application of automation were typical of many installations.

The work in progress turned out to be far greater than had been forecast. Many more skips were required to hold the total quantity of production and separate provision had to be made for vertical stacking of the skips. This was due to the need to produce five different parts from the press. A run of adequate length was necessary to keep setting time within proper limits, and if this was established at seven working days, 35 days total stock was needed for five parts. Also, because of the possibility of breakdown, 20 days stock had to be held in reserve.

The activities of cutting the strip from sheet, feeding to the blanking press, stacking from the blanking press, feeding the transfer press and stacking production from the transfer press accounted for four more men than had been allowed for in the original estimate.

The main problem arose from the mistaken understanding that the material used would be supplied in consistent batches from the rolling mill. The material as it was made from a wide sheet varied considerably, in fact almost from blank to blank, and as the tools could only be preset to give an accurate form for one exact thickness the resulting pressings were inconsistent.

The net result was that the hand adjusting previously used had to be reinstituted on assembly and some 10 extra persons were needed to ensure the required rate of production. This extra number of persons very considerably reduced the saving in labour resulting from the use of the press.

Finally, the Sales Department were surprised to learn that a more consistent product was not being achieved as a direct consequence of the new automatic method.

Subsequently and only after a much attenuated development period proper facilities were established to reduce the labour serving the presses, and the material was obtained to the correct degree of accuracy. The assembly labour was reduced and as the whole section settled down and inspection and setting techniques improved, better parts were produced resulting in a much smoother operation of the sub-assembly. Thus in the last analysis this project was successful, but only after a very heavy and largely unnecessary expenditure had occurred on development due to an inadequate engineering examination of the problems involved.

CASE NO. 4

This study deals with the commencement of manufacture of an entirely new product for the firm concerned. The design called for a unit built up from a dozen steel castings weighing from 4 lb. - 12 lb. each. The castings had to be machined to very fine limits, both along the axis and radially, and for technical reasons a material with poor machinability had to be used. The firm had no previous experience in machining parts of this type.

The production engineers were in difficulty from the commencement, for the sales forecasts for the new product were completely hypothetical. The major preoccupation was to avoid any very heavy investment in capital equipment until the sales potential was proved, and a second objective was to keep the highest degree of flexibility possible in case design changes were found to be necessary. The first sales target announced was 200 units a week, and the preliminary investigation was based on this figure.

The proposition decided upon was to use well designed heavy duty turning and boring lathes fitted, where necessary, with copying attachments and micro switches. The various operations on each piece would be controlled, that is, stopped and started or positioned electrically, a special control board being used to give the instructions in sequence. The arguments in favour of this type of machine were numerous, and it was felt that the repetitive positioning of slides and cutting tools by the hydraulic and electrical systems would result in the consistent achievement of the exact limits needed, in much the same way as the normal automatic lathe operates. Thus, the human operator with his inconsistencies would be removed from the scene and full control delegated to the machine itself. It was further reasoned as a result of this delegation that drawing limits which could not be maintained on a manually operated semi-automatic would now be achievable. This belief led to the elimination of several finishing operations which would otherwise have been added.

It was decided to proceed with the appropriate number of machines to meet the sales forecast. After the machines had been ordered, the sales targets were revised upwards to 400 units a week, and as the manufacturing course had been set more similar machines were called for. Later, the Sales Department again revised the forecast and called for 750 units a week, and although this quantity warranted a different approach, the capital investment in the existing machines was so high that they could not be discarded and replaced by different equipment, in spite of difficulties which were arising from their use.

At this stage it is interesting to note that normally this firm planned all new projects on the basis that the equipment provided should be adequate to achieve economical production and sales targets on a day shift basis. The inevitable rise in requirements that stemmed from production at the right price could then be met by the use of a night shift and if the growth continued, the period during which night shift handled the increased demand was used to

obtain radically improved equipment needed for the next manufacturing period. Unfortunately, in this case, due to the heavy capital investment required, this line of thinking had to be abandoned at the outset of the project.

The machines were delivered and a long production development period ensued. The material suppliers in this case were not able to maintain their original expectations with regard to the limits on the castings, and extra material had to be removed by the machines. The cutting problems and swarf clearance problems were greater than had been foreseen and each operation had to be drastically replanned. Simultaneously, mechanical and electrical breakdowns confused the general picture, but all concerned worked steadily to achieve the originally estimated times and limits. This initial training and development period was far longer than had been expected and in due course stock was taken of the situation. For the battery of machines twice the predicted number of setters was required, and the down time due to setting was doubled. The number of operators was double that required for a conventional set of automatics, the rejection rate was far above that commercially admissible in spoiled material and rectification costs were also very high. The spares for the machines were costly and maintenance costs were high and most serious of all, in spite of day and night shift, the output levels were not being achieved, so that a sub-contracting programme on to orthodox machines had to be instituted. This was in spite of carefully organised inspection procedures and incentive schemes.

During this development period it had been vital to keep to the very close engineering limits for the components. As the product was being proved in service it was possible to increase several of the tolerances and this was done at this stage, thus reducing the rejection and rectification costs.

Ultimately the sales forecast of demand proved to be too high for reasons outside the firm's control, and the management was faced with making a completely fresh approach to this project. The fact that the lowest possible capital investment had been made, and that the machines were flexible enough to be used again, more than justified the production engineers' approach.

One aspect of this application was that the machines being used were themselves undergoing development: at the time of ordering it was believed that the machines and their control systems were fully developed. The other and more interesting aspect is the illustration in this case of the dilemma which can often arise when a new but untried process is introduced to a factory. The process may be advanced and therefore regarded with doubt by all concerned with operating it. The management has to induce an attitude that enables the personnel to overcome all the problems, if necessary over a lengthy period, and in time becomes conditioned itself to dealing with the problems. This leads to a situation where a process which may not be satisfactory is made to work by

sheer determination, when in the last analysis it would be better to recognise the truth, although the consequences for those responsible for recommending the process may be serious.

CASE NO. 5

Reference to the definitions at the end of this Paper will explain why this last case history has been included. Automation can exist with respect to a single operation and even only to the control element of that operation. The moment a function in any plant normally carried out by the human muscle or brain is delegated to a piece of equipment, then we can say with accuracy that we are increasing the general level of automation.

The setting for this very simple and general story is one of the Midlands cities immediately after the last War. The management had decided to establish a heavy engineering works capable of producing a wide variety of machinery, most of which demanded a high degree of precision bearing in mind the size of the plant involved. The local labour force on the site was to be utilised to the fullest degree in spite of the fact that it was accustomed mainly to the rough machining of billets and steel plates.

A very thorough review of all the factors involved in production had been made and all the important features had been dealt with, including sales outlets, product design, suitable machinery, cranes and equipment and sources of supply of basic material. A strong inspection force had been established to ensure the quality of the work and the foremen who had been transferred with the existing labour had adjusted themselves, not without difficulty, to surrendering some of their powers to the new authority.

It was in this setting that the management decided to survey the country for the latest optical devices for measuring and setting of machinery. A survey was made and authorisation was given for the purchase of measuring equipment and optical setting devices for the machine shop, the assembly department and the inspection department. For the machine shop an alignment telescope was supplied, suitably adapted for the quick setting of the boring bar steady relative to the spindle of the boring machine. The assembly department and the inspection department were provided with optical devices which, through the use of prisms, enabled right angles to be measured with great accuracy, and parallelism of surfaces to be established. A suitably obvious show case was made

routine for the introduction of automation

	ACTIVITY	STATEMENTS (Reflecting or controlling activity)
Stage 1	Original Production Situation Situation at start of history	Routine cost statements Current cost of production from original situation.
Stage 2	Forecast of firm's requirements Recognition and appraisal of situation and preparation of terms of reference as basis for action	Terms of reference (basic) Outline of engineering solution. Forecast output limits. Approx. capital costs. Time planning. Approx. unit costs.
Stage 3	Assessing profit and authorising Planning whole proposition with detailed estimates. Preparation of sanctions and instructions.	Terms of reference (Budgets and Instructions for Implementation) Budgets cover: engineering; capital; ancillary equipment; development and start up costs. Unit costs.
Stage 4	Implementation of automation Covers engineering; production of equipment; development; installation and start up: taking production to final stage.	Routine statement of cost of implementation Normal accounts statements against budgets
Stage 5	Final production situation Operation of the automatic process on a settled basis.	Routine cost statements Final cost of production arising from automatic process.

for the equipment when not in use so that all concerned would be reminded of the existence of the newer methods of measuring.

It must be reported that in a large sense this introduction was successful. Some time was wasted learning to use the new equipment and often the traditional method was employed in preference. It did achieve one object, however, in that it helped to inculcate a new attitude towards the problems of measurement and accuracy in the newly formed works, and provided a stimulant in thinking with regard to this aspect of production which proved valuable in later years.

The point then, in this case history, is that a change in a method which constitutes a radical departure from previous practice may be worth while in itself for the effect it has on the thinking throughout the whole organisation. Its value cannot be measured in savings per piece produced, and the observer cannot any more than the management make a real assessment of the effect achieved.

These case histories were selected from a large number with the object of illustrating typical effects which may be caused by the introduction of some degree of automation. In preparing this Paper and reviewing the results of other studies, it has become increasingly clear that the firms that consistently achieve the best results insist on exact terms of reference being generated at each important stage. These terms of reference cover sales forecasts, engineering propositions both for product and equipment, estimates of capital and unit cost with unmistakable clarity, and stand as separate documents as part of the normal accountancy routine employed within the firm.

To conclude this Paper, reference is made to an attempt to set out in graphical form a typical routine for the introduction of automation shown on the preceding page, and the set of definitions already referred to, which have been prepared to clarify the use of certain terms in the case studies.

DEFINITIONS RELATIVE TO TERMS USED

As five widely different case histories are described in this Paper, the following definitions are given so that we may have an agreed meaning for the terms used relative to engineering production, namely:

"Operation"; "Production"; "Automation".

Operation

An operation is a concise element of work and consists of either moving, forming, finishing or assembling material. Each operation requires:

1. the application of force;
2. the guidance and control of that force from start to finish.

Production

Production is the combination together of a number of operations to effect all the changes required to the material, with the end object of increasing its utility to the community.

Automation

Automation may be relative to one operation or to

a number of operations in sequence, or to all the operations involved in any given situation.

Automation Relative to an Operation

The condition where the machine (as opposed to human muscle) provides the total force, and (as opposed to human brain) provides the complete guidance and control of that force from start to finish.

Automation Relative to a Number of Operations

The condition where the equipment (as opposed to a human agency) provides the means whereby a number of the operations are combined together in sequence to provide a number of changes to the material in process.

Automation Relative to all the Operations

In the extreme case this is the automatic factory. Full automation exists when all the operations required to effect a given change are such that the force and control is fully supplied by the equipment and all the operations are controlled in their correct sequence without the intervention of a human agent.

THE PRODUCTION OF PRESSURE VESSELS IN ALUMINIUM AND ALUMINIUM ALLOYS

by A. TOWNSEND, A.M.I.Mech.E., A.M.I.Prod.E., M.I.E.I.
and R. N. SAUNDERS

★ ————— ★
Mr. Townsend is Works
Superintendent of The A.P.V.
Co., Ltd. at Crawley, Sussex.



Mr. Saunders is the
Company's Chief Job Study
Engineer.

IN presenting this Paper the authors do not intend to deal with the theories of fabrication, either in design or welding considerations. These aspects have been the subject of many previous Papers and publications, and have been well covered. The intention, then, is to report on the practical considerations of production that are based on production experience.

Great strides have been made in the techniques of production, since the first aluminium pressure vessel was fabricated by hammer welding, and with the advancements in welding brought about by the inert gas shielded arc processes many of the difficulties of fabrication have been overcome.

The inert gas tungsten arc welding process was introduced into the United Kingdom from the U.S.A. in 1943 by the Ministry of Aircraft Production, and was in general use by 1946, following a B.W.R.A. Symposium on the Welding of Light Alloys in that year. The inert gas metal arc process was introduced in 1952, although certain inconclusive research work had been carried out in this country before that date, and the original patents are dated 1949. Although these processes enable the manufacturer to weld much thicker materials under conditions that were not possible by gas welding, they do in themselves present problems.

One of the difficulties encountered in these methods is the shrinkage and distortion that can occur, which calls for a very high degree of skill in the assembly of components. This is particularly important where the final form, or shape, or the position of fitments is required to be a high dimensional standard.

MATERIALS TABLE I
Extract from BSS 1470/1477
CHEMICAL COMPOSITION (per Cent.)

Alloy	Aluminium	Copper	Magnesium	Silicon	Iron	Manganese	Chromium	Titanium	Zinc Max.
BS1470	S1A	99.8 min.	0.02 max.	—	0.15 max.	0.15	—	—	—
	S1B	99.5 "	0.05 "	—	0.3 "	0.4 max.	0.05 max.	—	—
	S1C	99 "	0.10 "	—	0.5 "	0.7 "	0.1 "	—	0.1
	NS3	Remainder	0.15 "	—	0.6 "	0.7 "	1.0-1.5	—	0.2 max.
	NS4	"	0.10 "	1.8-2.7	0.6 "	0.7 "	0.5 max.	0.5 max.	0.2 "
	NS5	"	0.10 "	3.0-4.0	0.6 "	0.7 "	1.0 "	0.5 "	0.2 "
BS1477	NS6	"	0.10 "	4.5-5.5	0.6 "	0.7 "	1.0 "	0.5 "	0.2 "
	PIA	99.8 min.	0.02	—	0.15	0.15	—	—	—
	PIB	99.5 "	0.05	—	0.3	0.4	0.05	—	—
	PIC	99 "	0.10	—	0.5	0.7	0.1	—	0.1
	NP4	Remainder	0.10	1.8-2.7	0.6	0.7	0.5	0.5	0.20
	NP5/6	"	0.10	3.5-5.5	0.6	0.7	0.5	0.5	0.20

TABLE 2
MECHANICAL TEST REQUIREMENTS.
SHEET. Extract from BSS 1470

Alloy	Tensile Strength Tons/Sq. in.	Elongation on 2" Per Cent.	Bend Test (Min.)
S1A-0	5.0 max.	35	180° Flat
S1B-0	6.0 "	30	"
S1C-0	6.5 "	30	"
NS3-0	7.5 "	30	"
NS4-0	11-14.0	18	"
NS5-0	14.0 min.	18	"
NS6-0	17.0 "	18	"

Bend Test applies to materials up to and including 12 swg.
Elongation Test applies to materials over 12 swg.

TABLE 3
MECHANICAL TEST REQUIREMENTS.
PLATES. Extract from BSS 1477

Alloy	Plate Thickness (in.)	0.1% proof stress min. tons/sq. in.	Tensile strength min. tons/sq. in.	Elongation on 2" or 4vA* min. per cent.
PIA-M	0.253" to 1" incl.	—	3.5	30
PIB-M	0.253" to 1" "	—	4.0	30
PIC-M	0.253" to 1" "	—	4.5	30
NP4-M	0.253" to 1" "	—	12.0	12
NP4-M	0.5" to 1" "	—	12.0	15
NP5/6-M	0.253" to 1" "	8.0	17.0	12
NP5/6-O	0.253" to 1" "	7.0	17.0	18

* For round test pieces only.

It is, however, possible to produce pressure vessels in aluminium and its alloys by methods which compare very favourably with those in use on ferrous vessels, and which are in many cases being manufactured to the B.S. 1500 and ASME Codes.

The lack of a Code dealing specifically with aluminium pressure vessels has been the subject of much discussion, and indeed has been the subject of several Papers. A skeleton for a British Code does exist in the various British Standards and the specifications of Ministry departments, together with other official or semi-official bodies.

This need may shortly be satisfied, for an Aluminium Pressure Vessel Code is now the subject of consideration by a British Standards Committee.

materials

Metals chosen for pressure vessel application in the chemical and atomic energy fields are usually selected from the following grades:

- pure aluminium;
- aluminium - 1½% manganese alloys;
- aluminium magnesium alloys.

The chemical analysis, and mechanical properties, of the most commonly used of these alloys, are shown in Tables 1, 2 and 3.

Apart from specialised fabrications for the chemical industry pure aluminium is used extensively in the atomic energy fields, because in common with other light alloys it is not greatly affected by nuclear

bombardment. Aluminium has a thermal neutron absorption cross section of about 0.22 barns, which is low compared to that of other metals, and neutrons tend to pass through, rather than be absorbed by, the material.

The potential radioactive hazard from aluminium is low as its half life, or the time taken to lose half its radioactivity, is very short and is in the region of two minutes. Because of this property aluminium can be placed in the heart of the reactor, and its efficiency remains high as it offers so little resistance to neutrons, "Windows" may be provided in this material which enable irradiation experiments to be carried out.

The material is virtually unaffected by contact with pure ordinary water or heavy water, used as cooling and moderating media in some types of reactor.

For nuclear energy work, the copper content of the material must be closely controlled in order to maintain the high level of corrosion resistance of the aluminium, copper in the order of .01% - .02% maximum being usually acceptable.

Filler wire materials normally used in the welding of the various alloys are shown in Table 4, and as can be seen it is usual for the pure grades of aluminium to be welded with a filler wire of like composition. The non-heat treatable alloys are being increasingly used for pressure vessel work, and details are given later in this Paper of vessels manufactured in NS6 and NP5/6.

The mechanical properties of aluminium generally improve at lower temperatures, which makes it attractive for the storage of liquids at sub-zero temperatures.

The designer may also use castings and forgings to construct his vessel and although these may be somewhat limited in the sizes in which they are available, this can be overcome by welding segments or sections together to form larger components.

material control

It is essential, in order to satisfy the requirements of the various inspection authorities normally employed on this class of work, that strict control be maintained on all materials used.

The usual requirements are that :

- materials must be ordered against a recognised specification and should be supplied with certificates covering the physical and chemical properties;
- these certificates must be endorsed at the material supplier's works, by the inspecting authority concerned, when he inspects and releases the materials;
- the materials are again identified against their respective test certificates by the authority concerned, after receipt at the manufacturers and before their release to the shops;
- where several items are cut from one sheet, the sheet should be marked out, and the identification marks transferred in the presence of the inspector before the sheet is cut;

TABLE 4
SELECTION OF FILLER RODS.

Alloy	Welded to	Filler Rod to BSS 1475
99.8% 1A 99.5% 1B 99% 1C Any Pure Grade	99.8% 1A 99.5% 1B 99% 1C Al-1½% Mn. N3 Al-Mg. N3. N5. N6 Al-Mg-Si. H9-H20. H30	99.8% G1A 99.5% G1B 99% G1C Al-1½% Mn. NG3 Al-5% Mg. NG6 Al-12% Si. NG2
Al-1½% Mn. N3	Al-1½% Mn. N3 Al-Mg. N4. N5. N6 Al-Mg-Si. H9. H20. H30	Al-1½% Mn. NG3 Al-5% Mg. NG6 Al-12% Si. NG2
Al-Mg. N4. N5. N6 N4. N5. N6	Al-Mg-Si. H9 N4. N5. or N6	Al-5% Mg. NG6 NG6

- all identity marks must be preserved throughout all operations—rubblings of identities may be taken, and the marking transferred after machining or cutting has been carried out;
- the identification marks should preferably be transferred by lightly mechanically etching them on to the parts in question;
- the identities thus preserved are entered on to a material record form, to be in the Inspection Folder of the completed vessels.

In many cases the inspecting authority may apply this rigid control to pressure parts of the vessels only.

The use of ultrasonics should not be overlooked on the inspection of raw materials and, indeed, many inspecting authorities insist on this check being carried out at the supplier's works, before accepting the material, to ensure that it is free from flaws and laminations.

cleaning

Cleanliness is of paramount importance when welding aluminium alloys.

- Working Area.** It is advisable to allocate a working area restricted to this class of work only. This working area must be kept free from all grease, swarf metallic filings and concrete dust. The floor should be cleaned twice daily only, a vacuum cleaner being used in preference to a broom, especially if welding is in progress. Neither grinding nor polishing must be carried out in or adjacent to this area. If mild steel or copper are being welded in the same shop then it should be arranged that this be done some distance away; this is particularly important when the pressure vessels are to be used for certain chemicals such as high purity hydrogen peroxide.
- Weld Preparation.** The weld preparation should be well scraped and scratch-brushed, using stainless steel wires, immediately before welding. The brushes used should be kept for this work only. If there is grease contamination present this must also be removed. The practice of swabbing the weld preparation with liquid trichlorethylene or carbon tetrachloride for this




Fig. 1. Butt welded test coupon




Fig. 2. Liquid oxygen vessel

purpose is not recommended. Cleaned work should not be handled before welding without the use of gloves.

- (c) *Welding Rods and Filler Wires.* All filler rods for argon arc welding must be cleaned by dipping in a dilute solution of caustic soda, rinsed in hot water, dipped in a dilute nitric acid solution, re-washed in hot running water and then thoroughly dried by heating. The recommended dilution is approximately 10% by volume. If these processed filler rods have not been used within 12 hours, then they must be re-cleaned. Welding wires for argon arc welding should be kept in the cases supplied by the manufacturers until required for use. It is also advisable that these should be stored in a warm atmosphere to prevent any risk of moisture due to condensation. All electrodes, filler rods, and welding wires must be free from grease, and careful handling to prevent this contamination is important.
- (d) *Preparation.* Welding preparation should be made by machining or routing which gives a smooth clean surface free from crevices and burrs, which could form traps for dust and dirt. The use of chipping tools and grindstones should be avoided. As far as the form the weld preparation should take, though one can generalise on most butt and fillet welds, it is policy to establish the method on test pieces before commencing work on the actual components.

welders' tests and the approval of welders

The welding method and procedure to be adopted on this class of work is decided by the welding specialists of the company, and a trial is made, usually of approximately 3 ft. in length. This procedure test

piece is radiographed and the results compared against the specified standard, before cutting to provide tensile and bend specimens as required by the code of construction.

The test piece, if successful, is accepted as both a procedure test and as a welding test, for the particular welder who carried out the work.

Any number of welders may then be approved on the same welding procedure, by making individual test welds in the thickness of material representing the job. The test plates for a welder's test may be limited to approximately 12 in. in length.

After the initial test any of the approved welders who have completed a successful weld may be employed on the workpiece, using the procedure in which they were approved. It is necessary for any one welder to pass several different tests where he is employed on different procedures on any one job.

The approval lasts for varying periods according to the code of construction, and may vary from one test each 12 months (providing he is continually employed on the same class of work) to a test every two months regardless of this provision.

Should a welder fail on a retest he should be removed from the work, and given additional training, if necessary, until he is able satisfactorily to pass once more. Certain cases of construction, or inspection requirements, are very strict on this point, and may require the welder to wait one month before retaking his test.

Fig. 1 shows a typical welder's test coupon, and the method of cutting this to carry out the necessary mechanical tests.

design and fabrication of an aluminium alloy pressure vessel, for storage of liquid oxygen, at a working pressure of 800 lb. per sq. in.

The vessel about to be described is shown in Fig 2, and is one of a batch of eight manufactured in the alloy NP5/6. The body of each vessel consisted of four plates each $1\frac{3}{4}$ in. thick, which were rolled and welded into two belts of 2 ft. 6 in. inside diameter.

These were formed by rolling into half cylinders, with an allowance of 3 in. of "straight" left on each edge to facilitate rolling. The half cylinders were then planed to size and edge prepared, with a suitable shrinkage allowance left on.

The welding of the two half cylinders was carried out by the inert gas welding process. The root run was made by the inert gas tungsten arc process, and the filler runs by the inert gas metal arc process. Fig. 3 shows the typical weld preparation.

Because of the cost of reeled wire and the problems of distortion that arise when large amounts of weld metal are deposited, experiments are continuously being carried out on the thicker materials to reduce the angles shown in this sketch. Radiography was carried out at the root run stage, and again after the completion of the weld.

Two cylinders were then turned to length, and edge prepared. By using the same welding methods they were joined together to form one cylinder 2 ft. 6 in. inside diameter, approximately 5 ft. long.




Fig. 3. Typical weld detail — Double operator inert gas tungsten arc technique employed on root run inert gas metal arc on filler runs




Fig. 4. Sectional elevation of oxygen vessel (scale: 1 in. = 1 ft.)

DETAILS OF WELDED CONNECTIONS

Scale: $\frac{1}{2}$ size




Fig. 5. Boss in position before welding




Fig. 6. Boss welded and machined




Fig. 7. Boss welded and machined

The top of the vessel was formed from an alloy forging, welded to a short spherical skirt. At the lower end the vessel was closed with a completely hemispherical end, manufactured from a circle and segments. Fig. 4 shows the completed vessel and the form of manufacture.

Various fittings were required on each vessel to accommodate the level gauges and outlets, and in all cases these were required to be free from crevices. Figs. 5, 6 and 7 illustrate the methods adopted.

For attaching the various cover plates and fittings, austenitic stainless steel studs were used, with an interference fit in the vessel.

In view of the duty for which these vessels were required, special precautions were necessary to ensure that every item used in their construction was completely free from grease. To conform with this requirement and to ensure that no damage was done to the threads in the vessel, the following procedure was adopted to the fitting of the studs:

1. studs were frozen in an insulated container of "Dryice" for a period of up to eight hours. On the larger studs of $1\frac{1}{8}$ in. Whit. size, sufficient shrinkage occurred to overcome the interference;
2. studs and holes were then treated with a lubricant consisting of a molybdenum disulphide powder, mixed with industrial alcohol;
3. the studs were next inserted into their respective holes, and driven home by a powered torque wrench, set to a predetermined load.

After all fitting had been completed, the vessels were tested with a hydraulic pressure of 1,200 p.s.i.

The cleaning process, before despatch, consisted of washing with caustic, followed by a nitric wash before finally cleaning with distilled water.

the fabrication of a reactor core tank in 99.8% purity aluminium

Materials

The materials used in the construction of this vessel, shown in Fig. 8, were 99.8% purity aluminium to B.S. 1477 P1A, B.S. 1470 S1B and B.S. 1476 E1A for the shell, with a permissible copper content of 0.01% maximum. Tubes under 6 in. bore were in 99.8% aluminium to B.S. 1471 T1A with a maximum copper content of 0.01%. Tubes 6 in. and over in diameter were manufactured in 99.5% purity aluminium to B.S. 1471 T1B with a maximum copper content of 0.05%. The fuel element nozzles were made in HE9 material and the location sockets in NE5M to B.S. 1476.

Welding Processes

Inert gas tungsten arc process.
Inert gas metal arc process.

Radiography

Vessel fully radiographed on all butt welded seams.
Welds not radiographed to be penetrant dye tested.

Inspection

By customer at manufacturers' works to B.S. 1500.
Materials were ordered and bonded as previously described in this Paper. Welders were tested and approved by the inspection authority before commencement of the fabrication.



Fig. 8. Aluminium reactor core tank in foreground (Merlin type reactor in background)




Fig. 9. Aluminium reactor core tank
(scale: $\frac{1}{2}$ in. = 1 ft.)

method of fabrication

Fig. 9 shows the general arrangement of this vessel, and designates the sections into which it was divided to suit the particular needs of the manufacturing plant available. As can be seen from this sketch, the true datum from which all major dimensions are given is the underneath side of the top flange. This was obviously not convenient from a manufacturing point of view, especially as the flange was finally machined as almost the last operation.

It was decided, therefore, to create a temporary datum line approximately 1 ft. below the spun bottom end. This datum line was in fact a large MS plate of approximately $1\frac{1}{2}$ in. thickness, which was marked out to give the correct angular position of the major items of the vessel.

Four pedestals were welded to the lag radius of the tank to support the vessel during its manufacture. Fig. 10 shows the first section in position on its template, and the new datum line.

The first operation in actually constructing the vessel was to spin the bottom of the vessel which had been fabricated from two semi-circles. This was carried out on a mechanical spinning machine. At the same time the header plate was turned to its correct diameter, and its supporting members manufactured.

The header plate was then welded into position in the spinning and the assembly mounted on its template. (Stage 1, Fig. 10.) Seven holes were next bored through the doubling plates and spinning to accommodate the three inlet pipes and the four outlet pipes.

Short lengths of $12\frac{3}{4}$ in. O/D and $9\frac{3}{4}$ in. O/D tubes were next welded into position in these holes, the assembly having been removed from the template for this operation.

All welds were checked for cracking, using the penetrant dye and developer process, before the assembly was set back on the template for machining.

Details of Aluminium Reactor Tank

Fig. 11. (right) Detail of header chamber




Fig. 13. (below) Detail of typical tube welds





Fig. 12. Typical shell weld

The machining operations carried out at this stage were:

1. face top of header plate;
2. bore and tap the 26 holes to accommodate the fuel element nozzles;
3. turn the top edge of the spinning to length and prepare the edge for welding.

Whilst this work was in progress the fabricating shop were manufacturing the three belt sections of the vessel, and the main flange.

Main Flange

This was made up of forged segments welded together and machined. Approximately $\frac{3}{8}$ in. was left on the top side, and on the underside of this flange for finally machining to size after completion of all welding.

Top Section

This comprised a belt of $\frac{1}{2}$ in. thick aluminium 6 ft. 7 in. dia. \times approximately 2 ft. long, manufactured from two plates 10 ft. 6 in. \times 2 ft.

Heavy Shielding Section

The heavy section was made from two plates 10 ft. 8 in. long \times 2 ft. 6 in. wide and $1\frac{1}{4}$ in. thick. These were formed into a cylinder 6 ft. 8 in. outside diameter and welded.

Lower Section

Two 11 ft. long \times 5 ft. 4 in. wide \times $\frac{1}{2}$ in. thick plates were rolled and welded to form the lower section cylinder.




Fig. 10. Welding during Stage 1 of fabrication




Fig. 14. Aluminium reactor core tank




Fig. 15. Aluminium reactor tank packed for transport to Australia. The wooden base on which the framework stands becomes the bottom end of the packing case

assembly of sections

The top section and heavy section were machined to length, leaving suitable shrinkage allowances for the welds, and edge prepared.

The lower section was machined at the bottom end only, and its edge prepared to suit the dishing. An allowance of approximately 4 in. was left on the length of this belt, to enable it to be machined after all tubes had been welded in and before joining it to the top half of the vessel.

The top half of the reactor was then made up by welding the flange to the top section and by welding this assembly to the heavy section. Welding the lower section belt to the dishing completed Stage II and presented the vessel as two sub-assemblies.

A heavy steel reinforcing ring was bolted around the top end of the lower half of the vessel to give rigidity for the subsequent operations.

Using the template, the holes for the sleeves, which located the various beam tubes, were bored and edge prepared. The sleeves were formed from 1 in. thick plate in two halves, finished machined on the outside diameter and rough bored on the inside.

The tubes were then welded in using the edge preparations shown on the drawing (Fig. 13). After these welds had been satisfactorily inspected for cracks by penetrant dye, the sub-assembly was re-set on the large lathe and its length reduced to the drawing size, plus a suitable weld shrinkage allowance.

Before this machining operation could be carried out, a very detailed inspection check was necessary to determine the "best" dimension to machine to. This was necessary: (a) in order that the flange would have sufficient machining allowance left on either side to clean up to the drawing size; (b) to bring the beam and through tubes into drawing tolerance; and (c) to bring the header plate, or rather the tops of the fuel element nozzles, into drawing tolerance.

As could be expected, even with all the attention given to the fabrication, some welding distortion had occurred which made the calculating of the length to suit all conditions and tolerances virtually impossible. Advantage was taken in machining the length of the fuel element nozzles to bring these into their correct position, and thus removing one of the "fixed" dimensions.

The final body weld was then made and radiographed.

By setting the complete vessel mounted on its template in a horizontal position, with the template bolted back to the face plate of a large lathe, the final machining operations on the flange were carried out.

The flange end of the vessel was supported by means of a "spider", in turn supported from the tailstock of the lathes.

drilling of top flange

It was necessary to align the drilling template on the top of the vessel, with four location holes bored

in the base template, and this was carried out by means of an optical alignment telescope.

The alignment operation is a somewhat tedious business. It is essential to keep the temperatures of the shop in which this type of work is carried out reasonably constant, or quite alarming results can occur.

It is interesting to note that during one of these alignment operations the temperature in the shop was allowed to fall by approximately 15°F, and due to the construction and method of heating the shop the temperature was not uniform throughout. The errors of alignment increased rapidly, as the temperature fell, but returned to their original state after the temperature was restored.

Having aligned the drilling template it was securely clamped in position and a small pillar drill mounted on it, to drill the pilot size holes.

The template was then removed and the holes opened up to their correct diameter.

Testing

The completed vessel was tested as follows:

1. 10 p.s.i. hydraulic pressure
2. 10 p.s.i. air pressure

with the open end suitably blanked off.

Cleaning

Cleaning was carried out by caustic/nitric/demineralised water washes and the vessel inspected for cleanliness afterwards by wiping with soft tissue paper.

the fabrication of a regenerator in NP5/6 material

Figs. 16, 17 and 18 show the main construction details of this vessel, which if viewed with the photographs of the regenerators (Figs. 19 and 20) do give a reasonable impression of the methods used in fabrication.

The ends were manufactured from two semi-circles, welded together by an automatic welding process, and then "spun" into dishings.

One end was from $1\frac{9}{16}$ in. thick, and the other end was from $1\frac{5}{8}$ in. thick material. The ends were finally machined down to a nominal 1 in. thick, at the brims, and edge prepared as shown.

A manway outlet was necessary and was fitted with a compensating pad, the details of which are also shown in Fig. 18.

Cleaning methods were similar to those previously described, and the vessels were subjected to a 150 p.s.i. hydraulic test followed by a 100 p.s.i. air test.

conclusion

In describing the fabrications detailed in this Paper, there must of necessity be some sections that could with advantage be further expanded. It is felt, however, that sufficient detail is given to allow those interested to assess some of the difficulties and

Aluminium Alloy Regenerator




Fig. 16. Regenerator




Fig. 17. Typical weld preparation




Fig. 18. Detail of manway reinforcement




Fig. 20.

problems that are encountered on this class of work.

The authors wish to express their thanks to the Directors of the A.P.V. Co. Ltd., Crawley, for permission to publish, and to their colleagues for the assistance and encouragement given to them during the preparation of this Paper.

REFERENCES

1. The arc welding of aluminium. Aluminium Development Association, Information Bulletin No. 19.
2. A.S.M.E. Boiler and Pressure Vessel Code, Section VIII and IX.
3. Proceedings of symposium on aluminium pressure vessels. Institution of Mechanical Engineers, 28th October, 1958.
4. TOMLINSON, J. E. and SLATER, D. Automatic welding of aluminium plate. *British Welding Journal*, August, 1958, Vol. 5, No. 8.
5. LANCASTER, J. F. Welding of aluminium tank for experimental reactor. *British Welding Journal*, August, 1957, Vol. 4, No. 8.
6. SLATER, D. and TOMLINSON, J. E. The development of M.I.G. technique for welding aluminium. *British Welding Journal*, May, 1961, Vol. 8, No. 5.



Figs. 19 and 20. Aluminium alloy pressure vessels of the regenerator type

TRAINING FOR THE EFFICIENT CONTROL OF QUALITY

by J. HOLMES, A.M.I.E.I.



MOST industrial manufacturing and processing organisations employ an executive whose specific job is to worry about quality. The title afforded this person varies from one concern to another; the modern trend is to have a Quality Director or Manager, although many companies have preferred to enlarge the scope of the Chief Inspector's function to fill the need completely. The traditional Chief Inspector was merely concerned with administering a department which was fully employed in looking for defects. It has long been realised that looking for defects after a part has been made is an admission that you are not sure of what standard of work you

are producing, and that this is a very expensive way of trying to control quality. Today, all efforts are directed at controlling the quality of the things we make whilst they are being made.

These executives, these "men of quality", are interested in all functions concerned in the manufacturing sequence, design, planning, production, handling, transport, etc.; they are concerned in seeing that the problems of creating and maintaining quality receive the maximum degree of attention at every stage. They are more concerned with the prevention of defective work than the mere apprehension of it. They frame policies which are designed to achieve efficient control of quality, and these policies must inevitably include the use of some statistical techniques.

the prime enemy

The obstacles to successful quality control are many, but towering above all, dwarfing the fallibility of machines and materials, is the attitude of peoples' minds. In all departments from the highest to the lowest, apathy will be found to be the prime enemy of quality. Much of this apathy will be found to stem from a genuine belief that quality is the concern of the other man, that the individual's particular effort has no effect on the prevention of defects and maintenance of good standards.

The primary task facing a Quality Manager or Chief Inspector wishing to implement a progressive quality control policy is to bring about a change of

★—————★

Mr. Holmes, a Quality Engineer, has been responsible for designing and operating quality training programmes in companies allied to the motor industry.

★—————★

heart. He must convince his colleagues and all employees that quality does matter and that they are personally concerned with the problems associated with it. Everyone must become quality-conscious and understand how effective control of quality can be achieved. This task is one of mass communication and will obviously respond more rapidly to a systematic approach rather than a haphazard one. There are, in fact, two distinct parts to this problem. Firstly, to explain and convince all employees of the importance of quality, to see that all have a clear understanding of the customer's quality requirements and the Company's policies which are designed to enable these requirements to be met economically. Secondly, to spread an appreciation, and in some instances give actual training, in the theory and use of any statistical techniques which are destined to be used for quality control purposes.

choice of approach

The approach to this problem will naturally be influenced by the size of the manufacturing unit concerned and the numbers of people employed. For the purposes of this article, attention will be focused on the methods which could be applied by a company large enough to employ a member of their senior staff to work full-time on this exercise. This does not infer that smaller firms are excluded from taking action in this field; it does mean that they would have to scale down their activities and would probably require quality training to be carried out by a member of the staff on a part-time basis.

After having decided to institute a quality training programme, the first requirement is to appoint an individual to plan and operate it. This individual must have senior staff status and be directly responsible to the quality executive. He must be an engineer, enthusiastic about the problems involved in quality engineering, and possessing a sound knowledge of the basic principles of statistical quality control. The status afforded to this man is important, because he will be involved in lecturing to all levels of management as well as to works' employees.

allocation of space

What space will need to be allocated for this programme? It is envisaged that training will be carried out with small groups of personnel, a maximum of 12 in a group. The reasons for this are two-fold; small groups cause less disruption to production and certain aspects of this training are more effective when the size of the group being trained is relatively small. The requirement space-wise is quite modest: a conference room or a classroom in the education department will suffice. One company, which has accomplished much in this field of quality training, do in fact use a caravan which has been fitted out as a conference room for this purpose.

Fig. 1 shows the general form of the training programme. The courses which have been designated A, B and C are not necessarily intended to be executed in that order; local requirements will dictate

the way the programme is presented. It can be seen that the three courses consist of lectures, the contents of which will now be summarised.

COURSE A. This particular talk must be designed to show firstly, that quality matters both from the company and national aspects. There is never any shortage of evidence that can be called for on this score, and newspapers and customers' letters can be used to make the point. Next, it must show how quality is the personal responsibility of everyone in the organisation. Instances can be highlighted where the various departments have been responsible for quality failures. For example, cases where drawing limits have proved to be unnecessarily tight, where inadequate planning has caused defects, where purchasing have placed orders with sub-standard suppliers and where work has been damaged by rough handling. The object is to show that all departments can and often do cause poor quality work.

Next, the company's policies can be explained and it can be shown how they are designed to prevent quality failures. It must be proved that efficient control of quality does not require "empire building"; that if it can be successfully introduced it is a means of reducing the numbers of people involved in non-productive work. The framework for successful quality control is already in existence; all that is required is that people should be more conscientious.

This lecture will first have to be presented to the senior management, so that they are convinced of its usefulness, and that advantages are to be gained by presenting the talk to the rest of the employees. Subsequent lectures will be given to foremen, designers, planners, buyers, etc., right through the family tree to setters, operators and inspectors. Wherever possible it is a decided advantage to arrange the groups of employees so that there are representatives from all departments in each group. This arrangement will stimulate discussion and inevitably serve to underline the lesson that everyone is responsible for quality.

Many people will leave this type of meeting having discovered for the first time that the company is seriously concerned with quality and that they are expected to do something about it.

There is another form that Quality Appreciation discussion can take, and one which will show immediate benefits. A senior designer could be asked to prepare an analysis of one of the company's products so that he can describe and demonstrate its functioning and its design problems to a mixed meeting of planners and supervisors from all departments. The actual talk need last only 20 minutes; the discussion and questions which will inevitably follow will be the valuable aspect of the exercise. At the next meeting a senior planner could analyse the planning of a specific product with a similar group which this time would include designers. The meetings need not, and indeed could not, be held too frequently, the important thing being that they become a continuous feature of the company's activities.

A QUALITY CONTROL TRAINING PROGRAMME

LECTURES




Fig. 1

Where it has been tried, very considerable advantages have been gained from this type of training. Once again the widespread responsibility for quality is demonstrated, but also very useful knowledge is gained by all concerned in these meetings. In this form it would be necessary to limit attendance at these talks to technical staff and supervisors.

COURSE B. This consists of simple instruction given to works employees in the importance and functioning of the company's products. This is an effort to interest the "button pressers", "lever pullers" and "trolley pushers" in the things they help to make, to induce a pride in workmanship and a sense of responsibility.

There is a very widespread belief held by management that all employees on the shop floor are only interested in pay day and that the end product is of no consequence to them. A belief held by other managers is that works employees acquire a reasonable knowledge of their products in the course of their normal work. Both of these beliefs are erroneous. Although isolated exceptions will be found, it can be stated with complete conviction that:

- (a) in modern industry the operators, setters, inspectors and other works personnel have very limited knowledge of the nature and importance of the things they help to make; and
- (b) there is a very strong and natural desire amongst the majority of employees to have a reason for being proud of the things they make.

If the latter point cannot be accepted, it is an admission that little or no reliance can be placed on the human factor in improving and maintaining quality standards. This could be quite disastrous, as we are, and will be for many years to come, dependent upon the human factor in controlling quality in our workshops.

Here is a very useful activity which should be operated as a continual process. Works employees should attend short talks on the company's organisation and products. The talks should be arranged so that they occur infrequently but continuously; it would be a mistake to organise a series of concentrated lectures on this subject. The idea behind this training is not to impart detailed knowledge but simply to instil a sense of belonging, a sense of responsibility. What is required here is good strong medicine administered in very small doses over a very long period. Supervisors will be surprised at the effect such training will have on an employee's attitude towards his work.

COURSE C. The third course in this programme is concerned with providing training in statistical techniques. A company which uses or intends to extend the use of statistical quality control is faced with two distinct training problems. One is to train the specialists, the people who must originate control schemes and specify procedures; and the other is to train the very large numbers of employees who are going to be required to use, and therefore understand,

these techniques. The former problem will involve a comparatively small number of people and the necessary training is best provided by one of the education authorities which run residential courses on the subject. The training concerned in the latter problem can be carried out as a part of the proposed quality control training programme.

A large percentage of employees will need appreciation talks on this subject. For example, planning engineers will need to know the basic principles of statistical quality control as they will be meeting the various technical terms associated with the subject, and will, once the systems have been established, have to specify the use of standard control procedures. Foremen, setters and inspectors will require quite detailed instruction on the subject to ensure that they are convinced of the usefulness of the various charts and sampling schemes employed. Operators will need to have the control charts explained to them and be shown that the charts are designed to help and not hinder.

The presentation of this particular subject lends itself to clear and easy demonstration with the aid of quite inexpensive equipment, all of which can be "office made". The basic equipment needed consists simply of a device which will illustrate variability and another which will demonstrate sampling theories. The mechanics of this type of apparatus are well known.

Appreciation talks on this subject can, when backed up by well produced hand-outs, satisfactorily cover the subject in 90 minutes. When the more detailed training is needed it will be necessary to organise a course within a course. At least four two-hour sessions will be required in order to pass on sufficient knowledge to enable people to use intelligently the statistical control schemes in the shops.

The training programme so far described consists of lectures and demonstrations reaching out to individuals. There is no end to this programme, although certainly its momentum will relax as Courses A and C are completed. From this time on the quality training could probably be organised by a person on a part-time basis without impairing the value of the programme. It should be realised, however, that in many companies it will take a number of years to reach this point successfully.

the written word

There is now to be considered the other approach to quality education, the approach of mass appeal through the written word. Many companies have already published small booklets on quality which are distributed to all employees, and some companies operate quality poster campaigns. Both these methods have their value, both have their dangers.

A booklet, if purely an appeal to conscience, might be read once and cannot be republished with any useful effect for a considerable period. If it is to be useful it must be compelling in its presentation and contain sufficient information to ensure that it is retained for reference from time to time. Only larger companies will be in a position to appropriate the

necessary funds to produce a booklet having the required attributes.

Education by poster is a tool which is within the reach of all industrial organisations. The danger here is stagnation. One cannot compete with a book in the content which can be put over but it is possible to compel people to read a poster by imaginative design. If posters are changed or moved in a "follow the leader" fashion through the shops, the campaign can be made to live and a great deal of useful propaganda broadcast. This method of urging the control of quality can be quite cheap; indeed, a poster campaign involving 12 different posters which are continually moving and gradually being changed can be operated at a cost of below £15 per annum over a period of five years. The contents of posters should be as local as possible, with quality trouble spots highlighted and possible danger spots pointed out.

cost and savings

What is the cost of a quality control training programme? What savings would it bring? A training programme by itself will not save money—on the contrary, it will cost money. It is the adoption of the policies of which the programme is merely a part which will effect savings. The amount which can be spent on training will depend upon the estimated savings resulting from the successful adoption of an effective quality control policy. The form and intensity of quality training required will vary from one firm to another according to the factory size, the product and many other factors. An examination of the failure quality costs in one's own firm will indicate the amount of training which is necessary. Companies who have instituted quality training have proved it to be an essential step in making progress towards fully integrated control of quality.

Letters to the Editor

From: **W. T. Jackson, A.M.I.Prod.E.**

Quality Management

It was stimulating to read the article by Oliver Lawrence in the October Journal, particularly as it appeared currently with the President's admirable article: "A Time for Greatness".

It is my opinion that the first requirement to increase productivity is to control logically the course of product design and development to the stage where production drawings are proved for utility, appearance and cost.

The writer does, of course, acknowledge the importance of design and development and also the necessity of somebody asking the questions. I think that this cannot be too strongly emphasised and also that the questions should be asked of the right people at the right time, namely, all those concerned with production and the selling of the product, during the design and development stage.

From: **Francis B. Willmott, M.I.Prod.E.**

Wage Demands

In spite of (or because of) exhortations which cause irritation, wage demands after "The Little Budget" are most likely to be intensified beyond a mere shred of expediency to urgent necessity! Exhortation is fast becoming a by-product of weakness and a sign of ineptitude in dealing with a situation rationally.

This is not intended to convey the impression that the wage demands are justified, but rather to emphasise the futility of saying "No", and later on giving way. This happens all too frequently, with the result that a new crop of demands usually occurs after conceding a previous one: it becomes a habit.

There is only one basis for increased pay, and that is when the economy of the undertaking can afford to pay. Today, with costs already too high and ever increasing, the ability to pay does not truly exist unless it be related to increased work and production.

The Common Market

The time has come to recognise that in the event of becoming an active member of the Common Market, we shall assuredly benefit in unity and concord with other nations, in a bond and chain of circumstances linked to *free trade*. Sovereignty as such may well be minimised but not destroyed, because the shedding of any influence will be proportionate in the category of each nation caught up in this unique trading scheme.

The character and disposition of a race of people can never be entirely obliterated but only changed superficially which, in practice, will not be a bad thing, for it could weaken the too powerful and reflect strength in the weaker. This in sequence could foster better and more harmonious relationships between nations.

Interrelation of Work Study, Ergonomics, Operational Research and Cybernetics and Their Application to Production Engineering

THE Institution's Summer School for 1961 was held at The College of Aeronautics, Cranfield, and ran from 29th August to 1st September. The theme was "The Interrelation of Work Study, Ergonomics, Operational Research and Cybernetics and their application to Production Engineering". Over 100 students attended the School as residential guests in the fine quarters on the campus at the College and were welcomed by the Principal, Professor A. Murphy.

The School was formally opened by the President of the Institution, Mr. Harold Burke, who referred briefly to the seriousness of the national and international situation. The industrial progress of Great Britain was compared with that of other countries,

showing Britain to be behind the U.S.S.R., U.S.A. and West Germany; and the very real point made that unless the science of management changes rapidly in this country, it may be too late.

In introducing the first speaker, **Dr. J. E. Faraday** (*Imperial Chemical Industries Ltd.*), **Professor J. Loxham** (*Head of the Department of Production and Industrial Administration, Cranfield*), made passing comment to the fact that now, more than ever before, the professional institutions should work together with the aim of maximising the use of national resources.

In this opening address, Dr. Faraday set the tone for the School by firstly defining the respective terms. In two of these four the term "money", "costs" or "economics" was quoted, and Dr. Faraday put



Mr. A. G. Simms demonstrating in the Operational Research Laboratory
at The College of Aeronautics



An interested group in the College's modern Ergonomics Laboratory

forward the conclusion that production engineers and, in fact, any engineer is in principle at least a manager. As a manager, the engineer must be an expert in the two fields of management; the science and art. As far as the science is concerned these techniques help the manager to make quantitative decisions and the lecturer concluded by stating that the integration of these techniques by chronological use is the application of scientific method to management.

The speaker on Work Study, **Mr. G. P. Wade** (*Engineering & Allied Employers' West of England Association*), introduced his talk by offering the suggestion that the basic aim of work study is to optimise the use of resources. Much of the material was historical, but the speaker did make the point that work study action is largely remedial and not so often original.

Mr. Wade opined that this state of affairs was not really desirable, but that work study principles should be used at the design stage of the product. The students readily realised the limitations of "rate-fixers" and many agreed that the use of stop watches on the floor did not pose as serious a problem as many might believe.

The speaker also suggested that the Work Study Department might be considered as really part of the management function which specialises in human relations, and that its future activities might include liaison between the operational research specialists and the shop floor.

It was rather interesting to note that a denial of this hypothesis was put forward by the speaker on operational research, **Mr. A. G. Simms** (*The College of Aeronautics*). He felt that the operational research

specialist in fact looked at a much broader picture than the work study man and aimed at total optimisation rather than sub-optimisation. Further, the operational research specialist, by virtue of his training, is in a much better position to realise the implications of decisions on both a short and long term basis, including both the economic and social aspects.

Mr. Simms briefly referred to the concept of model building and the testing and verification involved, but he emphasised that operational researchers did not make decisions, but merely collected and interpreted data.

Again, unfortunately for the work study practitioners, their cause was mildly criticised by the speaker on ergonomics, **Mr. W. T. Singleton** (*The College of Aeronautics*), who indicated the necessity of broadness of concept for management workers. In defining the subject the speaker said that in common with growing techniques, their meaning tended to change over time because of new developments.

Ergonomics is the theory of servomechanisms, information and communications and Mr. Singleton freely used block diagrams to illustrate the principles. These block diagrams consisted of men and machines, but the speaker made the point that the most important part was the link between these commodities. Thus the ergonomist needs to have a knowledge of functional anatomy, physiology (in the mechanical sense) and psychology (mental studies).

The speaker concluded by showing the results of static ergonomic studies on such things as instrument dials, and inferred that with more study in the field of dynamic ergonomics this would become an optimisation technique in its own right.

Contrary to the ergonomist's point of view, the speaker on cybernetics, **Dr. E. Edwards** (*The College of Advanced Technology, Loughborough*), said that the matter of his subject dated back at least to the change from Roman to Arabic numerals. It was easy to infer from this that cybernetics rather specialises, at least in its better known use, in the detailed theory of information.

Dr. Edwards went on to explain "distortion" in systems and the importance of "language" and "codes and rules". There followed a rather lengthy discussion on the basis and advantages of binary number systems and their application to computers. This, of course, introduced some words on data processing and thus closed the circle in interest for the production engineer.

Mr. A. E. De Barr (*The Machine Tool Industry Research Association*), in his remarks included a very interesting historical exposition of the machine tool industry, and pointed to the newer trends and the attention which production engineers and designers must give to such things as vibrations and feed-back control systems. He also pointed to what might be considered an exponential cost increase in producing "quality" machines, but felt because of the past history of the industry it was desirable to continue along these lines.

The School closed by considering some sociological problems of production engineering, and the lecturer, **Dr. T. Lupton** (*The College of Advanced Technology, Birmingham*), indicated that psychology was a

changing study dependent upon the society to which it is applied. He also made the point that the desires of labour and management are precisely the same, but that labour is frustrated in its desire to "get on with the job" because of poor organisation on the part of management.

The speaker then went on to consider three basic types of organisation; bureaucratic, traditionalistic and charismatic, and that further, production engineers by installing job specifications establish what might be called an unsatisfactory, bureaucratic system.

In concluding, Dr. Lupton indicated that this problem, at least in its present state of development, was very difficult to solve but that at least an awareness of the facts by all concerned would be a tremendous start.

The Chairman, **Dr. T. U. Matthew**, then invited general discussion on the School as a whole and **Professor Henderson** (*Melbourne University*) stressed the importance which Australian Universities and industry are placing on operational research and advanced decision-making techniques.

Other guests at the School included: **Mr. E. J. Bell** (*The Victoria Electricity Commission, Australia*) and **Mr. H. Sutton** (*H.M.I., Ministry of Education*).

General thanks were also expressed to Professor Loxham for his part in the organisation, and to him and **Mr. Seymour Hills** for the most interesting demonstrations arranged in the respective laboratories.

W.S.H.



Members listening to Mr. Horton, of The College of Aeronautics, in the Work Study School

MANAGEMENT STUDIES

It is hoped that this Study will be the first of a series conducted in industry by the Technical Department of the Institution. The Study is not a complex one, and the method is very well known, but the important point is that the analysis is quantitative: that is, it deals with figures and facts and reaches a factual conclusion.

This new service is open to any firm, and managements are urged to submit their problems for consideration. Further, in order that members of the

Institution may study problems which they would not otherwise meet in their own particular industry, it is hoped that they will volunteer to serve on small, short-life Sub-Committees to consider these very problems. In this way, both firms affiliated to the Institution and individual members may take the opportunity to help in solving not only their own difficulties but also those of industry as a whole, and thereby make a real contribution towards improving the nation's present economic situation.

W. S. Horwood

Economic Life Determination

A CASE STUDY

THIS exercise is an examination of the economic life of five-ton Morris table top trucks. They were bought in 1952 and operated by a large city and suburban truck firm. It is to be emphasised that the method is equally applicable to any other item of capital equipment.

the vehicle replacement policy

There does not appear to be any precise method of determining when a vehicle should be replaced, and every known approach has certain limitations. Some users advocate the "drainage" policy, i.e., they take the view that as long as a particular vehicle operates at some sort of reasonable cost they are not faced with the problem of finding additional capital, or alternatively, can put available capital to other use. Their attitude is to drain every penny from the vehicle whilst it will operate without regard to its re-sale or trade-in value. This system appears to have little scientific basis.

There are other users who believe the "break-point" policy is the answer. Under this method it is suggested that when the total operating costs of a vehicle are at their "minimum" then replacement should be considered. In arriving at the "minimum"

operating cost figure, fuel, lubricants and tyres, being of a reasonably non-varying nature, are ignored and only the initial cost of the vehicle, together with the maintenance costs, are used. The initial or investment cost will decrease as mileage increases, and this is called the depreciation function.

The more usual situation, however, is that of a chain of machines, where the outgoing are continually replaced by incoming items. In this case discrete values of time will be used in a tabular solution for the minimum cost of the investment.

It is easy to deduce that:

$$\text{Present cost } C_t = \left[B - S(T) + \sum_{t=1}^T E_t \right] \frac{(1+i)^T}{(1+i)^T - 1}$$

Where B = Total installed cost (present value)

$S(t)$ = Depreciation function (at present time)

E_t = Maintenance expense function (at present time)

T = Life of equipment

t = Number of years elapsed

i = Annual alternative interest rate.

(Equation 1)

TABLE I
TABLE OF MAINTENANCE COSTS

PERIOD	TRUCK 1		TRUCK 2		TRUCK 3		TRUCK 4		TRUCK 5		TRUCK 6		TRUCK 7		TRUCK 8		MEANS	
	Mileage	Cost (£)	Mileage	Cost	Mileage	Cost	Mileage	Cost	Mileage	Cost	Mileage	Cost	Mileage	Cost	Mileage	Cost	Mileage	Cost
June 30 1952	6,750	79	6,037	77	7,669	202	6,564	126	5,200	67	8,014	129	7,409	160	7,793	97	6,929	117
June 30 1953																		
June 30 1953 to June 30 1954	12,413	187	11,726	225	14,215	357	12,420	281	11,825	171	15,227	332	14,572	300	14,543	251	13,368	263
June 30 1954 to June 30 1955	20,026	386	18,817	353	21,723	512	19,938	403	19,495	304	22,439	511	22,517	435	20,624	475	20,633	422
June 30 1955 to June 30 1956	25,986	560	26,141	416	28,836	797	26,704	668	26,306	572	29,921	646	30,053	562	27,644	614	27,687	604
June 30 1956 to June 30 1957	30,374	806	31,949	766	34,793	1,128	32,869	845	32,245	732	34,362	815	36,930	774	33,494	743	33,379	951
June 30 1957 to June 30 1958	36,011	1,006	36,959	963	41,577	1,297	38,325	1,416	38,455	981	38,805	1,100	41,449	868	39,535	1,017	38,889	1,081
June 30 1958 to June 30 1959	40,912	1,812	41,595	1,051	45,814	1,657	41,560	1,530	43,250	1,201	44,427	1,299	46,747	1,040	45,610	1,281	43,732	1,360
June 30 1959 to June 30 1960	46,813	2,133	47,685	1,247	50,846	1,796	45,101	1,663	50,000	1,400	50,585	1,522	52,385	1,287	50,465	1,470	49,240	1,565

depreciation

The depreciation has been computed by collecting prices quoted by the many second-hand truck dealers in the city. These are the prices which these dealers would pay, and thus represent true values to the company if they were selling. No prices quoted by advertising sellers have been used since these are inflated by the seller's mark-up.

assumptions

1. The data has been arranged to calculate the economic life directly on a time basis, instead of a mileage basis. This has been done to simplify computation, and it is considered a reasonable assumption on the grounds that each truck's yearly mileage, total mileage, and costs are fairly close over each year.
2. Administrative costs and direct overhead varies with the size of the fleet, and has been charged at 5% of maintenance cost, on the recommendation of the Company.
3. The maintenance charges have been corrected to present values by the use of the retail price index. The "All Groups" index has been used (based on 1939 as 1,000), which includes food and groceries, rent, clothing and miscellaneous. It is believed that this follows closely the average wage and thus indicates labour charges fairly accurately. It is doubtful whether materials used in maintenance follow the same series, but since these charges are not specifically available, the whole adjustment is at least pessimistic.

TABLE 2
CORRECTED VARIABLE MAINTENANCE COSTS

Mean Mileage	Mean Cost (£)	Cost per Mile per Year (£)	Mean Cost plus 5% O/H	Retail Price Index	Correction Factor (Present Wth.)	Corrected Maintenance Cost per Year
6,929	117	·0169	123	2,550	$\frac{3,052}{2,550}$	149
13,368	263	·0227	276	2,622	$\frac{3,082}{2,622}$	324
20,633	422	·0220	493	2,644	$\frac{3,082}{2,644}$	517
27,687	604	·0258	634	2,758	$\frac{3,052}{2,758}$	710
33,379	951	·061	999	2,885	$\frac{3,082}{2,885}$	1,067
38,889	1,051	·0236	1,136	2,920	$\frac{3,082}{2,920}$	1,200
43,732	1,360	·0577	1,429	2,992	$\frac{3,082}{2,992}$	1,471
49,240	1,565	·0372	1,642	3,082	1	1,642

TABLE 3
TABLE OF DEPRECIATION VALUES

Dealer No.	1952	1953	MODEL — PRESENT WORTH				1958	1959	1960
			1954	1955	1956	1957			
1	150	200	225	250	625	750	900	925	1,495
2	100	100	125	200	625	700	750	900	1,495
3	75	75	125	200	450	550	650	850	1,495
4	100	110	125	150	450	475	550	650	1,495
5	75	125	125	250	350	450	550	650	1,495
Mean	100	122	145	210	500	585	640	795	1,495

TABLE 4
TABULAR SOLUTION

	1	2	3	4	5	6
T	$\frac{\sum_{t=1}^T E_t}{t-1}$	B	S(T)	(2) — (3) + (1)	$\frac{(1+i)^T}{(1+i)^T - 1}$	C (4) × (5)
1	149	1,495	795	849	7.675	6,500
2	324	1,495	640	1,179	4.120	4,850
3	517	1,495	585	1,421	2.921	4,150
4	710	1,495	500	1,705	2.335	3,990
5	1,067	1,495	210	2,352	1.982	4,680
6	1,200	1,495	145	2,550	1.760	4,500
7	1,471	1,495	122	2,844	1.595	4,546
8	1,642	1,495	100	3,037	1.481	4,552

4. All fixed costs associated with maintenance expense have been ignored, as this will move the total cost curve upwards and will not affect the minimum point. These are :

- (i) *Petrol* : This is regarded as fixed since the variation due to different operating conditions (e.g., city or suburbs) is far greater than that due to wear, and the Company uses only a mean figure.
- (ii) *Oil* : The consumption follows roughly :
1st year — 1 pint per 1,000 miles.
2nd year — 2 pints per 1,000 miles.
3rd year — 3 pints per 1,000 miles.

Thus rate of increase = 1 pint per 1,000 miles each year
= 6 pints per year increase
= 6×1.2 shillings = 7.2 shillings per year.

This is a negligible percentage of total maintenance cost increases per year and is thus neglected.

- (iii) *Grease* : Constant.

- (iv) *Taxation* : Comprehensive and third party insurance — Constant.

- (v) *Tyres* : About the only cause of excess wear would be worn king pins, and/or shock absorbers, and in 50,000 miles the failure of either of these would be rare. Thus tyre cost is regarded as constant.

5. The alternative interest rate has been fixed at 15%, which is the external dividend paid by the Company for the last five years. Since trucking is by far the most important (financially) section of the business, and the Company is about 99% public owned, this rate of 15% as an alternative investment to trucking seems reasonable.

extreme cases

There seems little point in getting cost per mile for all trucks and time periods, since it is unrealistic to use these values selected from more than one truck to make extreme cases. Instead, an effort has been made to select two trucks with :

- (i) lowest mileages with highest costs;
- (ii) highest mileages with lowest costs.

CORRECTED MAINTENANCE COSTS FOR EXTREME CASES

TABLE 5

Mileage	Cost (£)	Cost plus 5% O/H	Correction Factor	Corrected Maintenance Cost per Year
6,750	79	83	$\frac{3,082}{2,550}$	101
12,413	187	196	$\frac{3,082}{2,622}$	231
20,036	386	405	$\frac{3,082}{2,644}$	472
25,886	560	588	$\frac{3,082}{2,758}$	657
30,374	806	846	$\frac{3,082}{2,935}$	904
36,011	1,006	1,058	$\frac{3,082}{2,920}$	1,119
40,912	1,812	1,900	$\frac{3,082}{2,992}$	1,960
46,873	2,133	2,237	1	2,237

Case (i)

TABLE 6

Mileage	Cost (£)	Cost plus 5% O/H	Correction Factor	Corrected Maintenance Cost per Year
7,409	160	168	A	203
14,572	300	343	S	403
22,517	435	456		531
30,057	562	590	A	661
36,930	774	812	B	868
41,449	868	910	O	961
46,747	1,040	1,090	V	1,127
52,385	1,287	1,359	E	1,359

Case (ii)

Truck No. 1 was found to suit case (i) and truck No. 7 to suit case (ii). The procedure for computation was now repeated for each case, and the total cost curve sketched.

conclusion

1. Although graphs have not been drawn, it can be seen from Table 4 that the lowest total cost occurs somewhere between three and four years. Had the graph been drawn, we would have found this to be 3.67 years and this occurs immediately prior to the first rebore and would be approximately at the end of the second set of tyres. This intuitively then would be one of the most economic points to sell the vehicle anyhow. Using the two extreme cases as in

Tables 7 and 8 the minimum costs occur at 3.33 and 3.9 years, so that these do not affect the decision substantially.

2. This model has been computed using the time basis instead of the mileage basis, and the validity of this assumption with regard to accuracy could be questioned. In this case, the decision to work on the time basis has been taken because most of the vehicles cover the same mileage in the same time with roughly the same costs (Table 1). The actual variance of economic life has been calculated as nearly as possible by taking the two above-mentioned extreme cases, although clearly had the problem been worked to its ultimate conclusion, we would have calculated on a mileage basis of each truck.

TABULAR SOLUTION FOR EXTREME CASES

Case (i)

TABLE 7

	1	2	3	4	5	6
T	$\sum_{t=1}^T Et$	B	S(T)	(2) - (3) + (1)	$\frac{(1+i)^T}{(1+i)^T - 1}$	$\frac{C}{(4) \times (5)}$
1	101	1,495	795	801	7.675	6,150
2	231	1,495	640	1,086	4.120	4,480
3	472	1,495	585	1,382	2.921	4,050
4	657	1,495	500	1,652	2.335	3,860
5	904	1,495	210	2,189	1.982	4,330
6	1,119	1,495	145	2,469	1.760	4,340
7	1,960	1,495	122	3,333	1.595	5,315
8	2,237	1,495	100	3,632	1.481	5,390

Case (ii)

TABLE 8

	1	2	3	4	5	6
T	$\sum_{t=1}^T Et$	B	S(T)	(2) - (3) + (1)	$\frac{(1+i)^T}{(1+i)^T - 1}$	$\frac{C}{(4) \times (5)}$
1	203	1,495	795	903	7.675	6,940
2	403	1,495	640	1,258	4.120	5,190
3	531	1,495	585	1,441	2.921	4,215
4	661	1,495	500	1,656	2.335	3,861
5	868	1,495	210	2,153	1.982	4,265
6	961	1,495	145	2,311	1.760	4,065
7	1,127	1,495	122	2,500	1.595	3,990
8	1,359	1,495	100	2,754	1.481	4,083

3. The fleet operated by this Company is quite large, and if it were sold *en masse* too often it could depress market values and lead to new depreciation function, and in this case lead to a different economic life. However, in this case, with a probable resale cycle of four years this condition is not likely to arise.

4. If the depreciation curve were drawn from Table 3 it would be seen that between 1955 and 1956 there occurred a marked step in the graph. This is due to the Morris Company becoming part of the British Motor Corporation, with a consequent slump in second-hand prices. This discontinuity of depreciation

function could have had serious effects on the solution had we not used a "step-wise" solution. That is to say, if Equation 1 had have been integral and not discrete, the discontinuous function would have presented difficulties.

5. It is important to realise that over a period of time money inflates, thus the use of some form of index for labour charges is necessary. It would have been possible to use a discounting procedure here, but the different results would probably have been only fractional.

Mr. W. G. Bennett, M.B.E., Member, has accepted a new appointment with Messrs. Sanderson Brothers & Newbold Ltd., Sheffield. This follows his retirement



last April from the post of General Manager of the Holman subsidiary company, Maxam Power Ltd. He was previously Technical Director and General Manager of The Climax Rock Drill and Engineering Co. Ltd., which was acquired by Messrs. Holman Brothers in 1958. Mr. Bennett, who went to Cornwall from Glasgow in 1930, was a very early member of the Cornwall Section and is a Past

Chairman. He was a very active Committee Member and during his years of office presented many technical Papers to the Section. A presentation has been made to him by the Cornwall Section Chairman, Dr. K. Farnell, in appreciation of his long service to the Section.

Mr. P. Bhattacharji, Member, has recently joined the Board of Saxby & Farmer (India) Private Ltd., Calcutta. He was formerly with Burn & Co. Ltd., Howrah.

Mr. C. Ellis, Member, has been appointed Deputy Managing Director of Edward Pryor & Son Ltd., Sheffield.

Mr. W. G. Mackenzie, Member, has been appointed to the Board of Telephone Cables Ltd., Dagenham, as Works Director.

Mr. V. E. Shute, Member, is now Works Manager of Appleby Edmonds Ltd., Birmingham (formerly Joseph Appleby Ltd.).

Mr. H. R. Stansfield, Member, has left the United Kingdom to take up an appointment with David Brown Greaves Private Ltd. for three years.



Mr. E. L. Tuff, Member, Director and General Manager of Projectile and Engineering Co. Ltd., has recently been appointed Deputy Managing Director. He has been with the Company for 30 years, and was formerly General Manager.

Mr. G. Ronald Pryor, Hon. Member and Immediate Past President, is the Chairman of a new Company to be known as Edward Pryor Developments Ltd., which will devote its activities to the design of automatic marking machines and ancillary equipment.

Mr. D. Foulger, Associate Member, has recently relinquished his appointment with Rolls-Royce Ltd. (Oil Engine Division), Shrewsbury, and has taken up a position as Mechanical Engineer, Public Works Department, Bermuda.

Mr. J. Hay, Associate Member, has been appointed a Special Director and Works Manager of Vickers-Armstrongs (Engineers) Ltd., Barrow Works.

Mr. E. Hampshire, Associate Member, has been appointed Works Manager (Heavy Departments) of Samuel Fox & Co. Ltd., a subsidiary of The United Steel Companies Ltd.

Mr. J. L. Hughes, Associate Member, has recently taken up an appointment as an Assistant Lecturer (Grade B) in Production Engineering at the Wigan & District Mining and Technical College.

Mr. F. T. Jones, Associate Member, has been appointed a Director of Microcell Ltd. (a subsidiary of B.T.R. Industries).

Mr. D. F. Irving, Associate Member, has relinquished his position as a Production Development Engineer with The Glacier Metal Co., Kilmarnock, and has taken up an appointment as Senior Sub-Contract Engineer with Distington Engineering Ltd., Workington.

Mr. C. H. John, Associate Member, has recently been appointed a Lecturer in Production Engineering in the Department of Mechanical Engineering at The Borough Polytechnic, London.

Mr. E. B. Loewendahl, Associate Member, has recently been appointed to the Board of Centec Machine Tools Ltd. as Works Director.

Mr. S. Metcalfe, Associate Member, has relinquished his position with the North Lindsay Technical College, Scunthorpe, and has taken up an appointment with the North-East Essex Technical College, Colchester.

Mr. P. H. Reynolds, Associate Member, has now been transferred to the Fuel Element Design Office, U.K.A.E.A. Engineering Group, as Engineer II.

Mr. P. H. Mainprize, Associate Member, has relinquished his position as Senior Lecturer at Garnett College, London, and has taken up an appointment as Head of the Engineering Department, Wolverhampton Technical Teacher Training College, Wolverhampton.

Mr. E. M. N. Manekshaw, Associate Member, has taken up a new appointment as Manager of Containers & Closures Ltd., Garifa, West Bengal.



Mr. S. Schonbrenner, Associate Member, has relinquished his position as Senior Service Engineer with Francis Kein & Co., Calcutta, and has settled in England. He now holds the post of Resident Engineer with T. H. Calow & Co.

Mr. W. S. Stirrup, Associate Member, is now a Lecturer at the Letchworth Regional Technical College.

Mr. B. E. Terry, Associate Member, has relinquished his appointment with Lacrinoid Products Ltd., and has taken up the position of Technical Director of Willamot Products Ltd., London.

Mr. W. A. Whitlock, Associate Member, has been appointed a Director of Bryans Aeroquipment Ltd., in addition to his existing duties as Works Manager.

Mr. James M. Clegg, Associate Member, has relinquished his position as Chief Project Engineer with de Havilland Aircraft Co. Ltd., Farnworth on his appointment as Manager of the Commercial Manufacturing Unit, de Havilland Aircraft Co. Ltd., Farnworth, Lancs.

Mr. J. A. Allcott, Graduate, has relinquished his position as Project Engineer with Hardy Spicer Ltd., and has taken up an appointment with Stewart & Lloyds Ltd. (Production Management).

Mr. W. Barnett, Graduate, is now an Administrative Engineer in the Power Reactor Equipment Department at Fairey Engineering Ltd.

Mr. M. J. Berry, Graduate, has been appointed Production Controller, Advanced Design Division of Unbrako Socket Screw Co. Ltd., Coventry.

Mr. N. J. Brown, Graduate, has relinquished his position with E. C. Little & Co., and has joined the Lockheed Hydraulic Brake Co. Ltd., as a Jig and Tool Designer.

Mr. D. H. Clark, Graduate, is now Senior Methods Engineer with U.D. Engineering Co. Ltd., London.

Mr. D. Copeman, Graduate, has taken up an appointment at the North-East Essex Technical College, Colchester.

Mr. G. Crackle, Graduate, has taken up the position of Jig and Tool Design Draughtsman at Rolls-Royce Ltd., Derby.

Mr. E. R. Gibbs, Graduate, has taken up the position of Production/Tool Engineer with I.B.M. World Trade Laboratories (G.B.), near Winchester.

Mr. G. Goode, Graduate, is now a Designer with Distington Engineering Co. (United Steel Companies), Workington.

Mr. D. W. Hicks, Graduate, has relinquished his position as Planning Engineer with Smiths Motor Accessories Ltd., and has taken up an appointment as Planning Engineer with English Electric Aviation Ltd., Stevenage.

Mr. J. E. Pearce, Graduate, has recently been promoted from Production Engineer to Assistant to Works Manager, Peto Scott Electrical Instruments Ltd., Weybridge.

Mr. A. M. Potter, Graduate, has relinquished his appointment with Dartmouth Auto Castings, Smethwick, and has taken up a position as Work Study Engineer with Dunlop Rim & Wheel Co. Ltd. at their Tyseley Factory.

Mr. P. G. L. Scott, Graduate, has taken up an appointment as a Product Designer with Hoover Electric Motors Ltd., Cambuslang.

Mr. P. G. Smith, Graduate, is now a Design Draughtsman with J. H. Booth & Co., Consulting Engineers, Bristol.

Mr. J. G. Warren, Graduate, who was previously Senior Designer, has been appointed Development Engineer, Chaphone Engineering Developments Ltd., Sutton Coldfield.

CORRECTION

In the October issue reference was made to the appointment of **Mr. R. Cooper**, Graduate, as Sales Office Manager of the Machine Tool Division of Monks & Crane Ltd., but due to a printing error the firm's name appeared as "Monks & Cove".

Obituary

W. J. MORGAN, M.B.E., D.L.C., M.I.Mech.E., M.I.Prod.E.

The death of Mr. Bill Morgan, following a heart attack last month, is recorded with profound regret. His passing is an inestimable loss to the machine tool industry, which he had served faithfully and with distinction for over 30 years.

He first became a familiar figure in the machine tool world as Technical Adviser to the Import Duties Advisory Committee in 1932, but it is as Secretary to the Machine Tool Trades Association, to which office he was appointed in 1939, that he will be most widely remembered. In 1951 he was appointed also General Manager to the Association, resigning from this dual office in 1958. He continued, however, to act as adviser, and was closely connected with the formation of the Machine Tool Industry Research Association, acting as General Secretary during its formative stages.

Mr. Morgan was closely concerned with the control of machine tools during the Second World War, and was instrumental in producing the report on the British Machine Tool Industry for the Director-General of Machine Tools at the Ministry of Supply, in 1945. For his services to the industry, he was awarded the M.B.E. in 1946.

His character was such that he inspired not only respect but warm affection amongst his countless friends and associates, who will not easily forget him.

E. G. HOLBERRY, M.I.Mech.E., M.I.Prod.E.

The death last month of Mr. E. G. Holberry, Works Director of E.M.B. Co. Ltd., at the age of 51, is recorded with deep regret. He joined the Company in 1952, as Works Manager, and was appointed to the Board in 1958. His drive and initiative were outstanding and yet "E.G.H.", as he was affectionately known throughout the works, was regarded as a friend and confidant by both workpeople and management.

His wise counsel will be sadly missed by a wide circle of friends.

DIARY FOR 1962

- | | | | |
|----------------------|-----|-----|--|
| JANUARY 25 | ... | ... | Annual General Meeting of the Institution.
10 Chesterfield Street, Mayfair, London, W.1. |
| MARCH 28 | ... | ... | The 1961 George Bray Memorial Lecture
at the University of Birmingham.

Speaker : Mr. J. F. Stirling , Executive Technical Director, James A. Jobling
& Co. Ltd.

Subject : The Production of Industrial and Domestic Glassware. |
| APRIL 5 - 7 | ... | ... | Aircraft Production Conference, College of Aeronautics, Cranfield.

Theme : Building Aircraft for the Competitive World Market. |
| MAY 15 and 16 | ... | ... | Eighth Annual Conference of Engineers Responsible for Standards.
The Connaught Rooms, London. |

Hazleton Memorial Library

ADDITIONS

The Hazleton Memorial Library is a reference and lending library freely available to members of the Institution. It is open on every weekday, excepting Saturdays and public holidays, from 10 a.m. until 5.30 p.m. Members may borrow all books and periodicals, with the exception of those which are constantly required for reference, and the current numbers of periodicals. The initial loan period is one month, and this can often be renewed upon application to the Librarian. Applications for loans, loan renewals, and for information can be made by post and telephone by members unable to visit the library; and books and periodicals can be sent to members by post, the Institution paying the cost of postage one way.

Bibbero, Robert J. **"Dictionary of Automatic Control."** New York, Reinhold; London, Chapman and Hall, 1960. 282 pages. 48s.

An encyclopaedic dictionary covering theory and basic concepts; computers and data processing; industrial machine and process control; aircraft and missile control and telemetering; and control components and design factors. Reference only.

Buckingham, H. and Price, E. M. **"Principles of Electronics."** 2nd edition. London, Cleave-Hume Press, 1958 (reprinted 1960). 419 pages. Diagrams. 18s. 6d.

Not intended for students making a very specialised study of electronics, but rather for general electrical engineering students, heavy current electrical engineers, and others, who are becoming actively concerned with electronic methods and their applications, and require a good grounding in the subject. About a quarter of the book explains the theory; another quarter describes valves, semi-conductors, photoelectric cells; cathode ray tubes and other electronic devices; and the rest is devoted to a wide range of methods used in engineering.

Carter, Harley. **"Dictionary of Electronics."** London, Newnes, 1960. 377 pages. Diagrams. 35s.

Concise definitions of terms from many branches of electronics including radio television, communications, radar, electronic instrumentation, and industrial electronics. Circuit symbols; abbreviations, colour codes, conversion tables, and diagrams of valve bases are given in an appendix. Reference only.

De Dani, A. **"Glass Fibre Reinforced Plastics."** Advisory editor, A. de Dani. London, Newnes, 1960. 296 pages. Illustrations. Diagrams. 50s.

A handbook—with contributions from experts in their respective fields—for users and moulders of glass fibre reinforced plastics.

Contents: Raw materials—Glass fibre reinforcements—Polyester resins—Other resins—Silicone resins—Ancillary materials—Moulding methods—Non pressure or hand lay up moulding—Low pressure mouldings: production of articles from rovings—Low pressure mouldings: processes using atmospheric pressure—High pressure mouldings: matched metal die mouldings—High pressure mouldings: dough moulding—Jigs—

Tools—Finishing operations for reinforced polyester laminates—Laminate properties—The moulding shop—The laboratory.

Drinberg, A. Ya. and others. **"Technology of Non-Metallic Coating."** by A. Ya. Drinberg, E. S. Guverich and A. V. Tikjomirov. Translated from the Russian by E. Bishop. London, Oxford, etc., Pergamon Press, 1960. 551 pages. Diagrams. 80s.

Discusses theoretical principles of film formation, the mechanism of ageing of coatings; organic lining materials; the properties of various coatings (including inorganic coatings); and their fields of application; corrosion protection; methods of applying coatings; and safety measures. There is information on the materials used in the Soviet paints and finishes industry. The original of this work was published in Russia in late 1957, and was planned as a text-book for students of chemical engineering specialising in the field of non-metallic coatings.

Furniture Development Council, London. **"Methods of Materials Handling in the Furniture Industry."** London, the Council, 1961. 58 pages. Illustrations. Diagrams. Mimeo. Spiral Binding. (F.D.C. Method Study Report No. 1.)

This report is based on a study of eight firms in the furniture industry, and is an attempt to show how the method study approach can assist in reducing handling costs. It is in three sections, the first containing an introduction conclusion and recommendations; the second the reports on the eight firms; and the third a discussion of how to approach a materials handling problem by the use of basic method study technique.

Hervis, F. R. J. **"The Evolution of Modern Industry."** London, etc., Harrap, 1960. 320 pages. 18s.

This book is written primarily for the type of student (e.g., students of industrial administration), who needs to have a knowledge of economic development and in particular of the development of industry, but has no time to become a specialist in economic history. It traces the evolution of British industry from earliest times to the present day, describing and discussing the causes and effects of the main economic events.

Contents: Mediaeval industry—The rise of English trade—Economic changes—Industry and trade before the industrial revolution—The industrial revolution—

Iron, steel and coal—Engineering—Cotton and the factories—Main economic periods since 1789—Transport and steel—Joint-stock companies—Industrial combination and monopoly—Public utility industries—Co-operative societies—The supply of capital—Trade unions—The evolution of distribution—Overseas trade and investment—Twentieth century industries—Modern industrial organisation—A guide to further reading.

Lockspeiser, Sir Ben. **"Man and His Machines: Automation and Computation—Their Origins and Effects."** London, Institute of Personnel Management, 1960. 12 pages. (Institute of Personnel Management, National Conference, Harrogate, 1960. Paper presented.)

Moslo, Ernest. **"Runnerless Molding."** New York, Reinhold; London, Chapman and Hall, 1960. 162 pages. Illustrations. Diagrams. 40s.

Describes the techniques used for the injection moulding of thermoplastics without the aid of a conventional sprue and runner system that must be removed from the mould each time a part or group of parts is injection moulded.

Contents: Introduction—Materials and automatic molding machines—An early runnerless mold—A practical runnerless mold design—Nozzle design variations for runnerless molding—Thin-wall container molding—Multiple cavity runnerless molds—Manifold and multiple runner arrangements—Large section runnerless molding—Valve gating for precompressed molding—Sequential impact molding—An insulated runner system for injection molding.

Scheele, Evan D. (and others). **"Principles and Design of Production Control Systems,"** by Evan D. Scheele, William L. Westerman and Robert J. Wimmert. Englewood Cliffs, N.J.; London, Prentice-Hall International, 1960. 369 pages. Illustrations. Diagrams. 42s.

An attempt to develop a scientific approach to the solution of planning and control problems in any type of production or management activity. The book describes specific steps, in chronological order for the design and use of production control systems: (1) Applying the principles of production control to any activity; (2) Making use of existing equipment and techniques as aids to production control; (3) Demonstrating methods of analysing and evaluating production control problems; (4) Developing the ability to adapt systems for continued effectiveness; (5) Setting up the relationship of the system to other management functions.

Schenk, Hilbert. **"Heat Transfer Engineering."** London, Longmans, 1960. 313 pages. Diagrams. 28s. (First published in Englewood Cliffs, N.J., by Prentice-Hall in 1959.)

An introductory text-book suitable for mechanical engineering undergraduates. It is assumed that the reader is familiar with such concepts as the Fanning friction factor, the viscosity, and the principles of dimensional analysis as applied to fluid systems. The author deals in turn with each of the modes of thermal energy transfer; then discusses systems involving two or more of these mechanisms; and finally describes systems involving several components. Detailed consideration is given to the theory and design of heat exchangers and other complete units. There are problems at the end of each chapter. The author believes that the field of heat transfer offers an ideal place for students to undertake individual work of originality and importance, and many of the end-of-chapter problems will suggest experimental projects. Chapter II (on heat transfer testing) deals with the principles of heat transfer test work and makes suggestions for apparatus and experiments.

Bower, C. T. **"Aids to Machinshop Practice: 200 Practical Hints, New Methods and Novel Ideas for Engineers, Machinists, Draughtsmen and All Concerned with Engineering Production."** London, Odhams Press, 1961. 192 pages. Illustrations. Diagrams. 18s.

Contents: Assembly methods—Drawing office aids—Drilling and tapping—Gauging and testing—Grinding practice—Work handling—Jigs, fixtures and machine attachments—Lathe work—Machineshop maintenance—Marking out—Milling work—Production methods—Welding practice.

Bowman, Edward H. and Fetter, Robert B. **"Analysis for Production Management."** Revised edition. Homewood, Ill., Richard D. Irwin, 1961. 562 pages. Graphs. Tables. Diagrams.

The first edition of this book was published in 1957. In this edition some additional material has been added where appropriate in order to expand the perspective and to account for new developments. The number of problems at the end of each chapter has been increased. The book is the outgrowth of a course in production management offered to first year students at M.I.T.'s School of Industrial Management. Some knowledge of mathematics, including statistics and calculus; and a knowledge of economics is assumed. The book is orientated towards the analysis of the economic problems of production management.

Contents: Section I. Orientation. Introduction—Analyses and decisions—Schematic models. Section 2. Mathematical programming. Linear programming—Special programming monitors. Section 3. Statistical analyses. Statistical control—Sampling inspection—Industrial experimentation. Section 4. Economic analysis. Total value analysis—Incremental analysis—Simulation—Equipment investment analysis—Case studies.

British Institute of Management, London. **"Case Study Practice: An Account by Specialists Working in Different Branches of Management Education of Their Experiences in the Use of Case Studies."** London, The Institute, 1960. 53 pages.

The case study method of teaching is fairly new, and although its value can easily be exaggerated, its potential value as an additional technique in the teaching of management is obvious. The contributors to this pamphlet represent respectively, a university, a technical college, the civil service, a firm of management consultants, a large, and a small industrial company.

Buffa, Elwood S. **"Modern Production Management."** New York and London, Wiley, 1961. 636 pages. Illustrations. Diagrams. 82s.

This book attempts to present the undergraduate student in particular, and to others a survey of modern knowledge of production management, a subject in which development has recently been very rapid. "Production" the author maintains, is the "operations" phase of any activity, and although the factory model is predominant throughout most of the book, the author recognises significant production systems in other types of activity, e.g., in hospitals, retail stores and offices. He concentrates throughout on what he calls the "hard core" production concepts, whilst recognising the existence of cognate concepts such as organisation, personnel management, and industrial relations. A grounding in analytical methods (for which some knowledge of mathematics is necessary)

is given early in the book so that problems of systems, design, operation and control can be based on these methods. The treatment of the usual "production" subjects (e.g., production and inventory control layout; quality control; maintenance) is based on these methods. There are problems at the end of each chapter.

Dalziel, Stuart and Klein, Lisl. **"The Human Implications of Work Study: The Case of Pakit Ltd., Stevenage, Herts., Human Relations Unit, Warren Spring Laboratories."** London, D.S.I.R., 1961. 81 pages. Charts.

This case study is the first fruit of a research project sponsored by the D.S.I.R. and Medical Research Council, Joint Committee on Human Relations in Industry. It describes the operation of work study in a medium sized firm in the Midlands.

Derry, T. K. and Williams, Trevor I. **"A Short History of Technology, From Earliest Times to A.D. 1900."** Oxford, Clarendon Press, 1960. 782 pages. Illustrations. 48s.

This book owes something to the recently published five volume *Oxford History of Technology*, but is not an abridgement of the larger work. Historians have considered man in his political environment, and, later in his social and economic environment. But it is only recently that the importance of technological factors has been recognised. This book is an attempt to draw attention to these. It is the technological equivalent of the numerous economic histories and social histories which have appeared in this century, and can be profitably read by technologist, historian and general reader. The Far East is excluded from the survey for lack of available sources, although, as the authors state, our debt to the Far East may be greater than is supposed. Bibliographies and chronological tables which relate technological to political and other events, should be of great help to the student.

Contents: Part 1. *From earliest times to A.D. 1750.* General historical survey — The production of food — Production of domestic needs — The extraction and working of metals — Building construction — Transport — Communication and record — Early sources of power — The beginnings of the chemical industry. Part 2. *The Industrial Revolution to A.D. 1900.* Historical survey — The steam engine — Machine tools and their products — Modern transport — Building construction: requirements of urban communities — Building construction: requirements or transport — Coal and the metals — New materials: coal-gas, petroleum and rubber — The rise of the modern chemical industry — Textiles — Pottery and glass — The internal combustion engine — The electrical industry — Printing photography and the cinema — Agriculture and food — Epilogue: technological and general history.

European Productivity Agency. **"Fitting the Job to the Worker: International Conference of Zurich, March, 1959."** General Report by Professor Bernard Metz. Paris, the Agency, 1960. 115 pages. Diagrams. 7s. 6d.

One of the aims of the E.P.A. is the improvement of working equipment, methods and environment, since these affect productivity. This Conference represents

phase three of a project aimed at interesting industrialists in "fitting the job to the worker". The first two phases comprised respectively a visit by European experts to American institutions which specialise in human engineering, and a technical seminar for European experts.

Contents: The respective roles of physiology and experimental psychology — Heavy muscular work — Work place design — Presentation and use of sensory information provided by the work process — Design of controls — Lighting and noise — Heat and working environment — Working hours and pauses — Bibliography.

Lea, F. C. and Simons, Eric N. **"The Machining of Steel: A Simple Explanation of its Principles and Practice."** Second edition. London, Odhams Press, 1960. 208 pages. Illustrations. Diagrams. 21s.

A handbook for students, apprentices, operatives and others, which gives the fundamental principles of cutting and shaping steel and its alloys, together with practical information on the machines and methods used.

Contents: Introduction — The lathe — Planing and shaping machines — Single-edge cutting tools — Milling practice — Drilling practice — Broaching practice — Reamers — Sawing practice — Factors in the cutting of steel — Speeds, feeds and coolants — Materials for cutting tools — Jigs, gauges and fixtures — Indexing. *Appendices:* Machining manganese steel — Electro-spark cutting.

Nadler, Gerald. **"Work Simplification."** New York, London, etc., McGraw-Hill, 1957. 292 pages. Tables. 50s. 6d.

Contents: Introduction — People and problems — Getting started — Product process chart — Form process chart — Man process chart — Operation chart — Therblig chart — Multi-activity chart — Analysing non-repetitive work — Other analysis techniques — Getting ideas — Selecting the "best" method — Designing the proposed method — Reviewing and testing — Installing the new method — Fundamentals of work measurement.

Saverin, M. M. (Editor.) **"Increasing the Loading on Gearing and Decreasing its Weight."** Translation supplied to the Department of Scientific and Industrial Research by the Pergamon Institute. Oxford, London, etc., Pergamon Press, 1961. 204 pages. Diagrams. 70s.


The results of a series of investigations carried out in the U.S.S.R. to find the most efficient ways of running gear transmissions to allow full use of their load carrying capacities and to reduce their weight. The book includes articles on a number of reduction gears at present in use in several rolling mill plants, measures to reduce the weight of cylindrical reduction gears, investigations into the laws governing changes in the life and fatigue, limit of tooth surfaces as a function of loading conditions, results of investigations on the load carrying capacities of gears with extended centre distance meshing with zero total displacement of the original contour, investigations of the load carrying capacity of gears with extended centre distance meshing with a large positive total displacement, the problems of the dynamics of spur gears and the experimental determination of the rigidity of gear teeth.

**INSIST
ON
GENUINE**

Jacobs

CHUCKS


*"I'm not talking
out of the back of my head"*



*"I quite believe you.
A true chuck runs true
because it is a true Jacobs
chuck made by Jacobs—the best
known name in chucks"*




*"Your dealer can supply
genuine Jacobs chucks in
all sizes for light,
medium or heavy duty"*



THE JACOBS MANUFACTURING COMPANY LIMITED, ARCHER RD., SHEFFIELD, 8

JC/3



THE MONEY THAT MANAGERMENTS SAVE THROUGH MOBIL ECONOMY SERVICE

**More than £1,360
saved in a year
at J. Blakeborough
& Sons Limited**

TAKING POSITIVE ACTION to cut maintenance and lubrication costs, J. Blakeborough & Sons Ltd. world-famous valve manufacturers, consulted the experts—Mobil. After accepting their recommendations, and applying the correct lubrication programme, Blakeborough found that they had made direct savings of over £1,360. Indirect savings were estimated at a further £2,100.

World-wide experience of industrial lubrication

This example of the value of Mobil Economy Service is typical of many that could be cited from almost every industrial area of the world. In all these areas, the world-wide Mobil organization is applying more than 90 years' experience to the cutting of lubrication and maintenance costs.

One plan to meet all lubrication needs

The value of Mobil Economy Service is the value of expert knowledge methodically applied: it is a matter of assessing all the lubrication needs of a business collectively; considering how they can best be met with the fewest different lubricants in the smallest quantities; and making sure that everyone concerned knows how to use the lubricants to the best effect with the absolute minimum of work. The astonishingly large savings that are often achieved are the measure of the experience and skill that Mobil bring to the consideration of every industrial lubrication problem.



The Council of the Institution

1961/1962

President

Harold Burke

Vice-President

R. Ratcliffe, C.B., M.B.E.

Chairman of Council

R. H. S. Turner

Vice-Chairman of Council

A. L. Stuchbery

Immediate Past Chairman of Council

H. W. Bowen, O.B.E.

Past Presidents

Major-General K. C. Appleyard, C.B.E. Sir George Bailey, C.B.E. The Rt. Hon. the Earl of Halsbury E. W. Hancock, O.B.E.
Sir Leonard Lord, K.B.E. The Rt. Hon. Viscount Nuffield, C.H., G.B.E. G. Ronald Pryor Sir Walter Puckey
Norman Rowbotham, C.B.E. J. D. Scaife Dr. H. Schofield, C.B.E. The Rt. Hon. the Lord Sempill, A.F.C.

Presidents of Councils outside the United Kingdom

AUSTRALIAN COUNCIL — I. M. McLennan, C.B.E.

INDIAN COUNCIL — S. L. Kirloskar

SOUTH AFRICAN COUNCIL — E. H. Dallas

Chairmen of Regional Committees

East & West Ridings

W. A. Hannaby

Eastern

G. S. Howell

Midlands

T. W. Elkington

North Midlands

E. Steele

Northern

A. Cameron

North Western

H. G. Gregory

Northern Ireland

T. S. G. Kee

Scotland

H. W. Townsend

South Eastern

W. Robinson

Southern

C. Sumner

South Western

F. G. C. Sandiford

Wales

W. H. Bowman

Additional Representatives on Council

East & West Ridings

E. Levesley

Midlands

E. P. Edwards

North Western

R. S. Clark

South Eastern

G. Kelly

Chairmen of Standing Committees

John M. Brice

(Editorial)

R. M. Evans

(Research & Technical)

J. C. Z. Martin

(Papers)

R. V. Rider

(Library)

J. A. W. Styles

(Education)

H. Stafford

(Standards)

Dr. T. U. Matthew

(Membership)

Elected Members

G. V. B. Bevan

G. R. Blakely

A. Betts Brown

A. G. Clark

W. Core

C. E. Darlington

E. S. Hammett

R. W. Hancock

P. G. H. Jeffrey

R. E. Leakey

J. G. Noble

G. C. Oram

C. Phillips

P. J. Shipton

L. P. Simpson

J. W. H. Smith

J. P. Speakman

J. H. Winskill

Chairmen of Sections outside the United Kingdom where Councils are not established

Canada

S. Carroll

New Zealand

J. C. Fantham

Overseas Councils

AUSTRALIA

President

I. M. McLennan, C.B.E.

Chairman

N. L. Eaton

Immediate Past President

J. M. Steer

Past Presidents

W. Gwinnett, J. N. Kirby

Vice-Chairman

R. W. Deutsher

Honorary Secretary

J. M. Steer

Honorary Treasurer

K. G. Slorach

Delegates

H. J. Baker H. A. Colton B. H. Coombes C. S. Curtis S. Downie E. J. W. Herbert C. A. Gladman
R. Harris A. G. Jones A. E. Newcombe A. Pead F. W. Penny C. Pullen K. H. Shute L. W. Worthington

INDIA

President

S. L. Kirloskar

Vice-President

Air Vice-Marshal Harjinder Singh, M.B.E.

Chairman

T. R. Gupta

Vice-Chairman

A. Miller

Honorary Secretary

P. J. O'Leary

Honorary Treasurer

H. N. Ghosal

Section Representatives

P. Bhattacharji N. G. Chakravarty S. R. Chatterjee C. H. DeSousa B. F. Goodchild N. N. Sen Gupta C. K. Haldar
W. P. Karnick G. L. Lewis R. A. P. Misra R. D. Mistry C. R. Pal J. V. Patel R. N. Rai J. W. L. Russell E. W. H. Scaife
B. M. Sen P. V. Shah S. J. Shahany

SOUTH AFRICA

1st Vice-President

R. Young

2nd Vice-President

R. W. Chapple

Immediate Past President

G. G. Tardrew

President

E. H. Dallas

Past Presidents

A. B. Anderson R. H. Arbuckle D. N. S. Clare W. G. Gillespie H. J. G. Goyns D. E. Hamm J. Henry
T. H. Hunter D. Lion-Cachet C. J. Mogford J. Renwick

Elected Members

A. B. Anderson P. C. Ellett D. A. Horton G. K. Melvill D. A. Petrie G. M. Tompkins H. Veit M. E. Walsh

SECTION CHAIRMEN

R. Harris Adelaide
S. M. Patil Bangalore
Dr. T. U. Matthew Birmingham
A. Miller Bombay
N. N. Sen Gupta Calcutta
S. Carroll Canada
G. R. Faulks Cardiff
K. Farnell Cornwall
W. Core Coventry
H. L. Barman Derby
J. Baker Doncaster
J. N. Low Dundee
F. H. Eccersley Edinburgh
H. W. Townsend Glasgow
N. S. Payne Gloucester
G. Butler Halifax & Huddersfield
R. V. Taylor Ipswich & Colchester
C. L. David Leeds
J. H. Devonald Leicester
R. Preston Lincoln
E. Walshaw Liverpool
R. Hutcheson London
J. Cherry Luton
J. D. W. Taylor Manchester

R. W. Deutsher Melbourne
L. L. Gonda Montreal
Sir William Scott, O.B.E., J.P. Newcastle upon Tyne
J. C. Fantham New Zealand
T. S. G. Kee Northern Ireland
C. W. Maddison Norwich
C. H. Hodgkins Nottingham
F. S. Chappell Oxford
E. Steele Peterborough
H. A. Kench Preston
L. J. Service Reading
R. Bradford Rochester
J. G. Noble Sheffield
G. Deane Shrewsbury
E. H. Dallas South Africa
C. Sumner Southampton
S. R. Trevillion South Essex
T. Proctor Stoke-on-Trent
T. G. Whittam Swansea
N. L. Eaton Sydney
A. Smith Tees-Side
F. G. Sandiford Western
W. B. Pamment Wolverhampton
R. A. Percival Worcester

GRADUATE SECTION CHAIRMEN

W. E. Simpson Birmingham Graduate
J. Shaw Coventry Graduate
W. Shelton Leeds Graduate
J. L. Hignett Liverpool Graduate
W. G. Peters London Graduate
D. S. Bone Luton Graduate
..... Manchester Graduate

E. K. Stephenson Melbourne Graduate
G. G. Tate Newcastle upon Tyne Graduate
..... Rochester Graduate
R. H. Clarke Sheffield Graduate
R. E. Everhard Western Graduate
E. V. Albrecht Wolverhampton Graduate


Mo

like t

has q

help b

a BIG




Most companies start as small fish. But few plan to *stay* small. Most would like to grow into BIG fish given the chance. But growing takes money, and sad to say, not every small fish has quite as much money as he could wish. However, money is just what UDT *does* have. We supply money to help businesses expand, extend their premises, add new or replace old equipment. Do *you* dream of becoming a BIG fish? Perhaps UDT can help you grow.

UDT HELPS INDUSTRY TO HELP ITSELF

UNITED DOMINIONS TRUST (COMMERCIAL) LIMITED · 51 EASTCHEAP · LONDON EC3

FAMOUS FIRMS SPECIFY R.I.C. FINISHES



The David Brown Company, world-famous manufacturers of agricultural and industrial tractors and machinery, have long specified R.I.C. finishes on all their machines. For they came to appreciate that an R.I.C. finish could dependably withstand any form of gruelling working conditions. R.I.C. supply specially formulated finishes to the majority of leading manufacturers in the agricultural machinery industry. If you have a troublesome finishing problem make full use of R.I.C. experience and service!



David Brown 50TD Angledozer with rear mounted ripper



INDUSTRIAL FINISHES

ROBT INGHAM CLARK & COMPANY • HEAD OFFICE: 93-97 NEW CAVENDISH STREET • LONDON • W1 • TELEPHONE: LANGHAM 0831
DEPOTS: BELFAST, BIRMINGHAM, BRISTOL, GLASGOW, LEEDS AND LIVERPOOL

REGIONAL HONORARY SECRETARIES

East & West Ridings ...	D. B. Verity	Northern Ireland ...	P. L. McIlwraith
Eastern ...	A. B. Brook—Colchester 5151 (Business)	Scotland ...	D. S. Nicol
Midlands ...	A. C. Turner	South Eastern ...	J. Aikman
North Midlands ...	D. S. Townsend	Southern ...	J. W. Taylor
Northern ...	L. R. Douglass	South Western ...	A. Eustace
North Western ...	J. P. Speakman	Wales ...	P. H. F. Burton

SECTION HONORARY SECRETARIES

AUSTRALIA

Adelaide (South Australia) ...	B. H. M. Coombes, 11 Elmo Avenue, Westbourne Park, Adelaide, Australia.
Melbourne (Victoria, Australia) ...	A. G. Jones, 13 Laburnum Street, Brighton, S.5, Victoria, Australia.
Melbourne Graduate (Victoria Australia) ...	G. E. Robert, 18 Rosaline Avenue, Mount Waverley, Victoria, Australia.
Sydney (New South Wales) ...	K. G. Slorach, 98 Church Street, Castle Hill, New South Wales, Australia.

CANADA

Quebec ...	J. Brooksbank, 4805, Millette, Pierrefonds, Province of Quebec, Canada.
Toronto ...	A. M. Hand, 18 Rintella Court, Scarborough, Ontario, Canada.

INDIA

Bangalore ...	A. R. Iyer, Dy. General Manager, Hindustan Machine Tools Ltd., Jalahalli P.O., Bangalore, 13.
Bombay ...	C. H. de Sousa, Churchgate House, 32 Veer Nariman Road, Fort, Bombay, India.
Calcutta ...	C. K. Haldar, Asst. Director General, Ordnance Factories, 6 Esplanade East, Calcutta, 1.

NEW ZEALAND

New Zealand ...	A. F. Nutch, H. Beaney (Senior) Ltd., 398 - 406 Great North Road, Grey Lynn, W.2, Auckland, New Zealand.
-----------------	--

SOUTH AFRICA

South Africa ...	A. Aitken, 209-211 Pharmacy House, 80 Jorissen Street, Johannesburg, P.O. Box. 10837, South Africa.
------------------	---

UNITED KINGDOM

Birmingham ...	W. Silberbach, 45 Bagnell Road, Kings Heath, Birmingham, 14.
Cardiff ...	A. E. Haynes, c/o A. B. Metal Products Ltd., Abercynon, Glamorgan—Abercynon 331 (Business)
Cornwall ...	F. G. Hawke, 3 Bellevue Terrace, East Hill, Tuckingmill, Camborne, Cornwall—Camborne 3491 (Private)
Coventry ...	R. L. Aston, Lanchester College of Technology Coventry, Priory Street, Coventry.
Derby ...	W. F. Radford, 15 Sherwood Avenue, Chaddesden, Derby—Derby 42424 Ext. 137 (Business)
Doncaster ...	G. R. Wimpenny 16 Tickhill Square, Denaby Main, Doncaster.
Dundee ...	A. J. Fraser, 51 Fintry Drive, Dundee.
Edinburgh ...	D. A. Bowman, The Scottish Council (Dev. and Ind.), 1 Castle Street, Edinburgh—Caledonian 7911 (Business)
Glasgow ...	D. S. Nicol, 35 Manse Road, Bearsden, Glasgow.
Gloucester ...	A. Emery, 3 Radnor Road, Hatherley, Cheltenham.
Halifax & Huddersfield ...	D. B. Verity, Kendoon, 168 Roils Head Road, Norton Tower, Halifax, Yorks.
Ipswich & Colchester ...	D. G. Petch, "Valandon", 231 Berghott Road, Colchester, Essex.
Leeds ...	J. Keightley, 42 Kingsley Avenue, Adel, Leeds, 16.
Leicester & District ...	J. A. Stovin, 14 Queens Drive, Leicester Forest East, Leicester.
Lincoln ...	H. Wright, 101 Longdales Road, Lincoln—Lincoln 21241 (Business) Lincoln 27462 (Private)
Liverpool ...	S. Bateman, 17 Brooklet Road, Heswall Hills, Wirral, Cheshire.
London ...	C. F. Weide, Vickers-Armstrongs (Engineers) Ltd., Crayford Works, Crayford, Kent.
Luton ...	J. F. W. Galyer, Luton College of Further Education, Park Square, Luton, Bedfordshire.
Manchester ...	J. P. Speakman, 223 Douglas Road, Atherton, near Manchester—Trafford Park 2431 Ext. 888 (Business) Atherton 538 (Private)
Newcastle upon Tyne ...	L. R. Douglass, Gateshead Technical College, Durham Road, Gateshead, Co. Durham.
Northern Ireland ...	P. L. McIlwraith, 25 Ward Avenue, Bangor, Co. Down—Bangor (County Down) 5896
Norwich ...	V. Crowther, 2 Willow Lane, Norwich, Norfolk.
Nottingham ...	K. Liqueurish, 28 Mona Street, Beeston, Nottingham—Nottingham 25-4831 (Business) Nottingham 25-6315 (Private)
Oxford ...	K. F. Watson, 30 Stanway Road, Headington, Oxford.
Peterborough ...	N. Holmes, "Arncliffe", 11 Mary Arny Road, Orton Longueville, Peterborough—Peterborough 67474 (Business)
Preston ...	M. A. Goody, 1 Langdale Crescent, Ribbleson, Preston, Lancashire.
Reading ...	P. J. Smallbone, "Maryfield", Darlington Road, Basingstoke, Hants.
Rochester & District ...	W. G. Clements, 11 Charing Road, Gillingham, Kent.
Sheffield ...	W. Edwards, 2 Wollaton Drive, Bradway, Sheffield.
Shrewsbury ...	W. M. Buchan, Llanberis, 36 Mytton Oak Road, Shrewsbury—Shrewsbury 51544 (Business) Shrewsbury 4880 (Private)

UNITED KINGDOM — continued

Southampton	R. C. C. Wadey, White Lodge, Holly Road, Ashurst, Southampton—Southampton 75533 (Business).
South Essex	E. R. Easman, 4 Onslow Close, Chingford, E.4—Seven Kings 3456 (Business)
Stoke-on-Trent	W. Elliott, 1 Longview Avenue, Alsager, Stoke-on-Trent.
Swansea	C. L. Clarke, 11 Alder Road, Cimla, Neath, South Wales.
Tees-Side	T. Young, 47 The Headlands, Marske-by-the-Sea, York—Redcar 3509 (Private)
Western	A. Eustace, 19 Ferndale Road, Northville, Bristol, 7—Bristol 693871 Ext. 243 (Business)
Wolverhampton	I. R. Jones, "Shalimar", Clive Road, Patterningham, Wolverhampton.
Worcester	R. Wheeler, Old Farm House, 7 Parish Hill, Bournheath, near Bromsgrove, Worcestershire.

CORRESPONDING MEMBER IN MALTA

L. Walmsley, B.I.M. Ltd., Marsa Industrial Estate, Malta, G.C.

CORRESPONDING MEMBER IN MIDDLE EAST

J. Merkin, 15 Sha'anani Street, Ramat Gan, Israel.

CORRESPONDING MEMBER IN RANGOON

J. T. Foster, Office of the Principal, Regional Marine Diesel Training Centre,
Dalla Dockyard, Inland Water Transport Board, Phayre Street, Rangoon, Burma.

CORRESPONDING MEMBER IN FEDERATION OF RHODESIA AND NYASALAND

R. P. W. Curtis, Copper Belt Technical Foundation, Chingola, Northern Rhodesia.

GRADUATE SECTION HONORARY SECRETARIES

Birmingham	A. Parkinson, 64 Wychall Road, Northfield, Birmingham, 31—East 2051 (Business) Priory 4073 (Private)
Coventry	N. A. Martin, 2 Home Farm Crescent, Whitnash, Leamington Spa.
Leeds	B. Noble, "Lane side", 25 Intake Lane, Batley, Yorks.—Leeds 637991 (Business)
Liverpool	T. Drysdale, "Stoneleigh", 2 Livingston Drive South, Liverpool, 17—Hunts Cross 2121 Ext. 46 (Business)
London	B. W. Jenney, 58 Langdale Gardens, Perivale, Middlesex.
Luton	D. A. Slough, 41 Felix Avenue, Luton, Bedfordshire—Luton 2440 Ext. 286 (Business) Luton 286 (Private)
Manchester	J. R. Ellis, 50 Avonlea Road, Sale, Cheshire.
Newcastle upon Tyne	J. D. Rennison, 26 Kells Gardens, Low Fell, Gateshead, 9, Co. Durham—Low Fell 7-7721 (Private)
Rochester & District	D. M. Samson, 123 York Road, Maidstone, Kent.
Sheffield	P. Brown, 21 Rowan Tree Dell, Totley, Sheffield—Sheffield 23038 (Business) Sheffield 365984 (Private)
Western	J. Russell, 1 Beaufort Road, Clifton, Bristol—Bristol 693871 Ext. 390 (Business) Bristol 33437 (Private)
Wolverhampton	R. Wise, 52 Pargeter Street, Walsall, Staffs.

LOUGHBOROUGH COLLEGE STUDENT SECTION

Chairman:

A. K. Bird, c/o 8 Shannon Square, Lane Head, Burnley, Lancs.

Honorary Secretary:

J. B. Carmichael, Hazlerigg Hall, Ashby Road, Loughborough, Leics.

MATERIALS HANDLING GROUP

Chairman:

H. Bond, Midland Electric Manufacturing Co. Ltd., Reddings Lane, Tyseley, Birmingham, 11.

Secretary:

S. Horwood, Assistant Education and Technical Officer, 10 Chesterfield Street, Mayfair,
London, W.1.

EDUCATION DISCUSSION GROUPS

London Centre

Chairman:

D. E. Peerman, "Oddlywood", Fox Close, Wigginton, Tring, Herts.

Honorary Secretary:

D. R. C. Holmes, 35 Sandringham Drive, Ashford, Middlesex.

Midland Centre

Chairman:

W. L. Jackson, Senior Lecturer in Production Engineering, Chance Technical College, Smethwick

Honorary Secretary:

N. Ward, 88 Sutton Oak Road, Streetly, Sutton Coldfield.


A

A

**PRODUCTION
CYLINDRICAL
GRINDERS**

STANDARD
AND FULLY
AUTOMATIC MACHINES
IN THE SIZE RANGE
12" x 24" TO
16" x 120"

NEWALL
ESTABLISHED IN 1900



BUILT THROUGHOUT TO J.I.C. STANDARDS

NEWALL GROUP SALES LIMITED
PETERBOROUGH • TELEPHONE 3227

save CAPITAL now

AND INCREASE
PRODUCTIVITY
by installing
STONE-VAPOR
steam-raising equipment

Complete installation costs need only be a fraction of the cost of conventional boilers, boiler houses and associated equipment.

WE ARE EXHIBITING
AT THE
INTERNATIONAL FACTORY
EQUIPMENT EXHIBITION
AT EARLS COURT
ON STAND No. D.22

Write for illustrated literature that describes the Stone-Vapor method of steam-raising.

STONE-VAPOR BOILERS



J. STONE & CO. (DEPTFORD) LTD., ARKLOW ROAD, LONDON, S.E.14. TELEPHONE: TIDEWAY 1202

J.S.16




DEEP THROAT PRESSES

for high speed
blanking,
punching and
forming on large
wide sheets

BLISS

Here is a new Bliss Press with features to boost production and cut operating costs. These presses have been designed for use where holes are to be punched or blanks cut at a distance from the edge of a wide sheet. The range includes two bench models of 2½ and 5½ tons capacities and six floor models in capacity ranges 10-60 tons. All complete with parts interchangeable with Bliss Bench and Inclinable Presses of similar tonnages.

*Standard features include:
fully stress-relieved frame;
rolling key clutch; extra
long gibs and heavy duty
precision-forged steel
crank shafts.*



E. W. BLISS (ENGLAND) LIMITED • CITY ROAD • DERBY

LONDON OFFICE: 2-3 THE SANCTUARY • WESTMINSTER • S.W.1



STILL IN SERVICE TODAY THANKS

TO A **METALOCK** REPAIR

BUILT BY

FIELDING & PLATT

ALMOST **50** YEARS AGO

100 TONS POWER—AND

OVERLOADED

EVERY DAY



THE ANSWER FOR

CRACKED AND

FRACTURED

CASTINGS



COLD CASTING REPAIR SPECIALISTS

FOR YOUR IMMEDIATE SERVICE

Bristol
Cardiff
Birmingham
Glasgow
W. Cumberland


Bristol 56014
Cardiff 29719
Bearwood 2799
City 7203
Egremont 381

Liverpool
London
Newcastle
Sheffield
Works

Central 3820
Whitehall 8902 - 5
Newcastle 24808
Sheffield 29361
East 1446



GRAND BUILDINGS · TRAFALGAR SQUARE · LONDON · WC2



Technical and Maintenance Tuition on

VICKERS

Oil Hydraulic Equipment

Regular instructional courses are held at the Birmingham Offices of Stein Atkinson Vickers, comprising a series of two-day lecture sessions, based on the application and servicing of VICKERS Hydraulic Equipment.

★ In March 1962 a special one-week instruction course in Maintenance will include extensive practical work. The courses are free and a prospectus will be sent to anyone sponsored by his Company or Principal. Lecturers are also available to address engineering groups and works organisations.

STEIN ATKINSON VICKERS HYDRAULICS LTD

Division of Vickers Incorporated, U.S.A.

197 Knightsbridge, London, S.W.7. Telephone: KNightsbridge 9641


Technical Sales and Service at London, Glasgow, Birmingham, Leeds and Manchester

MANUFACTURERS IN BRITAIN OF VICKERS HYDRAULICS

CRAWFORD RAPIDGRIP

**NEW
LEVER
-OPERATED
CHUCK**

for use
with
Crawford
Multibore
Collets



This powerful new dead-length chuck is particularly suitable for bar and second operation work; fitted with a Crawford rear support stop it can hold exceptionally short pieces. It is designed for operating Crawford Multibore Collets with their $\frac{1}{4}$ " size range. There's less operator fatigue, too, because Rapidgrip's simple, powerful rack and pinion gear is easier to operate than more direct lever systems of collet closing. Another special feature is the fixed front cap which ensures constant accuracy. An independent key allows easy bore adjustment.

**CRAWFORD
COLLETS
LIMITED**

Witney · Oxon
Witney 334




London Stockists: Acbars Limited 16-18 Macleod Street
Walworth Road London SE17 Rodney 7191

Midland & N.W. England Stockists: Retselp Engineering Ltd
Vulcan Road Industrial Site Lode Lane Solihull
Birmingham Solihull 2239

Agents for N.E. England: Alfred Herbert Ltd Carlisle
Square Newcastle 1 Newcastle 28864

Agents for Scotland: R. McSkimming & Co 65 West
Regent Street Glasgow C2 Douglas 7391-2





THE SCIENTIFIC APPROACH


Multi-channel oscillograms being made of the performance under load of a Cowlishaw Walker steel frame eccentric press at the Manchester Works of Associated Electrical Industries Ltd. This meticulous graphical analysis of the performance of this new range of eccentric presses of advanced design guarantees to the user:— higher productivity, better pressings and longer tool life.

COWLISHAW WALKER AND COMPANY LIMITED

BIDDULPH, STOKE-ON-TRENT • Phone: Biddulph 3254 • London Office: 117 Victoria Street, Westminster, S.W.1. Victoria 5472

Why transfer lines ?

*Linked machines are cheaper
and operate at higher efficiency*




- 1** Buffer stocks between each machine allow tool change without production time loss, thus raising normal efficiency ratings well above normal 80%
- 2** Machines load and unload each other automatically with interlocked cycle control.
- 3** Max-Muller linked machines are used for most types of machining including turning, milling, drilling, tapping etc.

PRODUCTION EXAMPLE ...

Six of these linked machines produce a finished turned and drilled brake disc

every 39 seconds !

Operations — turn outside diameter both sides, bore, chamfer all over and drill four stud holes.



FOR ECONOMICAL AUTOMATION

HENRY PELS & CO. LIMITED.


32-38 OSNABURGH ST., LONDON, N.W.1 Tel: EUSTON 4113

Introducing
the

CVR200

CONSTANT VOLTAGE D.C. RECTIFIER

(PATENT APPLIED FOR)



The Arcmaker CVR 200 Constant Voltage D.C. Rectifier supplying welding current for Lincoln Electric Co. Ltd. Sprite CO₂ Welding.

Continuous research and development by Lincoln Electric Co. Ltd. Engineers to provide the customer with even greater efficiency and quality of performance in welding power sources, has resulted in the production of the new **Arcmaker CVR 200** Constant Voltage D.C. Rectifier Unit.

This unit, which has been primarily designed for use with the Lincoln Electric Co. Ltd. **Sprite CO₂** Semi-Automatic Hand Welding Unit and other automatic welding processes, provides a compact, reliable and manoeuvrable power source with a voltage range of 14—30 volts D.C. in 16 steps (at 415 volts input) and a continuous output of 200 amperes at 25 volts.

For further details of the new **Arcmaker CVR 200** Constant Voltage D.C. Rectifier, please write to:

LINCOLN ELECTRIC CO LTD

WELWYN GARDEN CITY • HERTFORDSHIRE • ENGLAND

Tel: Welwyn Garden 24581 (10 lines) Cables & Grams: Shield-Arc, Welwyn Garden City



11/4/61

FRONTOR

Front-operated multi-tool chucking lathes

The latest development of a remarkably efficient lathe design: Ideally suited to small, medium or large batch production the FRONTOR machines offer marked advantages in both setting and operating and require a minimum of floor area.

Available with:

- Semi-auto cycle
- Transfer equipment
- Constant feed facing
- Auto-cycle with magazine feed
- Copying attachments
- Automatic chip disposal



FRONTOR machines are a joint development of two leading German machine tool manufacturers :

J. G. Weisser Söhne

FRONTOR 25

Nominal turning
diameter: 9 $\frac{3}{4}$ in.



Maschinenfabrik Diedesheim

FRONTOR 40

Nominal turning
diameter 15 $\frac{3}{4}$ in.

Write for full details:

SOLE BRITISH AGENTS

SYKES

MACHINE TOOL COMPANY LIMITED

Hythe Works, The Hythe, Staines, Middlesex. Telephone Staines 55474 (5 lines) Telegrams Sytool Staines



T
T




L
F
T



S

CEJ **FORMATOR** **CIRCULAR** **THREAD CHASING** **TOOLS**



**LOW COST TOOLING
FOR SHORT RUNS AND
THE LARGER COMPONENTS**

CEJ JOHANSSON LTD.

*Specialists in Threading
and Precision Measurement*

SOUTHFIELDS ROAD, DUNSTABLE, BEDS. TEL: DUNSTABLE 62422



DRIVE FOR SMOOTH PRECISION WITH INDUSTRIAL DIAMONDS

The finest pistons are turned with diamond tools and, for matching precision, their conrods are honed with diamonds.

Industrial diamond tools cut, grind, and polish with unsurpassed speed and accuracy and so make a vital contribution to increased efficiency and production in thousands of engineering processes.

To find out if diamond abrasives, diamond tools, or diamond impregnated wheels can help you in *your* problem, please get in touch with the Industrial Diamond Information Bureau. This Bureau is backed by the world's largest laboratory devoted to diamond technology - The Diamond Research Laboratory in Johannesburg. For information and advice, without obligation, please write to the address below.




The Industrial Diamond Information Bureau

2 CHARTERHOUSE STREET (DEPT. 8), LONDON, E.C.1.
Telephone: Fleet Street 7157

high torque

to B.S.D.

...and high torque, high slip



TOTALLY-ENCLOSED FAN-COOLED
TYPE 'D'. For duty in atmospheres laden with dust and dirt.



VENTILATED DRIP-PROOF
TYPE 'C'. Drip-proof in any position.

'ENGLISH ELECTRIC' offer
HIGH TORQUE: Types 'D' and 'C' motors.
HIGH TORQUE, HIGH SLIP: Type 'C' motors for
high inertia machines such as drop stamps and presses.


- **Foot, flange and skirt mounted**
- **Complying with BS 2960**
- **Class 'E' insulation**

Send for full information to:
Industrial Machines Department,
The English Electric Company Ltd.,
Phoenix Works, Bradford

'ENGLISH ELECTRIC'

**high torque
Industrial motors**

The English Electric Company Limited, English Electric House, Strand, London, W.C.2.



For the Modern Machine Shop

Multi-spindle Drilling Machines with adjustable spindle centres

A range of these machines is available and all models have infinitely variable hydraulic feed and automatic cycle of rapid advance, feed, rapid return and stop. Any number of spindles, with either fixed or adjustable centres, can be provided within the machine capacity. A brief specification of each machine is set out below, and we shall be pleased to supply full particulars upon request.

RANGE OF MACHINES

No. 0

Fixed head, moving table
Drive motor 5 or 7½ h.p.
Drilling area 10 in. diameter,
10 in. square or
13½ in. × 8½ in.

No. 1

Moving head, fixed table
Drive motor 10 h.p.
Drilling area 12 in. diameter,
12 in. square or
16 in. × 10 in.

No. 2


Moving head, fixed table
Drive motor 15 h.p.
Drilling area 18 in. diameter,
18 in. square or
24 in. × 15 in.

No. 3

Moving head, fixed table
Drive motor 20 h.p.
Drilling area 24 in. diameter,
24 in. square or
30 in. × 18 in.


No. 4

Moving head, fixed table
Drive motor 25 to 30 h.p.
Drilling area 30 in. diameter,
30 in. square or
36 in. × 24 in.



Illustrated is
Model No. 2

The illustration
below shows
Model No. 0



This 60 page catalogue illustrates and describes the range of K. & W. machines for the modern machine shop.



Write for this catalogue today.

KITCHEN & WADE LTD.

Member of the Asquith Machine Tool Corporation

ARUNDEL STREET, HALIFAX, ENGLAND Telegrams: 'KAW, Halifax'. Telephone: Halifax 67744 (3 lines)

KW465



I used to worry over my production programme — finding the right engineering firm to handle the sort of precision work I required gave me endless sleepless nights — in fact it got so bad I even tried a bit of fishing — they said it was a good way to relax . . .

Well, I still go fishing — I find I enjoy it, but I sleep well at night and haven't any more worries, not since I got Peak Engineering to take over my production headache.



If you think we can help you with your problems, why not write to our Technical Representative, or better still visit us at our modern factory at Stratford-upon-Avon — the fishing there is very good.



PEAK ENGINEERING CO. LTD.

MASONS ROAD · STRATFORD-UPON-AVON · WARWICKSHIRE

Telephone: Stratford-upon-Avon 3821

Telex: 31627

When replying to advertisements please mention The Production Engineer

The BRAKE that has EVERYTHING



A powerful and efficient brake in an emergency.

A robust brake with a high cooling rate.

Maintenance is greatly reduced and the amount of unspent lining is visible at a glance.

Brake pads are easily replaced when necessary.

Adjustment is extremely simple.

WE INVITE ENQUIRIES
FOR ORIGINAL EQUIPMENT

ONE OF THE
AUTOMOTIVE
PRODUCTS
GROUP



Lockheed

DISC transmission brake

LOCKHEED HYDRAULIC BRAKE COMPANY LTD. LEAMINGTON SPA, WARWICKSHIRE

Regd. Trade Mark: Lockheed

Milling
tapping
rolling
and su
and eq


B.S.A.
to adju
form a
circum
revolv




Milling cutters, twist drills, reamers, taps and dies, dieheads, tapping attachments, screwed shank tools and chucks, thread rolling dies, drill chucks, drill holders and adaptors, arbors, oil and suds pumps, machine vices, lathe chucks, magnetic chucks and equipment, hacksaw blades, broaches, limit switches.



B.S.A. NAMCO dieheads are simple in construction and easy to adjust. Circular chasers ensure extreme accuracy of thread form and long life; they can be reground through 270° of their circumference. The range includes types for stationary or revolving spindles and for Swiss type and turret automatics.



supreme



B.S.A. high speed tapping attachments. A quick easy pre-setting ensures correct tap-driving pressure with reserve elasticity to relieve the tap of extreme stresses should it encounter an obstruction, thus preventing tap breakage. Three sizes utilise standard hand taps in the range $\frac{1}{16}$ " BSF to $1\frac{1}{2}$ " W., and two versions for capstan and turret lathes, $\frac{1}{8}$ " to 1".



variety and quality

B.S.A. SMALL TOOLS LIMITED

BIRMINGHAM 11. ENGLAND

Cables: MADRICUT BIRMINGHAM TELEX 33-451

Sole Agents Gt. Brit.

BURTON GRIFFITHS & CO. LTD.

Montgomery Street, Sparkbrook, Birmingham 11

Tel: VICTORIA 2351

50,000

HYDROVANE


BULLOWS

OIL-SEALED ROTARY COMPRESSORS FROM 1/3-250 H.P.

IN USE throughout the World!

The Hydrovane principle was developed and introduced by Bullows in 1948 and has since been adopted by all the major manufacturers throughout the World!

10 Licencees manufacturing Hydrovane Compressors throughout the World!



For further details of the Hydrovane principle send for our "Questions & Answers" Folder

AIR COMPRESSORS · SPRAY PAINTING EQUIPMENT · SPRAY BOOTHS

ALFRED BULLOWS & SONS LTD

HEAD OFFICE & WORKS LONG ST WALSALL STAFFS ENGLAND TEL: 27251

DEPOTS AT—13 SOUTH MOLTON STREET, LONDON, W.1

55a BRIDGE STREET, MANCHESTER, 3

70 GILMOUR STREET, GLASGOW, C.S

61/63 DRURY STREET, DUBLIN

BULLOWS (AUST.) PTY. LTD., ETHEL AVENUE, BROOKVALE, SYDNEY, AUSTRALIA


TELEPHONE: MAYFAIR 2313

TELEPHONE: BLACKFRIARS 5670


TELEPHONE: SOUTH 2383

TELEPHONE: DUBLIN 73188/9


David Brown MACHINES



**... with
David Brown CUTTERS**



**... with David Brown
MEASURING EQUIPMENT**



... for best results!

Co-ordinated equipment for maximum efficiency on gear shaving

All your gear shaving and testing equipment from one organisation. The perfect relationship in design and performance, giving peak efficiency at every stage. That's the ideal for best results.

And that's what you get when you buy David Brown gear shaving and measuring equipment.

David Brown are ready to prove it !

DAVID BROWN



THE DAVID BROWN CORPORATION (SALES) LIMITED


MACHINE TOOL DIVISION, ASHBURTON ROAD,
TRAFFORD PARK, MANCHESTER 17.
Telephone: TRAFFORD PARK 4741

TOOL DIVISION, PARK WORKS,
HUDDERSFIELD.
Telephone: HUDDERSFIELD 3500

OA/6409A


PRATT

HYDRAULIC




FLOW CONTROL VALVES

CONTROLS



PRESSURE CONTROL VALVES



DIRECTIONAL VALVES

The Pratt range of Hydraulic Control Equipment is designed to meet the needs of every industry.

Qualified Pratt Engineers are always ready to advise on equipment and circuits.

FLOW CONTROL VALVES—Adjustable 3 cu. inches per minute to 10 gallons per minute.

PRESSURE CONTROL VALVES—Pressure up to 2,000 P.S.I.

DIRECTIONAL VALVES—3 to 10 gallons per minute.

PRATT PRECISION HYDRAULICS LTD

HALIFAX · ENGLAND TEL: HALIFAX 66371/5

A Subsidiary of F. PRATT & COMPANY LIMITED
Famous for Workholding for 100 Years



**complete paint finishing plant
and air conditioning systems
for industry**


CARRIER ENGINEERING COMPANY LTD.

CARRIER HOUSE, 24 Buckingham Gate, London, S.W.1

Telephone: VICtoria 6858

Export enquiries to DRYSYS EQUIPMENT LTD., 24 Buckingham Gate, London, S.W.1, England

HERE'S AIR POWER FOR THE MEDIUM SIZED WORKSHOP



THE ATLAS COPCO COMPRESSOR TT6

Developed from the famous VT portable compressors, the Atlas Copco TT6 is a compact, heavy-duty machine for round-the-clock operation where there is a moderate but continuous demand for compressed air.

The compressor is a single-acting, two-stage machine with air-cooled cylinders and intercooler. It is built for a normal working pressure of 100 p.s.i. and has a free air delivery of 141 c.f.m.

NO FOUNDATIONS NEEDED. The TT6 and its electric drive motor are mounted on 'Metalastik' bonded rubber feet. This eliminates the need for foundations as the compressor can be placed directly onto concrete floors. The TT6 can also be moved from place to place as circumstances dictate.


Like the VT portables, the TT6 combines an outstanding power/weight ratio with a basically simple design which ensures reliable service and easy maintenance. The TT6 is a sound investment for medium-sized or small-but-growing companies.

AUTOMATIC CONTROL AVAILABLE. Available as an optional extra, the Atlas Copco Regulator allows the TT6 to be run with standard valve unloading system or as a fully automatic stop-and-start unit.

WRITE FOR THE LEAFLET Atlas Copco leaflet E1207-1 gives full details of the TT6. It is freely available on request from the address shown.

ATLAS COPCO (GREAT BRITAIN) LIMITED

Maylands Avenue, Hemel Hempstead, Herts. Tel: Boxmoor 6040
Sales and service depots: LONDON · BRISTOL · CARDIFF · LICHFIELD
LEEDS · MANCHESTER · NEWCASTLE · GLASGOW · BELFAST · DUBLIN



Atlas Copco

puts compressed air
to work for the world



RAPID RE-SET

Face Milling Cutters

Secure —

RAPID BLADE RE-SETTING

RAPID RE-SERVICING

REDUCED CUTTER DOWN TIME

REDUCED CUTTER COSTS



RAPID RE-SET EQUIPMENT

The use of the Wickman Rapid Re-set Cutter Body and three blade styles available provides a simple variation of blade geometry. The blades can be removed, re-ground, checked and replaced in any Cutter Body size within the range — **WITHOUT REMOVING THE CUTTER BODY FROM THE MACHINE**, thus reducing down times and costs to a minimum.

WRITE FOR YOUR COPY OF THE
NEW WICKMAN FOLDER —
"WICKMAN RAPID RE-SET FACE
MILLING CUTTERS" — FOR
THE FULL STORY.



GRIND — with special jig

GAUGE — for accuracy



RE-SET — in setting block

WICKMAN



LIMITED

WIMET DIVISION, TORRINGTON AVENUE, COVENTRY.

Telephone 66621

Shell achievement



A famous aero-engine firm found it could drastically reduce the cost of producing nuts made from S.62 steel, by changing over from conventional cutting oils to Shell Garia Oil 115. The facts are these. S.62 steel is heat-resistant and stainless. The quality of this steel and the call for very fine tolerances, as well as a very high percentage of full depth of thread, presented costly manufacturing problems. The breakage of taps, the need for constant re-setting, and the high proportion

of rejects, built up the average cost of the nuts to over 1s. 2d. each.


By accepting the advice of the Shell engineer and changing over to Shell Garia Oil 115, this firm was able to produce 3,000 nuts between regrinding taps—resulting in the cost of each nut being reduced to 3d.

Write for the booklet 'Selecting Your Cutting Oils' to Shell-Mex House, London, W.C.2.



SHELL INDUSTRIAL OILS

Shell demonstration



To establish *facts* is the constant preoccupation of Shell research. Assumptions cut no ice.

For example, how 'extreme' is 'Extreme' Pressure?

To evaluate scientifically the respective performance of the many E.P. agents evolved, Shell devised the Four Ball Test machine illustrated.

In this apparatus a clamped $\frac{1}{2}$ " diameter steel ball revolves in contact with three identical static balls in a metal cup containing the additive to be tested. Pressure between the balls can be varied at will. Under these controlled rubbing conditions, coefficients of friction

can be plotted against load. With increasing loads, wear scars formed at successive stages may be measured and the welding point accurately determined. Developed for basic research, the Four Ball Test also plays an important workaday role in ensuring consistent batch quality—of prime importance on the machine-shop floor.

Thoughtful production executives who want to know more have only to write for the book, 'Selecting Your Cutting Oils', to Lubricants Dept., Shell-Mex House, London, W.C.2.




SHELL CUTTING OILS

When replying to advertisements please mention *The Production Engineer*

PARKSON

VERTICAL MILLER

2V



Capacity: 30 x 10 x 18 $\frac{5}{8}$ in.

Power feeds and rapid
traverse to all table
movements

24 Spindle speeds:

18-1000 rpm
or 24-1330 rpm
or 27-1500 rpm

Spindle Nose: 5 $\frac{1}{16}$ in. dia
no. 50 taper hole

Range of

PARKSON

Horizontal Milling Machines

1NA Universal

2N Universal

2N Plain

3N Universal

3N Plain

Adapta Model N



J. PARKINSON & SON



(SHIPLEY) LTD

SHIPLEY Telephone 53231 YORKSHIRE

1.
2.

3.



Ward**SPECIAL****TOOLING LAYOUT No. 14**

Floor to Floor Time :

2 mins. 45 sec.

**7DS CAPSTAN
LATHE**

Code Word : Sevends

Fitted with 13" Air Operated
3-Jaw Chuck.**CAST IRON
COVER**Tungsten Carbide Cutting
Tools.

DESCRIPTION OF OPERATION	Tool Position		Spindle Speed R.P.M.	Max. Cutting Speed		Feed	
	Hex. Turret	Cross-Slide		Feet per min.	Metres per min.	Cuts per inch	m/m per rev.
1. Grip at A - - - - -	—	—	—	—	—	—	—
2. Bore 4 3/8" dia., face bottom, form end boss	—	—	—	—	—	—	—
and drill 3/8" dia. hole, - - - - -	1	—	177	278	84.8	76	.334
Turn flange dia., - - - - -	—	—	119	180	54.7	Hand	Hand
Chamfer bore & flange - - - - -	—	—	—	—	—	—	—
Finish face end - - - - -	—	Rear	177	278	84.8	Hand	Hand
3. Remove from chuck - - - - -	—	—	—	—	—	—	—

'PRELECTOR'
Combination Turret
Lathes
with Preselective
speed-changing.

TURRET LATHES
with capacities up
to 35 in. swing over bed

1 1/2 in. to 2 1/2 in. 'D-S'
DOUBLE-SLIDE
Capstan Lathes
for heavier
accurate work.

Stock Tools,
Toolholders, Chucks
and Accessories for
Capstan and
Turret Lathes.

**H. W. WARD
& CO LTD**

SELLY OAK, BIRMINGHAM 29

Phone : Selly Oak 1131





Registered Trade Mark in Great Britain.

BED TYPE production milling machine


Designed for fast, accurate, profitable
production of small to medium size parts.

UPRIGHT — rigid one-piece construction . . . heavily ribbed to absorb vibration and torsional stresses imposed by high rates of metal removal.

POWER CONTROL STATION — conveniently located, compact grouping of switches which include master, spindle, table and coolant control.

TABLE FEED DRIVE — self-contained gear driven unit . . . quiet, positive power transmission. Individual quick-action magnetic clutches control feed, rapid traverse and table direction.

BED — multiple box-section construction, heavily ribbed throughout at all stress points to absorb the heaviest cutting forces . . . Integrally cast "square-wrap" table ways.



SPINDLE-HEAD — rugged compact design . . . micrometer dial, graduated to .001", facilitates accurate manual positioning . . . 12" vertical range . . . double clamping assures rigid, positive settings.

SPINDLE QUILL — three inches of cross-adjustment . . . quick, positive clamping.

SPINDLE — No. 40 N.S. taper . . . three-bearing spindle.


TABLE SCREW — has 126,000 p.s.i. tensile strength and a yield point of 100,000 p.s.i. . . . more than ample to move the load easily without distortion.

Choice of three horsepowers and speed ranges available — 2 h.p., 25-750 r.p.m.; 3 h.p., 50-1500 r.p.m.; 5 h.p., 100-3000 r.p.m. — independent $1\frac{1}{2}$ h.p. feed motor — choice of three feed rate ranges — $\frac{1}{2}$ to 20 i.p.m.; 1-40 i.p.m.; $1\frac{1}{2}$ - 60 i.p.m. — horizontal feed range 18 inches — vertical feed range 12 inches.

Milwaukee Mil
Model 1218

for SMALL, MEDIUM LOT
 and CONTINUOUS *Production*

CUTS SET-UP TIME



CENTRAL CONTROL GROUPING


An outstanding example of operating convenience. A "twist of the wrist" effectively eliminates backlash for either conventional or climb milling. The compactly grouped push-button Operator Control Station facilitates control of all table movements.

Either manual or automatic cycle. Automatic cycle table control is based on an electrically coded system, with a minimum of basic styles of trip dogs, to create a wide range of automatic milling cycles.

EASE OF ACCESS

... TO CUTTERS
 AND ARBORS

Cutters and arbors can be changed WITHOUT removing arbor supports from overarms. Merely extend one overarm, slide arbor support forward on extended overarm, swing it up, move it back and rest it on the other overarm.



Manufactured and Distributed by ...

KEARNEY & TRECKER - C.V.A. LTD.

GARANTOOLS HOUSE • PORTLAND ROAD • HOVE • SUSSEX Tel: Hove 47253 Cables: Cveatools (Telex) Hove

LONDON • BIRMINGHAM • GLASGOW • MANCHESTER • BRISTOL

NRP 3403

When replying to advertisements please mention The Production Engineer



**For
More Accurate
GEARS...**




V 10

**UNIVERSAL
HOBBING
MACHINE**

An entirely new model built for fast, accurate production. For generating spur gears and sprockets, splines and serrations—and worm wheels by the plunge cut method. Built-in differential for spiralling. Hob head swivels to 60° for left and right hand spirals. Tangential feed hob head available for worm wheels of high tooth angle and worms. Lever operated changeover from roughing to finishing feeds. Rapid return power traverse. Climb or orthodox hobbing methods can be used. A fast production model with hydraulic closed cycle and automatic hob shift is available for mass production of high grade gears.

Maximum diameter 10" Face width 8" 7DP

Write for
full details



DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14

Tel: WESTERN 8077 (8 lines) Telex: 23182 Grams: ACCURATOOL LONDON TELEX

MAXIPILOT

*For accurate,
high-output
copy turning*

DRUMMOND Maxi pilot at
the Austin Motor Co. Ltd.

This Maxipilot turning Austin Seven crankshaft primary gears demonstrates the application of this modern hydraulic multi-cycling copying lathe to accurate mass production work. It is a robust machine designed to exploit to the maximum the cutting possibilities of carbide tools. Available with either 20" or 32" between centres and max. swing 16" over the bed, 9½" over the cross slide.

DRUMMOND BROS. LTD.

GUILDFORD · ENGLAND

Member of the Asquith Machine Tool Corporation


Sales and Service for the British Isles

DRUMMOND - ASQUITH LIMITED

Member of the Asquith Machine Tool Corporation

KING EDWARD HOUSE, NEW ST., BIRMINGHAM Phone Midland 3431, Also at LONDON Phone: Trafalgar 7224 & GLASGOW Phone: Central 0922

D 390



"Done already, Dick?"


"Yes . . . wiring doesn't take long with Kopex, you know. Ever seen it? Look. It's pliable. Just cut it, bend it and fix it. Marvellous."

Kopex Pliable Electrical Conduit. A significant advance in electrical wiring installations. Easily bent by hand, remains rigid after bending and can be shaped to any radius without distorting the bore. P.V.C. covered for protection against oil, corrosion and suds. Ideal for wiring machine tools and special purpose machinery in factories and chemical plants, etc.

Kopex couplings are made in a variety of metals, and can be used with any standard electrical fittings, to make a rigid, permanent joint. Full technical information and prices on request.

KOPEX

P.V.C. covered **PLIABLE ELECTRICAL CONDUIT**
(also available without P.V.C. covering)



UNI-TUBES LIMITED

Head Office: 197 Knightsbridge, London, S.W.7

Tel: KNightsbridge 7811 5

Works: Alpha Street, Slough, Bucks.

Tel: SLough 25476 8

A member of **SMITHS** Group of Companies

USASPEAD

Super freecutting bright steel

Produced specifically for CAPSTANS and AUTOS

BS 970 1955. EN.1A

The engineering trade has long recognised the superior quality of this freecutting steel, which has acquired a wide reputation for ease of machining, high cutting speeds, long tool life and the ability to produce components of excellent finish and accuracy.

Usaspead super freecutting bright steel is closely controlled for chemical composition and mechanical properties, and responds readily to normal case hardening treatment.

A complete range of EN specifications is available.



A COMPLETE RANGE OF
EN SPECIFICATIONS
IS AVAILABLE

**MACREADY'S
METAL COMPANY
LIMITED,**

USASPEAD CORNER, PENTONVILLE
ROAD, LONDON, N.1.

Phone: TERminus 7060 and 7030 (30 lines)

Grams: Usaspead, London, Telex.

Telex No. 22788

WERNER

MILLING MACHINES



-increase output on small and medium batch sizes

FRITZ WERNER Punched Tape Controlled Milling Machines are standard machines with special electrical equipment for tape control which does not prevent manual operation.

A standard teleprinter tape determines spindle direction and braking; variable feed rates including rapid traverse; direction and length of table movements. The standard feature of automatic hydraulic clamping of stationary slides ensures rigidity. Automatic dividing attachments, circular tables and clamping fixtures can be included in the programme which can contain an infinite number of stages.




for further particulars write or telephone **TODAY**

WELSH HARP, EDGWARE RD., LONDON, N.W.2
TEL: GLADSTONE 0033

ALSO AT BIRMINGHAM • TEL: SPRINGFIELD 1134/5 • STOCKPORT • TEL: STOCKPORT 5421 • GLASGOW • TEL: MERRYLEE 2823

See a Demonstration
at our
London Showrooms
EXHIBITION
7-22 November

Norgren MICRO-FOG BEARING LUBRICATION



ECONOMIES YOU GET WITH NORGREN

Automatic and continuous lubrication. Hand oiling eliminated. Lubricant consumption greatly reduced. Uneven bearing wear eliminated. Helps keep work area cleaner.

A PROVED COST SAVER

A typical example of how Norgren MICRO-FOG Lubrication has lowered bearing temperatures as much as 50°F. and reduced oil consumption by 66%. A Norgren MICRO-FOG Lubricator creates a fog of extremely fine particles of oil that can be distributed through low pressure air lines to satisfy all lubrication needs on the machine. MICRO-FOG eliminates sumps, pumps, oil filters and high pressure piping, provides a big cut in equipment requirements, needs fewer oil seals and reduces costly maintenance and downtime.

Full details from

C. A. NORGREN LTD.

SHIPSTON-ON-STOUR, WARWICKSHIRE

Telephone: Shipston-on-Stour 676 (3 lines)

M-W 139



MULTIPLE DRILL HEADS

★ **COMPACT IN DESIGN**
★ **FIXED OR ADJUSTABLE CENTRE DISTANCES**

Hey Multiple Spindle Drill Heads convert Standard Drilling and Boring Machines to High Production Machines permitting drilling of all holes in a component simultaneously, with production rates equal to those obtainable on expensive special purpose machines.

Compact design reduces to a minimum, distance from drill head to machine spindle, whilst careful selection of material ensures an extremely efficient light weight head.

Heads are available with any number of spindles, covering a wide range of sizes

MAXIMUM PRODUCTION ON DRILLING, REAMING, TAPPING AND SPOT FACING OPERATIONS


HEY

ENGINEERING CO. LTD.
COVENTRY

PHONE: COVENTRY 88641

NRP 1596

We also manufacture Rotary Cam and Profile Milling Machines, Short Thread Milling Machines, Gear Tooth Rounding Machines, Tapping Machines, End Facing and Centring Machines, Special Machine Tools for High Production.



BASIC SECTION A-A
SECTION B-B FOR PT NR. 8/30

**WHEN
YOU WANT
THIS...
USE MOLLART**


Mollart will design your machines and production equipment, from simple tools to fully automatic plant for the light and medium engineering fields.

for further details, write today
THE MOLLART ENGINEERING CO. LTD.



KINGSTON - BY - PASS
SURBITON · SURREY · ENGLAND
Telephone: Elmbridge 0033 (5 lines)
Telegrams: Precision, Surbiton.

The floor-to-floor time for
milling the three faces is
6 MINUTES




The fastest means of milling light alloys

TABLE CANTS TO
THE VERTICAL ON
BOTH LEFT AND
RIGHT-HAND SIDES



Wadkin Articulated Arm Router, L.C.6, machining aluminium selector bodies for 5½" diameter pneumatic tube system. Photographs by courtesy of the Lamson Engineering Co. Ltd., London, N.W.10.



Wadkin type L.C.6, with table canted 10° to the right to present an inclined top face.


The Lamson Engineering Co. Ltd. appreciate the time-saving cost-cutting advantages of a machine specially designed for the rapid, precision milling of light alloys. That's why they have recently installed a Wadkin Articulated Arm Router, type L.C.6. This is a relatively inexpensive, medium capacity machine with cutting speeds up to 18,000 r.p.m., power rise and fall to the head, integral base plate, and a unique rising and falling canting table. Full details of the type L.C.6, and the heavy duty machine, type L.C., are given in Leaflet 945 available on request.

Wadkin Ltd., Green Lane Works, Leicester. Tel. 68151
London Office: 62 Brook Street, W.1. Tel. MAYfair 7048


Wadkin



ADAPTOR PLATES



CHUCK BLOCKS



MAGNETIC FIXTURES






ADDITIONAL
TOP PLATES

*** the complete
permanent magnet
accessory range**



the first name in magnetic tools
ask the experts for advice on your holding problem



SMALL TOOLMAKERS CHUCK
MOUNTED ON SWIVELLING BRACKET

Made by James Neill & Co. (Sheffield) Ltd—the originators of this equipment. Supplies through your usual 'Eclipse' Distributor

RENOLD



Spider Type Flexible Couplings —
range of 6 couplings up to 20 h.p.



Disc Type Flexible Couplings —
range of 16 couplings up to 600 h.p.



Chain Couplings —
range of 11 couplings up to 1,500 h.p.

Power transmission accessories


When it's a question of coupling one shaft to another . . .
RENOLD couplings are the answer !

RENOLD SPRAG CLUTCHES

For Over-running, Indexing and Backstopping

The Renold Sprag Clutch has many uses in all types of machinery and is ideal for the replacement of noisy ratchet-and-pawl mechanisms. It will give completely positive indexing with speed, accuracy and to unlimited graduations, is capable of high speed free-wheeling, and will remain free from measurable backlash throughout its life.

Write to Renold Chains Limited, Sprag Clutch Unit, 50 Cathedral Road, Cardiff, for Catalogues giving details of our range of clutches. Renold Chains Limited are licensed to manufacture Sprag & Reversible Locking Clutches by Formsprag Co. U.S.A.



THE NEW

RENOLD

R L CLUTCH

REVERSIBLE LOCKING


for

Position Control

Reversible Backstopping

Single Revolution Control

Torque Feed-Back Elimination




RENOLD CHAINS LIMITED MANCHESTER



When replying to advertisements please mention The Production Engineer

How good is a cutting fluid?



That's a very pertinent question to ask right at the start. Advisedly so, for we hold strong views about the part cutting fluids can and do play in the machining of metals. For far too many years, it has been pre-supposed that as long as you flooded the tool and workpiece with a fluid of some kind, things were bound to happen! Just what fluid seemed rather unimportant and one might be considered a niggler if one held a more rigid viewpoint. But have the bad old days really gone for good—the good of metal cutting that is? All too often, a tooling set-up gets every

kind of intelligent consideration until it comes to the question of coolant. The nearest drum or central bulk supply may be alright but could be just the opposite. A cutting fluid has a major responsibility in the province of machining and forming metals and it is our fondest tenet that until you have the right oil on tap, you are missing the sort of production savings that Fletcher Miller users secure. After 45 years, we have a lot of accumulated know-how (sorry about that word) and just the right cutting fluid for any metal production job. Call in the experts.

choose

FLETCHER MILLER

cutting fluids


FLETCHER MILLER LTD., HYDE, CHESHIRE

Telephone: HYDE 3471 (5 lines) Telegrams: EMULSION, HYDE

CF 138


CROWTHORN

**HEAVY
DUTY
LATHES**



The illustrations show a Crowthorn 18 in. Centre x 27 ft 9 in. Cap Bed Lathe admitting 20 ft. 6 in. between centres and, next a view of the quick power traverse mechanism.

The lathe is typical of Crowthorn Heavy Duty Lathe design.



Some notable features of the lathe

1. Special heavy duty tailstock with built-in Timken roller bearing assembly.
2. Bed casting of very heavy section, for rigidity and accuracy.
3. Quick power traverse to carriage by means of flange mounted motor and cable reel.
4. Heavy duty steadies with needle roller bearings.
5. Heavy duty grinding attachment available for mounting on cross slide in place of toolpost.
6. Taper turning attachment.
7. Micrometer dead stop.

CROWTHORN ENGINEERING COMPANY LIMITED

Makers of High Class Machine Tools for over half a century

REDDISH

STOCKPORT


ENGLAND

Phone: STOCKPORT 7271-2-3

Grams: CROWTOOL, REDDISH


A fast
automatic
-cycle miller

with **more weight**
more stamina
more power



Balanced feed control
from centrally placed
hydraulic cylinder to
reduce table-slide wear.

Emergency
table return
lever.



TWO HANDED START FOR SAFETY
Interlock lever must be lifted
before start cycle button can
be operated.

A & S

MODEL

1

HORIZONTAL MILLER

Air Hydraulic Automatic Cycle

No comparable miller has the weight and the power of the air-hydraulic A & S Model 1. 1,400 lb. weight, 2 h.p. strength and three bearings to spindle give this superb machine the speed, brawn and stamina no other hydraulic miller can touch. By air-hydraulic table drive (powered by the shop air supply), greater cutter life, immaculate finish and faster automatic cycles are achieved. Two air cylinders exert balanced thrust on the table slides, eliminating side-thrust wear, and safeguarding the unfailing accuracy of the machine. With two-hand control and an emergency return lever, the A & S Model 1 is also the safest of all millers. Write for illustrated brochure on A & S Model 1 Range.

Other models in the No. 1 range

- A-LSL—Hand Feed
- A-G—Automatic Feed
- A-J—Automatic Cycle

Still built up to top standard-AND top value!

ADCOCK & SHIPLEY LTD.

P.O. Box 22, Ash Street, Leicester.
Telephone: Leicester 24154-5-6 Grams & Cables: Adcock Leicester


**THIS MACHINE DOES THE WORK OF 4
TAKES UP THE SPACE OF 1**

- PUNCHING
- SECTION CROPPING
- PLATE SLITTING
- NOTCHING

**THE DE BERGUE 4 IN 1
MULTI-PURPOSE MACHINE**

Send for Brochure (W)

Made in several sizes, these, robust machines with recent improvements in design are an invaluable asset to constructors in STEEL.




A new range of Guillotines of modern design will shortly be available. Full particulars on request.

DE BERGUE MACHINE TOOLS LIMITED

WEST GORTON, MANCHESTER, 12, ENGLAND

Telephone EAST 2771

**MARKS AND MARKING
AUTOMATICALLY OR BY HAND**




SPARCATRON

We are pleased to announce
we are now distributors
of "SPARCATRON"
range of machines
including the Mk.V
plus R.L.G. electrics,
designed for the
manufacture of
large forging dies
for Forging
Industries.

Mk.IIIA

Tank size Length 25"
× Width 12" ×
Depth 7" Servo Head
can handle electrodes
weighing up to approx.
17 lbs. Mark IIIA is
ideal in Toolrooms for
the manufacture of
Press Tools, Die Cast-
ing and Forging Dies.




Mk.V

Rapid stock removal of up to 6
cubic inches per hour.

Work-tank Length 42" × Width
24½" × Depth 16" (allowing for
Die Block size Length 36" ×
Width 24" × Depth 14").

Servo Head handling electrodes
weighing up to alternatively
50 lbs. or 100 lbs.



Both these machines are mechanically and electrically safe for automatic operation;
complete isolation of the machine takes place on completion of the work.

Write or phone for details of the full Sparcatron Range

STEDALL MACHINE TOOL CO.

192-204, PENTONVILLE ROAD, LONDON, N.1

Telephone:—TERminus 3699 (25 lines)

Also at BRISTOL, MANCHESTER, LEICESTER & GLASGOW



This timer covers a wide range of industrial uses. It has a high degree of accuracy which meets all normal requirements. It is strongly made and reasonably priced. All its components are generously rated for long, trouble-free service.

The TY type timer is usually supplied in a steel case for wall mounting. There is also a steel cased form suitable for bench mounting but, if required it can be supplied without a cover, on a steel-front panel, for flush fitting to control panels and consoles.



LONDEX ELECTRONIC TIMERS TYPE TY

TIME RANGES

TY/1	4 to 120	secs., calibrated in 4	sec. divisions
TY/2	2 to 60	secs., " " 2	" "
TY/3	1 to 30	secs., " " 1	" "
TY/4	0.5 to 15	secs., " " 0.5	" "
TY/5	0.25 to 7.5	secs., " " 0.25	" "

The dial is calibrated in actual time. Connections are made to a shrouded terminal block on the front panel. A multi-tapped input transformer, a Thyatron, a timing condenser and resistance are the essential components. Two LONDEX relays are included to give a multiplicity of switching sequences. A voltage selector covers all supplies from 200 v. to 250 v. 50 cycles in 10 v. steps and a sequence selector gives a choice of three contact sequences.


Write for List P.E./190.

Manufacturers of Electrical automatic control apparatus.


LONDEX LTD

Anerley Works, London, S.E.20.

Telephone: SYDenham 3111



**It pays to
Standardise**



You can choose from Standard's Outstanding Range of PISTON RINGS & ASSEMBLIES for any type of engine . . . steam, petrol or diesel . . . also for compressor and hydraulic use.


THE STANDARD PISTON RING & ENGINEERING CO. LTD.
Premier Works • Don Road • Sheffield 9 • England
Telephone Sheffield 42076 (3 lines)
Telegrams: Ocean Sheffield 9

Morrisflex

FOR ALL GRINDING AND POLISHING SUPPLIES

FLEXIBLE SHAFT EQUIPMENT


and Remote Control Drives. Light, Medium and Heavy Duty for all trades



Model M.100
1 h.p.
2,800 r.p.m.




The New Morrisflex '300',
3,000, 9,000, 15,000 r.p.m.




Model M.137
1 h.p., 1,100,
2,800, 6,000
r.p.m.




M.A.605
'N' Type
Handpiece



M.B. 136/2
D/E Grinder
Handpiece



Model M.120, 2 h.p.
1,800, 2,800, 4,600,
r.p.m.



Model M.121,
2 h.p., 1,300,
2,800, 4,600
r.p.m.

B. O. MORRIS LTD, Morrisflex Works, COVENTRY
London Birmingham Manchester Glasgow
Leeds Bristol Whitley Bay Sydney, Australia

Turn
the
awkward
nut
easily



Leytool Universally Jointed SOCKET SPANNERS

Even when used at extreme angles the Leytool Universally Jointed Socket Spanner provides a firm and positive grip — essential to speed and ease of installation and servicing work, particularly because they operate in positions completely inaccessible to ordinary spanners. Made in sizes to fit every standard nut and bolt.

from **30/6**

Write for full details

Send for catalogue


of **Leytool** QUALITY HAND TOOLS

LEYTONSTONE JIG & TOOL CO. LTD. LEYTOOL WORKS, CROWHURST RD., HOLLINGBURY
Also at LEYTON, LONDON LEYtonstone 5022/3/4 ESTATE Nr. BRIGHTON, SUSSEX. Phone: BRIGHTON 57011



H.F. Induction Heating


1kW, 3kW, 7kW, 15kW Generators



Write or phone for leaflet HT/20/59.

FOR HIGH SPEED HARDENING, BRAZING & SOLDERING, ANNEALING & MELTING, GENERAL HEAT TREATMENT

- These equipments all have a high kVa output circuit.
- The variable power adjustment allows the exact heating pattern to be obtained.
- Push button control ensures that the same heating cycle can be repeated with consistent accuracy and unskilled operators can be used with complete confidence.
- Specially designed valves of our own manufacture are used and a liberal safety rating on all components provides long life and the minimum of maintenance during continuous production.
- Complete working installations can be supplied.
- Immediately available from stock.
- Free sample testing and advisory service.
- Technical representatives in London, Birmingham, Manchester and Glasgow.



Standard Telephones and Cables Limited

INDUSTRIAL SUPPLIES DIVISION
STANELCO PROCESS HEATING : FOOTSCRAY : SIDCUP : KENT
Telephone : FOOTscray 3333



Photograph by courtesy of Messrs. A. V. Roe & Co. Ltd.

In the short run, too

It is not only in the long run that Araldite proves so economical. For short runs, calling for tools which can be made quickly and cheaply, Araldite epoxy resins offer many advantages. These include: high strength and dimensional stability; resistance to wear and freedom from deterioration; excellent adhesion to many materials, facilitating bonding and the use of fillers or metal inserts; ease of manufacture from moulds of many materials; ease of modification in the event of change of design; suitability for making tools of any size. For the past ten years, Messrs. A. V. Roe & Co. Ltd. have used Araldite to manufacture large press tools for aircraft production. The photograph shows a freight door-frame measuring 84" x 60" x 4" for the new Avro 748. It is formed in 14 s.w.g. light alloy by an Araldite-faced double action draw tool, which has already produced over 100 pressings.

May we send you our booklet 'Araldite Resins for Tooling'?

Araldite epoxy resins are used
for producing patterns, models, jigs and tools
for casting high grade electrical insulation
for impregnating, potting and sealing electrical windings and components
for producing glass fibre laminates
as fillers for sheet metal work
as protective coatings for metal, wood and ceramic surfaces
for bonding metals, ceramics, etc.

Araldite

EPOXY RESINS

Araldite is a registered trade mark

CIBA (A.R.L.) LIMITED, DUXFORD, CAMBRIDGE. TELEPHONE: SAWSTON 2121

When replying to advertisements please mention The Production Engineer

AP645

The PROFILOSCOPE AND OPTIDRESS

For producing intricate forms on your Grinding Machine

Illustration shows the Optidress Wheelforming Attachment and Profiloscope with Slides in use on a Jones & Shipman 540 Grinding Machine producing an intricate template to a tolerance of .0005"



PRECISION GRINDING LTD

MILL GREEN ROAD · MITCHAM · SURREY Phone: MITCHAM 3014/6

NRP 5226A

NEW!

'Speetol'
REGD. TRADE MARK

QUICK-ACTION

JIG CLAMPS

**Combined
Screw & Cam
Action**

**Made in
Three Sizes**



(Patent
744064)

Completely Self-Contained &
Requiring No Extra Nuts, Bolts,
Studs, Springs etc. to be Fitted

The outstanding advantage of
"Speetol" Jig Clamps is that for the
first time there is now available an
entirely self-contained, quick-acting,
strap-clamp, specially designed for
incorporation as a single unit into
jigs and fixtures.

This range is backed by the
well-known "Speetog"
Template Service to
Drawing Offices.

**LITERATURE
and
TRACING
TEMPLATES
available
on request**

Speed Tools Ltd

VEREKER HOUSE, GRESSE ST., LONDON W1. Museum 1039/1099.

LOCTITE[®]

TRADE MARK


SEALANT

The Drop that Holds



This remarkable liquid plastic now widely used in every industry penetrates between closely fitting metal parts and hardens automatically inside the joint to give a vibration-proof lock and leak-proof seal. LOCTITE treated parts NEVER WORK LOOSE, yet can be removed with ordinary tools.


Min. of Aviation and A.R.B. approved



LOCTITE Sealant LOCKS THREADS

Loctite Sealant will lock nuts, set screws, studs, adjustment screws, etc. It makes them self-locking and dispenses with lock nuts, lock washers and other locking devices. Threads can be pre-treated in quantities, as Loctite Sealant does not harden while exposed to air.



Loctite Sealant locks bolts on giant earthmoving equipment permanently against vibration, yet bolts can be removed with ordinary tools!



LOCTITE Sealant RETAINS BEARINGS

Loctite Sealant restores the fit to worn housings and shafts. Holds bearings, gears, pulleys, sleeves, oil seals without a press fit. Eliminates re-boring, sleeving, shims and weld metal build-up. Loctite Sealant automatically fills clearance, prevents slippage.


Loctite Sealant is used on assembly of bearing in lieu of press fit.



LOCTITE Sealant SEALS JOINTS

Loctite Sealant seals against high pressure liquids and gases, completely filling the joint with tough plastic, resistant to heat, cold, water, oils, fuels and most chemicals. Replaces solder, requires no heat or fluxes.

Loctite Sealant seals hydraulic and fuel lines permanently leak-proof. Joints cannot work loose yet can be dismantled for servicing.



We will be pleased to send you the new illustrated LOCTITE Sealant Brochure giving full details and specifications. Write to Mr. J. A. Jenkins.

Sole Distributors:

LOCTITE

TRADE MARK

SEALANT

THE LIQUID LOCK FOR METAL PARTS

"LOCTITE" is the trade mark of the American Sealants Company U.S.A.

DOUGLAS KANE (SEALANTS) LIMITED, 243 UPPER STREET, LONDON, N.1 Tel: CANonbury 8646

AP 130

When replying to advertisements please mention The Production Engineer

Save **88%** on tools!
 Save **96%** on bench time!
 with **CROSLAND**
 BLANK & PIERCE DIES

NO DOUBT ABOUT IT, Crosland dies cut costs as cleanly as materials for these important reasons. They blank and pierce in one operation. They are an amazingly cheap method of tooling steel, non-ferrous and non-metallic materials. They save up to 96% bench time compared with hand methods on short to medium non-repetitive runs. They are infinitely cheaper than orthodox tools. Their super-hard steel cutting edges are set in a densified laminated material of high tensile strength and give clean, even results. And they're cheap to maintain and modify.

These are facts - Prove them to your Profit!

Write for fully descriptive literature to:

William Crosland Ltd.

BREDBURY, NR. STOCKPORT Telephone: WOODLEY 2621/2

**Let us
be your
machine
shop!**



**Complete facilities plus
precision & service second to none**

- Capstan and centre lathe work
- Milling—all types
- Surface and universal grinding
- G-SIP jig boring
- Centreless grinding
- Copy turning
- Cridan screw cutting
- Thread milling

... as well as
shaping, honing,
drilling, tool-
making, etc.
to meet your
every need.
A.T.D. & A.R.B.
Approved

MARSDEN & SHIERS LTD.

Davis Road, Chessington, Surrey. Phone: Elmbridge 5333 (3 lines)

MARK YOUR PRODUCT CLEARLY with **Imperial** **STEEL MARKING STAMPS**

Made from specially selected high grade steel each Imperial marking stamp is fully tested before leaving the factory. Available as Hand Stamps (sets or loose), Combination Stamps (sets or loose), or to customer's own specification. Write for catalogue and price list.



marketed by



GORDON WEBB & CO. LTD.

(DEPT P.E.) AVENUE CHAMBERS, VERNON PLACE,
SOUTHAMPTON ROW, LONDON W.C.1 TELEPHONE: HOLBORN 9444


A subsidiary of Imperial Typewriter Co. Ltd.



A heavy duty single roll feed teamed with a combined decoiling and levelling machine, handling 20 in. wide coiled strip at a large automotive accessory manufacturing plant in the Niagara Peninsula, Canada.



The Humphris standard range of decoilers, levellers and strip feeds is well-known and extensively used. Perhaps not so well-known is the fact that Humphris can supply virtually any size and shape of strip feed, strip leveller and decoiling machine. Whether your coils are light or heavy, thick or thin, narrow or wide, Humphris can offer you the necessary handling and feeding equipment.



exponents of advanced mechanisation

HUMPHRIS & SONS LTD. - POOLE - DORSET

TELEPHONE: POOLE 1800

TELEGRAMS: HUMPSONS

HUMPHRIS

When replying to advertisements please mention The Production Engineer

MELBOURNE


THE SPECIALISTS IN THE REBUILDING OF TURRET-TYPE AUTOMATICS

Can now offer

THE SAME UNSURPASSED REBUILDING SERVICE
FOR SWISS-TYPE AUTOMATICS



BECHLER



TORNOS
PETERMANN




- Machines are rebuilt to original specification of accuracy and limits.
- All parts fitted are interchangeable with maker's spares.
- Rebuilding not only costs less than a new machine but can also be charged wholly as maintenance expenses ranking for full tax relief.
- We can loan a machine equivalent to the one taken out thereby assuring customer of his continuity of production.

MELBOURNE ENGINEERING Co. Ltd. MELBOURNE Nr. DERBY

(H. E. SLAWSON, M.B.E., M.I.P.E., Man. Dir.) Tel: MELBOURNE 232

B. & S.



B.S.A.

C.V.A.



INDEX



★ May we visit your works and quote for rebuilding your machine?

Metal sawing problems?

Cold sawing machines are our speciality whether for ferrous, non-ferrous or difficult metals and we have an extensive range of standard machines which cut quickly - and accurately.

We also build machines for special applications.


If you have a cold sawing problem our experience could probably provide the solution. May we help you?

RUSSELL

**METAL SAWING & SAW
SHARPENING MACHINES**

S. RUSSELL & SONS LTD. Bath Lane, Leicester

Backed by 45 years of specialised experience



Lighten your handling costs with new MONORAIL CABLE-WAY CONVEYORS

Many years' development work has produced the new MONORAIL Cable-way Conveyor—the lightest and lowest-priced conveyor of its type in Britain. The system consists of rugged, lightweight trolleys riding on an overhead T-rail and drawn by a smooth-running cable for the fast and efficient movement of production and components. Standardisation of components and robust construction ensures reliability and reduces costs. Take your handling problems off the floor with Cable-way conveyors!

Three load capacities 80, 160 and 250 lb ☐ No heavy structure required
Low initial cost ☐ Easy to install and re-arrange ☐ After years of service
 the cable is extremely easy to replace ☐ No sudden failures without warning.
For information about heavier link or chain conveyors, please send for literature.

A complete OVERHEAD system

MonoRail systems meet every overhead handling requirement from the smallest gravity drives to complete automated systems, and include underslung cranes for loads up to 10 tons and 'cable-way' conveyors for the smooth and efficient movement of components and materials.

IF YOU WANT TO GET A MOVE ON


Send for the man with the **MONORAIL** plan

BRITISH MONORAIL LIMITED · WAKEFIELD ROAD · BRIGHOUSE · YORKS · TELEPHONE BRIGHOUSE 2244
A Member of the Herbert Morris Group of Companies

TGA 8H10

When replying to advertisements please mention The Production Engineer


WANT BETTER SAWING AT LOWER COST?



BRITISH BUILT MODEL V.36
CONTOUR SAWING, FILING
AND POLISHING MACHINE.

DoALL

HORIZONTAL & VERTICAL BANDSAWING MACHINES



MODEL C69 MANUAL POWER SAW

We stock original American DoALL Saw Blades.

Demonstration machines are installed in our showrooms to carry out cutting tests on your own work-samples. Backed by our own accumulated experience and coupled with the knowledge and research laboratory tests of our American principals, we can supply machines to Bandsaw anything — faster, with a better finish and less material waste.

Ask for demonstration and further particulars.

Illustrated are two of the large range of DoALL Machines.

GEORGE H. ALEXANDER MACHINERY LTD.

82 - 84 COLESHILL STREET · BIRMINGHAM 4 · ENGLAND

Telephone : ASTon Cross 3264

Telegrams : "VIKING" BIRMINGHAM

Alexander

take a good used machine!

Selecting a good used machine to assist or replace existing plant is so simple . . . just look where there is the biggest choice, and that's in a pretty big spot like The FJE Machine Centre.

Have what you will . . . machine tools; presses; sheet metal machines; woodworking machines; plate working machines; press brakes; guillotines; punch and shears; rolling machines; tin box making plant.

Action: contact London or Birmingham with your essential needs; inspect at the FJE Machine Centre under the most ideal conditions. The Centre is on the main A1 road near Highbury Corner in North London, easily reached by rail or road; no parking troubles.

Choose a good used machine from Edwards—for cash, hire purchase or hire!

F.J. Edwards Ltd

Edwards House, 359-361 EUSTON ROAD, LONDON, N.W.1

'Phones: EUSon 5000 Telex: 24264

'Grams: Bescotools London NW1

Lansdowne House, 41 Water Street, Birmingham, 3

'Phones: CENtral 7608-8

'Grams: Bescotools Birmingham 3





ESC
files for me
every time!

Toolroom fitters recognise
the superior life and
quality of E.S.C. files

ESC **ENGLISH
STEEL**

TOOL CORPORATION LIMITED
OPENSHAW, MANCHESTER

Facts and
fingers favour

FACIT

One-hand
operation

speeds
calculating



FIVE fingers and a FACIT will give you all the figures you want, whenever you want them. No more tedious mental drudgery. No more checking and double checking. Get a FACIT and do your everyday costing and computing with undreamed-of speed and unerring accuracy!

BUSINESS

AUTOMATION
—at its best!



ON-THE-SPOT SERVICE

from B & A branches in principal towns

FOR FURTHER INFORMATION POST THIS COUPON TODAY

Please send me details of the following Business Automation Equipment

- ☐ Modern Duplicating Methods
- ☐ Systems Machines
- ☐ Visual Control Charts
- ☐ Photocopying Equipment
- ☐ Calculators
- ☐ Standard and Portable Typewriters
- ☐ Adding Machines
- ☐ Book-keeping Machines
- ☐ Mail-Room Equipment
- ☐ Addressing Machines
- ☐ Banda Supplies

Name

Position

Firm

Address


PE.FC.2

BLOCK & ANDERSON LTD

Head Office: Banda House, Cambridge Grove, Hammersmith, London, W.6.
Tel: Riverside 4121 (20 lines).



Looking In the
right direction



Ratcliffe

SPRINGS

F. S. RATCLIFFE (ROCHDALE) LTD.,

Crawford Spring Works, Norman Road, Rochdale

Phone: Rochdale 40415

'Grams: Recoil' Rochdale

Telex 63178

FOR

METAL PRESSINGS WELDING FABRICATION ENAMELLING ASSEMBLIES

CONTACT

Adams Bros & Burnley Ltd
ELMGROVE RD, HARROW, MIDD. HARROW 6411

a full range of rugged industrial compressors


The large Compressor illustrated is typical of our 'Comoblok' range of machines. This range covers capacities from 500—2,000 c.f.m. These machines are of the double-acting crosshead type, and are suitable for pressures up to 50 p.s.i.g. single stage, and 150 p.s.i.g. two stage. They are remarkable for their low power consumption and compact design. Send for Leaflet No. T29.

The machine alongside is one of our Oil-free Range. These are available in capacities from 100 to 2,000 c.f.m., and at all pressures up to 150 p.s.i.g. They are specifically designed to deliver uncontaminated air, and have many special features incorporated which make them unique in this field of Compressors. Send for Leaflet No. T31.

The two smaller machines shown illustrate our 'Uniblok' and 'Twinblok' Range, and cover capacities of from 50 to 400 c.f.m. at all pressures up to 120 p.s.i.g. These are of the single stage, single acting type, styled to give a neat appearance and are unrivalled for their low maintenance and space saving features. Send for Leaflet No. T19.

Tilghman's have a complete range of Vacuum Pumps to offer in displacements from 50—2,500 c.f.m., and are capable of drawing 28" Hg. on a 30" Hg. barometer.


Tilghman's undertake the design and manufacture of special purpose Air & Gas Compressors, Boosters, etc., and welcome an opportunity of quoting for complete installations.



Send for our
informative
and valuable leaflet
on "Selection,
Installation and
Maintenance of
Air Compressors"

TILGHMAN'S *Limited* **AIR POWER DIVISION**
BROADHEATH • ALTRINCHAM • CHESHIRE

TELEPHONE: ALTRINCHAM 4242 (5 LINES) TELEGRAMS: TILGHMANS ALTRINCHAM



**TAKING
BUILT-IN STEPS
TO SAFETY!**

ROCKWELL HELICAL CLAMPS

BRITISH PATENT

A range of popular sizes
to suit any T slot or
clamping height.

No loose parts to lose.

Each size adjustable for height.

Any quantity Ex-Stock.



Write Dept. C/C or phone for leaflet giving
prices, size and technical details.

ROCKWELL
MACHINE TOOL CO. LTD.

WELSH HARP, EDGWARE ROAD,
LONDON, N.W.2 Tel: GLADSTONE 0033

Also at: Birmingham-Telephone Springfield 1134/5
Stockport-Telephone Stockport 5241 Glasgow-Telephone Merrylee 2822
S.C.6.

VULCASCOT

LEVEL-MOUNTS

... INCORPORATING VULCASCOT
ANTI-VIBRATION RUBBER PADS
MAKE MACHINES MOBILE.

● Reduce Vibration and Wear
● Simplify Machine Installations
● Precision Levelling without Shims
● No Drilling of Floors
● Less Noise, Less Nervous Strain

** Write or phone for literature to:*

Golden Jubilee 1961

VULCASCOT (GT BRITAIN) LTD.
87-89 ABBEY RD. LONDON N.W.8.
TEL. MAldon. Votr 7374/5

SLIDEWAY GRINDING

**SPECIALISTS IN
MACHINE TOOL
REBUILDING**



**WITH THE BROCKHOUSE UNIT
GRINDING HEAD AND TRUING
DEVICE FOR HORIZONTAL AND
VERTICAL GRINDING.**

- ★ Easily adaptable on most standard machines.
- ★ Rapid and accurate.
- ★ Slideway Grinding Enquiries invited.

Write for descriptive folder to:

J. BROCKHOUSE & CO. LIMITED

Machine Tool Division

ELMS WORKS : PENN ROAD : WOLVERHAMPTON

Phone: Wolverhampton 23801

AT

SETTING



SPARK MACHINING PRO DUCE INTRICATE SH APES LIKE THIS-IN INT RACTABLE MATERIALS-E CONOMICALLY AND **FAST**

If you want to know more about the **GKN** spark machine write to our U.K. agents

M. C. LAYTON LIMITED, ABBEY WHARF, MOUNT PLEASANT, ALPERTON, WEMBLEY, MIDD
RUDKIN & RILEY LIMITED, CYPRUS ROAD, AYLESTONE, LEICESTER
ALFRED HERBERT LIMITED, P.O. BOX 18, RED LANE WORKS, COVENTRY

MANUFACTURED BY WELSH METAL INDUSTRIES LTD., CAERPHILLY, GLAMORGANSHIRE




OTTERMILL

Serving World Industry

OTTERMILL BUSBAR TRUNKING is known and respected throughout most of the engineering world. Easily, cheaply and quickly installed it gives you instantaneous plug-in power at two foot intervals.

Its Advantages?

Complete planning flexibility, giving the works engineer a chance to wield complete control over workshop and production line layout. He knows there will be electric power wherever he wants it without a moment's interruption in main power supplies.

Write for details:

OTTERMILL SWITCHGEAR LIMITED

SALES OFFICE: 166 VICTORIA STREET, LONDON, S.W.1
Telephone: 1 ABBey 5095/6 Grams: Busbar, Sowest

WORKS: OTTERY ST. MARY, DEVON

Telephone: Ottery St. Mary 500 Grams: Busbar, Ottery St. Mary

ENV

facilities
for

HEAT TREATMENT



The ENV heat treatment plant is one of the most modern and comprehensively equipped in the London area. Facilities include full metallurgical control, quenching press equipment and electrically controlled flame hardening machine. Enquiries for heat treatment of production quantities are invited.


E.N.V. ENGINEERING CO. LTD

HYTHE ROAD, WILLESDEN, N.W.10

TELEPHONE: LADbroke 3622

Simple Setting—High Production

with **MODERN** automatics




TYPE 904

CAPACITY

Round Bars. Dia. 1 1/2"
Hexagon Bars. A/F 0.71"
Square Bars. A/F 3/4"
Maximum Travel of Tailslide 2"
Maximum Travel of cross slide 1 1/2"

SPINDLE SPEEDS

Speed Range 810-2,500 r.p.m.
No. of Speeds 14



TYPE 907

CAPACITY

Round Bars. Dia. 1 1/4"
Hexagon Bars. A/F 1.01"
Square Bars. A/F 3/4"
Maximum Travel of Tailslide 2 1/2"
Maximum Travel of cross slide 1 1/2"

SPINDLE SPEEDS


Speed Range 280-1,900 r.p.m.
No. of Speeds 12



Modern Machine Tools Ltd


P.O. BOX No. 56 · GOSFORD STREET · COVENTRY
Telephone: COVENTRY 22132-6 Cables: 'MODERN' COVENTRY

SM/MMT 6340



**But no Condensation at
UNITED DAIRIES**

...because Colt created the right climate



Four Colt Inflow Units delivering warmed, fresh air into the Boiling Room at Wilts United Dairies Ltd, Melksham.

COLT

Dripping, clammy conditions... dense fogging... it could happen in the Boiling Room of any Dairy, when the tanks are steam sterilised. It does not happen at Wilts United Dairies Ltd in Melksham, because United Dairies took suitable action and called in Colt to design a ventilation system.

You will find Colt systems at work throughout British industry, creating conditions in which men can work contentedly and efficiently. Colt's practical experience of ventilation problems that arise in every branch of industry could prove useful to you. Ask your Secretary to write to the Information Officer for the free Manual of Colt Equipment and Service.

industrial ventilation

COLT VENTILATION LTD SURBITON SURREY TEL ELMBRIDGE 0161

When replying to advertisements please mention The Production Engineer

INDEX TO ADVERTISEMENTS


Please note that all advertisement pages are prefixed with the letter "A"

	Page		Page		Page
Adams Bros. & Burnley, Ltd.	A106	Fletcher Miller, Ltd.	A90	Pryor, Edward, & Sons, Ltd.	A92
Adcock & Shipley, Ltd.	A91	Forgings & Presswork, Ltd.	—	Pultra, Ltd.	—
Adrema, Ltd.	—	G.W.B. Furnaces, Ltd.	—	Radyne, Ltd.	A46
Aircraft-Marine Products (Great Britain), Ltd.	A39	Gas Council, The	—	Ratcliffe, F. S. (Rochdale), Ltd.	A106
Airmec, Ltd.	A31	Gear Grinding Co. Ltd.	—	Reavell & Co. Ltd.	—
Alexander, Geo. H., Machinery, Ltd.	A104	Goshorn, John, & Co. Ltd.	A22	Renault Machine Tools (U.K.), Ltd.	—
Allen, Edgar & Co. Ltd.	A2	Goulder, J., & Sons, Ltd.	A17	Renold Chains, Ltd.	A89
Allspeeds, Ltd.	A33	Hardinge Machine Tools, Ltd.	—	Rockwell Machine Tool Co. Ltd.	A85, A108
Arc Manufacturing Co. Ltd.	—	Harvey, G. A., & Co. (London), Ltd.	—	Rocol, Ltd.	A5
Archdale, James, & Co. Ltd.	A36	Heenan & Froude, Ltd.	—	Rowen-Arc	—
Asquith, William, Ltd.	—	Henderson & Keay, Ltd.	—	Rubery, Owen & Co. Ltd.	—
Associated Electrical Industries, Ltd.	—	Herbert, Alfred, Ltd.	—	Rosse Muir Publications, Ltd.	—
Atlas Copco (Great Britain), Ltd.	A18, A74	Hey Engineering Co. Ltd.	A86	<i>Inset between A16, A17</i>	—
Automotive Engineering, Ltd.	—	Hordern, Mason & Edwards, Ltd.	—	Russell, S., & Sons, Ltd.	A102
B.S.A. Small Tools, Ltd.	A69	Humphris & Sons, Ltd.	A101	Ryder, Thos., & Son, Ltd.	—
B.S.A. Tools Ltd.	—	Ilford, Ltd.	—	Selson Machine Tool Co. Ltd.	—
Barber & Colman, Ltd.	—	Industrial Diamond Information Bureau	A64	Sharples Centrifuges, Ltd.	—
Benton & Stone, Ltd.	A45	Ingersoll-Rand Co. Ltd.	—	Sheffield Twist Drill & Steel Co. Ltd.	—
Birmingham Aluminium Casting (1903) Co. Ltd.	—	Ingham, Robert, Clark & Co.	A52	Shell-Mex & B.P., Ltd.	A76, A77
Birmingham Tool & Gauge Co. Ltd.	—	International Computers and Tabulators, Ltd.	—	Shell Chemical Co. Ltd.	A11
Bishop Eaves & Sons, Ltd.	A43	Isopad, Ltd.	—	Siemens-Schuckert (G.B.), Ltd.	—
Bliss, E. W. (England), Ltd.	A55	Jacobs Manufacturing Co. Ltd., The	A49	Slip Group of Companies, The	—
Block & Anderson, Ltd.	A106	Johansson, C. E., Ltd.	A63	Smit, J. K., & Sons, Diamond Tools, Ltd.	—
Bound Brook Bearings, Ltd.	—	Jones, A. A., & Shipman, Ltd.	A26	Smart & Brown (Machine Tools), Ltd.	A10
Braby, Frederick, & Co. Ltd.	—	Kane, Douglas, Sealants, Ltd.	A99	Snow, & Co. Ltd.	—
Brauer, F., Ltd.	—	Kearney & Trecker—C.V.A., Ltd.	A80, A81	Solex (Gauges), Ltd.	—
Bridges, S. N. & Co. Ltd.	A32	Kearns, H. W., & Co. Ltd.	—	Sparatron (Manufacturing) Ltd.	A14
British Aero Components, Ltd.	—	Keelavite Hydraulics, Ltd.	—	Speed Tools, Ltd.	A98
British Industrial Engineering Co. (Staffs), Ltd.	A13	King, Geo. W., Ltd.	A21	Speedright Gauge & Tool Coventry	—
British MonoRail, Ltd.	A103	Kitchien & Wade, Ltd.	A66	Standard Piston Ring & Engineering Co. Ltd.	A94
Brookhirst Igranite, Ltd.	A20	Landis Lund, Ltd.	A35	Standard Telephones & Cables, Ltd.	A96
Brookhouse, J., & Co. Ltd.	A108	Lang, John, & Sons, Ltd.	—	Stedall Machine Tool Co.	A93
Broom & Wade, Ltd.	A34	Lapointe Machine Tool Co. Ltd., The	—	Stein Atkinson Vickers Hydraulics Ltd.	A57
Brown, David, Corpn. (Sales), Ltd., The	A71	Ley's Malleable Castings Co. Ltd.	—	Stephens Belting Co. Ltd.	A32
Bullows, Alfred, & Sons, Ltd.	A70	Leytonstone Jig & Tool Co. Ltd.	A96	Stone, J., & Co. (Deptford), Ltd.	A54
Burndept, Ltd.	—	Lincoln Electric Co. Ltd., The	A61	Streety Manufacturing Co. Ltd.	—
Burton Griffiths & Co. Ltd.	A69	Lloyd, Richard, Ltd.	—	Sunbeam Anti-Corrosives, Ltd.	—
Butler Machine Tool Co. Ltd., The	—	Lockheed Hydraulic Brake Co. Ltd.	A68	Swift, Geo., & Sons, Ltd.	—
Canning, W., & Co. Ltd.	A3	Londex, Ltd.	A94	Sykes Machine Tool Co. Ltd., The	A62
Carborundum Co. Ltd., The	—	Macready's Metal Co. Ltd.	A84	Sykes, W. E., Ltd.	—
Castrol Industrial Ltd.	—	Markland Scowcroft, Ltd.	A15	Talbot Tool Co. Ltd., The	—
Carrier Engineering Co. Ltd.	A73	Marsden & Shiers, Ltd.	A100	<i>Inside Back Cover</i>	—
Churchill, Charles & Co. Ltd.	A1	Martonnair, Ltd.	A6	Teddington Industrial Equipment Ltd.	—
Churchill Machine Tool Co. Ltd.	—	Maxam Power, Ltd.	—	Terry, Herbert, & Sons, Ltd.	—
Ciba (A.R.L.), Ltd.	A97	Melbourne Engineering Co. Ltd.	A102	Thompson, John, Motor Pressings, Ltd.	—
Cincinnati Milling Machines, Ltd.	A8, A9	Metalock (Britain), Ltd.	A56	Tilghman's, Ltd.	A107
Colt Ventilation, Ltd.	A111	Midland Silicones, Ltd.	A30	Town, Frederick, & Sons, Ltd.	—
Control	<i>Inset between A16, A17</i>	Mobil Oil Co. Ltd.	A50	Tufnol, Ltd.	—
Cooper & Co. (Birmingham), Ltd.	—	Modern Machine Tools, Ltd.	A110	Tyer & Co. Ltd.	A22
Concentric (Engineering), Ltd.	—	Mollart Engineering Co. Ltd.	A87	Uni-Tubes, Ltd.	A81
Consultair Ltd.	A40, A41	Monks & Crane, Ltd.	A47	United Dominions Trust (Commercial), Ltd.	A51
Coventry Climax Engines, Ltd.	—	Morris, B. O., Ltd.	A95	Universal Tools, Ltd.	—
<i>Outside Back Cover</i>	—	"Morse Chain Division" Borg-Warner, Ltd.	—	Vacu-Blast, Ltd.	—
Cowlshaw, Walker & Co. Ltd.	A59	Motor Gear & Engineering Co. Ltd.	—	Van Moppes, L. M., & Sons (Diamond Tools), Ltd.	—
Crawford Collets, Ltd.	A58	Mullard Equipment, Ltd.	A7, A28	Vaughan, Associates, Ltd.	A12
Crompton Parkinson, Ltd. (Instruments)	—	National Industrial Fuel Efficiency Service	—	Vaughan, Edgar, & Co. Ltd.	A37
Crosland, William, Ltd.	A100	Neill, James, & Co. (Sheffield), Ltd.	A88	Vickers-Armstrongs (Engineers), Ltd.	A108
Crowthorn Engineering Co. Ltd.	A90	Newall Group Sales, Ltd.	A53	Walcot (Great Britain), Ltd.	—
D.M.M. (Machinery), Ltd.	—	Norgren, C. A., Ltd.	A86	Ward, H. W., & Co. Ltd.	A79
Davis, Stuart, Ltd.	A23	Norwood Steel Equipment, Ltd.	—	Ward, Thos. W., Ltd.	—
Dawson Bros., Ltd.	—	Optical Measuring Tools, Ltd.	—	Wadkin, Ltd.	A88
De Bergue Machine Tools, Ltd.	A92	Ormerod Shapers, Ltd.	—	Warner Swasey Asquith, Ltd.	—
Dembo, B. W., & Sons, Ltd.	—	Osborn, Samuel, & Co. Ltd.	—	Weatherley Oilgear, Ltd.	A6
Denison Deri Engineers, Ltd.	A27	Ottermill Switchgear, Ltd.	A110	Webb, Gordon & Co. Ltd.	A100
Dowding & Doll, Ltd.	A82	Park Gate Iron & Steel Co. Ltd.	—	Webster & Bennett, Ltd.	A4
Drummond-Asquith, Ltd.	—	Parkinson, J., & Son (Shipley), Ltd.	A78	Welsh Metal Industries, Ltd.	A109
Drummond Bros., Ltd.	A83	Payne Products International, Ltd.	—	West, Allen, & Co. Ltd.	—
E.N.V. Engineering Co. Ltd.	A110	Peak Engineering Co. Ltd.	A67	Wickman, Ltd.	A48, A75
Edwards, F. J., Ltd.	A104	Pels, Henry, & Co. Ltd.	A60	Wild-Barfield Electric Furnaces, Ltd.	—
Eco Furnaces, Ltd.	—	Plastics & Resins, Ltd.	—	Wilkins & Mitchell, Ltd.	A24, A25
Electrical Development Association	—	Power Petroleum Co. Ltd.	A29	Woodhouse & Mitchell	A98
Elliott, B. (Machinery), Ltd.	—	Pratt Precision Hydraulics, Ltd.	A72	Wolverhampton Die Casting Co. Ltd.	A19
English Electric Co. Ltd., The	A65	Precision Grinding, Ltd.	A98	—	—
English Numbering Machines, Ltd.	A42	Press Equipment, Ltd.	—	—	—
English Steel Tool Corpn., Ltd.	A105	Protolite, Ltd.	A44	—	—
Exors of James Mills, Ltd.	A16	—	—	—	—
Firth, Thos., & Brown, John, Ltd.	—	—	—	—	—
Flame Hardeners, Ltd.	—	—	—	—	—

All communications regarding advertisements should be addressed to the Advertising Managers, T. G. Scott & Son, Ltd., 1 Clement's Inn, London, W.C.2. Telephone: HOLborn 4743. Printed by Maxwell, Love & Co. Ltd., 309-317 Borough High Street, London, S.E.1.

Page	
A92	
—	
A46	
A106	
—	
A89	
A108	
A5	
—	
6, A17	
A102	
—	
—	
—	
6, A77	
A11	
—	
—	
—	
A10	
—	
A14	
A98	
—	
A94	
A96	
A93	
A57	
A32	
A54	
—	
—	
A62	
—	
Cover	
—	
—	
—	
A107	
—	
A22	
A84	
A51	
—	
—	
—	
A12	
—	
A37	
A108	
A79	
—	
A88	
—	
A6	
A100	
A4	
A109	
—	
3, A75	
—	
4, A25	
A38	
A19	

press fit



or slip



Always use **Grip**


Manufacturers of the complete range of jig bushes and liners to B.S.S. 1098/1953, together with special purpose bushes for sheet metals, plastics and moulded jigs. Catalogues sent upon request.

TALBOT TOOL COMPANY LIMITED

GRIP WORKS • ROEDALE ROAD • BRIGHTON • SUSSEX
Telephone BRIGHTON 56833

Telegrams GRIFTTOOLCO BRIGHTON






TOP TOOLS IN ACTION . . . at the Doncaster factory of International Harvester. It's just a co-incidence that this picture records such a neat example of high power harmony . . . or is it? After all, who is better qualified to know the best in power and movement than International?



International
Harvester
move
Rolls Royce
engines
with



Coventry Climax **FORK LIFT TRUCKS**
COVENTRY CLIMAX ENGINES LIMITED (DEPT.P.E.) COVENTRY

